UNITED NATIONS EP



United Nations Environment Programme Distr. GENERAL



UNEP/OzL.Pro/ExCom/62/9 4 November 2010

**ORIGINAL: ENGLISH** 

EXECUTIVE COMMITTEE OF THE MULTILATERAL FUND FOR THE IMPLEMENTATION OF THE MONTREAL PROTOCOL Sixty-second Meeting Montreal, 29 November - 3 December 2010

REPORT ON IMPLEMENTATION OF APPROVED PROJECTS WITH SPECIFIC REPORTING REQUIREMENTS

#### Introduction

- 1. The Governments of Canada, France, Germany, and Japan as well as UNDP, UNIDO and the World Bank have submitted progress reports on the implementation of the following projects, where specific reporting requirements are contained in the agreements, for consideration by the Executive Committee at its 62<sup>nd</sup> Meeting:
  - (a) <u>China</u>: Refrigeration servicing sector CFC phase-out plan: 2009 verification audit (UNIDO)
  - (b) <u>Colombia</u>: National phase-out plan for Annex A (Group I and II) substances (2009-2010 progress report) (UNDP);
  - (c) <u>Global</u>: Methyl formate as blowing agent in the manufacture of polyurethane systems. An assessment for the application in MLF projects (UNDP)
  - (d) Oman: Terminal phase-out management plan: audit report (UNIDO)

#### **Chillers Projects**

- (e) <u>Brazil</u>: progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)
- (f) <u>Colombia</u>: progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)
- (g) <u>Cuba</u>: progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP and Canada)
- (h) <u>Syrian Arab Republic</u>: Progress report on the demonstration project on the replacement of CFC centrifugal chillers (UNIDO)
- (i) <u>Global</u>: progress report on the global chiller replacement project (China, India, Indonesia, Jordan, Malaysia, Philippines, and Tunisia) (World Bank)
- (j) <u>Region Africa</u>: progress report on strategic demonstration project for accelerated conversion of CFC chillers in 6 African countries (Cameroon, Egypt, Namibia, Nigeria, Senegal and Sudan) (UNIDO, France, Germany, and Japan)
- (k) <u>Region Europe</u>: progress report on demonstration project on the replacement of CFC centrifugal chillers (Croatia, the former Yugoslav Republic of Macedonia, Montenegro, Romania, and Serbia) (UNIDO)
- (l) Region Latin America and the Caribbean: demonstration project for integrated management of the centrifugal chiller sub-sector in the Caribbean, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)
- 2. The Secretariat reviewed the progress reports on the above listed projects in light of the original project proposals, ODS data reported by the Governments concerned under Article 7 of the Montreal Protocol, and relevant decisions taken by the Executive Committee and the Meeting of the Parties.

#### China: Refrigeration servicing sector CFC phase-out plan: 2009 verification audit (UNIDO)

3. On behalf of the Government of China UNIDO, as the lead implementing agency for the refrigeration servicing sector CFC phase-out plan, has submitted to the 62<sup>nd</sup> Meeting of the Executive Committee an independent verification report regarding the CFC-12 consumption in the refrigeration servicing sector in China, covering the year 2009. Under this sector plan, the CFC-12 consumption of China is the basis for the agreed maximum allowable consumption for the sector.

#### Background

4. The refrigeration servicing sector CFC phase-out plan for China was approved at the 44<sup>th</sup> Meeting of the Executive Committee, with UNIDO as lead agency and Japan as cooperating bilateral agency. The total funds approved in principle for the plan amounted to US \$7,885,000 plus agency support costs of US \$836,130. The agreement was amended at the 45<sup>th</sup> Meeting to also include UNEP as a cooperating implementing agency. The refrigeration servicing sector CFC phase-out plan is aimed at supporting China in meeting its Montreal Protocol obligations, including the complete phase-out of the controlled use of CFCs prior to 2010. The last tranche for this sector plan has been approved at the 59<sup>th</sup> Meeting of the Executive Committee.

#### Progress report

- 5. The agreement between China and the Executive Committee specifies a maximum allowable CFC-12 consumption for the refrigeration servicing sector. This consumption is determined by verifying the Article 7 data, deducting from it verified consumption data from various sector plans where CFC-12 is being phased out in parallel. China has in previous years established a national stockpile, meant to supply CFC-12 to the refrigeration serving and MDI sectors beyond the accelerated closure of the production sector in 2007.
- 6. The agreement between China and the Executive Committee requires that the Article 7 consumption of CFC-12 in China be independently verified, while consumption in the refrigeration servicing sector is to be confirmed through China's own monitoring and auditing activities. The verification of the 2009 consumption of CFC-12 was in itself historically based on two verifications: the results of the World Bank's production sector verification, and the results of the verification of imports and exports, both of which were carried out under this sector plan. The import of CFCs to China in 2009 was zero. With production of 498.56 ODP tonnes and export of 100 ODP tonnes, the consumption of CFC-12 was 398.56 ODP tonnes. This consumption is 7.4 ODP tonnes below the limit of 406.0 ODP tonnes specified in the agreement between China and the Executive Committee for the year 2009.

#### Secretariat's comments

7. The Secretariat has advised UNIDO regarding the decision taken at the  $59^{th}$  Meeting of the Executive Committee to request UNIDO to provide annually, by calendar year, reports on the activities undertaken until the financial closure of the phase-out plan. UNIDO subsequently submitted an implementation report to the  $62^{nd}$  Meeting; however, at that time the documentation for the meeting had already been completed. The annual implementation report will be provided for consideration at the next meeting of the Executive Committee.

#### Secretariat's recommendation

- 8. The Secretariat recommends that the Executive Committee:
  - (a) Takes note of the verification report regarding the CFC consumption in the refrigeration servicing sector in China during the year 2009; and
  - (b) Takes note that the annual implementation report for the years 2009 and 2010 will be considered at the 63<sup>rd</sup> Meeting of the Executive Committee.

#### Colombia: National phase-out plan for Annex A (Group I and II) substances (UNDP)

9. The national CFC phase-out plan (NPP) was approved by the Executive Committee at its 41<sup>st</sup> Meeting. Under the NPP, the Government of Colombia committed to phasing out all CFCs and halons by 1 January 2010. The Executive Committee approved in principle US \$4.5 million for implementation of the NPP, and also the funding for two tranches at its 41<sup>st</sup> (US \$2,146,820) and 47<sup>th</sup> (US \$2,353,180) Meetings.

#### Progress report

- 10. A number of results have been achieved so far during the 2009-2010 work programme of the Colombia NPP, including: the certification of an additional 1,000 refrigeration servicing technicians, bringing the number of technicians certified since the beginning of the programme to over 4,500; the establishment of three refrigerant reclaiming centres; providing training equipment including ODS identifiers to 35 training centres; and organization of the annual seminar-workshop for the training institutes with the participation of 55 trainers. Nearly 10,000 records have been introduced into the Ozone Unit's servicing database. Technical assistance for the adequate disposal of halons has been provided to end-users in the telecommunications, banking, oil and energy sectors. Furthermore, several resolutions were drafted to amend the procedure established by the Minister of Environment to allow the import of refrigeration and air conditioning appliances; to establish environmental measures for the use of ODS; and to ban the use of hydrocarbon-based air conditioning systems in vehicles with more than 5 passengers.
- 11. The total approved funding of US \$4,500,000 has been disbursed.

#### Independent verification

12. In 2010, an audit of the 2009 consumption verification report was undertaken by an independent auditor who concluded that "2009 data on imports of ODS reported by the OTU (Ozone Technical Unit) are totally reliable; and that Colombia is accomplishing its targets on internal consumption as agreed." The auditor also recommended that "the control system for imports and exports and the institutional strengthening is widely consolidated. The main recommendation is to persevere on this path."

#### 2011 work programme

13. The Colombia NPP's work programme will focus on strengthening the refrigeration management plan by certifying 600 refrigeration technicians, strengthening the recovery/recycling network through the establishment of five refrigerant reclamation centres, and promoting the use of hydrocarbon-based refrigerants. It will also provide technical assistance and support to major ODS end-users in all sectors. Finally, the work programme will strengthen the national legal framework and the control of ODS trade, and strengthen the implementation and monitoring units.

#### Secretariat's comments

- 14. The Secretariat noted the comprehensive progress report on the implementation of the Colombia NPP, together with the supporting documents, including the verification report on national ODS consumption in Colombia. The 2009 CFC consumption of 110.6 ODP tonnes reported by the Government of Colombia under Article 7 of the Montreal Protocol is already 220.6 ODP tonnes below the allowable level of CFC consumption for that year of 331.2 ODP tonnes.
- 15. Upon a request for additional information on the status of implementation of the MDI Phase-out project, UNDP indicated that production of non-CFC MDIs is expected during the first quarter of 2011. The product development process, including registration, has been completed for salbutamol (production will commence once the manufacturing line is operational). The other four formulations are in different stages of development.
- 16. The Secretariat sought clarification from UNDP on whether the Government of Colombia will be able to achieve the complete phase-out of CFCs by the end of 2010 and sustain that level of consumption through the activities proposed in the final work programme. UNDP reported that, since 1 January 2010, CFC imports into Colombia were zero. Several actions are under implementation to reduce the use of CFC-11 in chillers and refrigeration equipment in operation. The established structure of national certification and training of technicians has allowed for mainstreaming and expansion of good servicing practices in refrigeration. At the regulatory level, the Government has established measures to ensure the sustainability of CFC phase out, including bans on imports of all CFCs and CFC-based equipment and on national manufacturing of products/equipment using CFCs.

#### Secretariat's recommendation

17. The Executive Committee may wish to take note of the progress report on the implementation of the national CFC phase-out plan (NPP) for Colombia, covering the 2009-2010 period, and approve the annual implementation programme for 2011.

### Global: Methyl formate as blowing agent in the manufacture of polyurethane systems. An assessment for the application in MLF projects (UNDP)

#### **Background**

- 18. UNDP has submitted to the 62<sup>nd</sup> Meeting a technical report: "Methyl formate as blowing agent in the manufacture of polyurethane systems; an assessment for the application in MLF projects". The complete technical review is attached to this document.
- 19. At its 56<sup>th</sup> Meeting, the Executive Committee approved two pilot project for validation of methyl formate as a blowing agent in the manufacture of polyurethane foam in Brazil, and in microcellular polyurethane foam applications in Mexico. It noted that the projects were consistent with decision 55/43(e) and that they had been designed to disseminate the results from the validation of methyl formate technology in rigid, integral skin polyurethane foam, and microcellular polyurethane foam applications globally, and on the understanding that the projects would be the final validation projects for methyl formate in the manufacture of rigid, integral skin polyurethane foams, and microcellular polyurethane foams (decisions 56/50 and 56/51).

#### **Executive summary**

- 20. UNDP formulated a number of pilot projects to investigate the safe use of methyl formate (ecomate® or MF) to replace HCFC-141b in polyurethane (PU) foams application. The use of MF-based systems has been evaluated at Purcom Quimica (Brazil) and Quimiuretanos Zadro (Mexico) with the objective of assessing its performance compared to HCFC-141b-based systems, and establishing the feasibility of its use in Multilateral Fund projects.
- 21. The technology using MF in PU foam is owned and marketed by Foam Supplies, Inc., (FSI) in the United States of America. While MF use is still small compared to HCFC-141b, it has been growing substantially in the last few years, from 40 tonnes in 2005 to 910 tonnes in 2010 (January to August).
- 22. At the time the project was approved by the Committee, Purcom was the only Article 5 licensee of the technology; for that reason, it was selected to implement the pilot project. Since Purcom does not market shoesole systems, this application has been separately assessed through Zadro. To avoid the perception that the funding provided by the Multilateral Fund would cause any preferential treatment, it was agreed from the outset with FSI and relevant licensees that they would grant non-exclusive (sub-) licenses to any interested party that applies for Fund assistance to phase out HCFCs.
- 23. The project identified 17 PU foam applications. The action plan was based on a thorough evaluation of previous work by FSI and its licensees, for incorporation into the assessment and the elimination of applications requiring direct injection (mostly continuous operations). For the purpose of the pilot projects, acceptability was defined as determining the safe use of the technology based on health, safety and environmental data; determining the applicability of the technology based on its processability; determining the applicability of the technology by measuring relevant physical properties before and after replacing HCFC-141b; and collecting complementary information and views from enterprises that have tested MF formulations in their production. The outcome of the assessment is summarized in the table below.

Application	Health, safety, environment	Processability	Physical properties	Assessment
Flexible and integral skin				
Hyper-soft molded	+	+	+	+
Hyper-soft blocks	+	+	+	+
Viscoelastic molded	+	+	+	+
Viscoelastic blocks	+	+	+	+
Steering wheels	+	+*	+	+
Structural (rigid)	+	+*	+	+
Semi-flexible	+	+	+	+
Shoesoles	+	+*	+	+
Rigid foams				
Residential appliances	+	-	=	-
Other appliances	+	+	+	+/-
Panels, transportation, reefers	+	+	+	+
Spray	+	+	+	+
Blocks	+	+*	+	+
Pipe-in-pipe	+	+	+	+
Buoyancies	+	+	+	+

<sup>\*</sup> Separate injection of MF recommended

<sup>+</sup> Acceptable, - unacceptable; +/- acceptable with conditions

- 24. Analysis of the outcome of the assessment led to the following conclusions:
  - (a) The use of MF as an alternative blowing agent to HCFC-141b in PU foam applications can be considered as an alternative in flexible/integral skin foam applications and in a number of rigid foam applications. For certain rigid foam applications mainly domestic appliances, the technology could not be recommended at this stage because the density required for this application cannot be reached by methyl formate at the current level of technology (i.e., further optimization of the technology is required), and for others the application of the technology should be analyzed on a case-by case-basis and could be subject to further optimization;
  - (b) To minimize safety risks for downstream users, such projects should preferably be implemented through their system suppliers as fully formulated systems;
  - (c) Project designers should ensure that: chemical compatibility is verified; minimum packed density is observed; health, safety and environmental recommendations are incorporated; and implications related to acidity are taken into account.
- 25. UNDP has developed generally applicable cost templates to calculate the incremental cost of conversion from HCFC-141b to MF-based foams. Capital costs and chemical costs can differ significantly from country to country and are also subject to economy of scale considerations.

#### Conclusion by the peer review

- 26. "The report and attachments are key parts of a comprehensive review of the suitability of MF for a range of applications as a replacement for HCFC-141b. The challenge is particularly severe as HCFC141b is used in a large number of A5 countries in almost all polyurethane foam applications. It must also be remembered that decision XIX/6 imposes tight and global deadlines that were rarely encountered by "emerging" blowing agents in the past. Many of the apparent shortfalls in MF's performance are very likely to be addressed by formulation optimisation but, in the present case, this optimisation process has not so far been led by the global polyurethane systems houses as was the case with earlier blowing agents".
- 27. The peer review highlights the following areas that require further data/attention:
  - (a) Information on experience and MF usage per application (sub-sector);
  - (b) Combustibility safety during foam processing need for concentration measurements and ventilation;
  - (c) Combustibility of the end product/foam in some cases;
  - (d) Data on spray foams and shoe soling elastomer applications;
  - (e) Further and longer-term dimensional stability test data, particularly for rigid insulating foams. As a temporary measure the density of foams which are normally near 32 kg/m³ could be increased by 2-3 kg/m³ to safeguard dimensional stability until more experience is gained; and
  - (f) Similarly, longer-term thermal conductivity testing using accelerated ageing methods such as the slicing method or ageing at 70°C

#### Secretariat's comments

- 28. The pilot projects for the validation of methyl formate approved by the Committee included workshops to disseminate the results of the projects. In this regard, a workshop was conducted in Brazil (23-24 March 2010) with the participation of 13 systems houses from six countries (Australia, Brazil, Chile, Colombia, Mexico, and the United States of America; 12 foam manufacturing enterprises from Brazil and Ecuador, representatives from six Article 5 countries (Argentina, Brazil, Chile, Mexico Paraguay and Venezuela (Bolivarian Republic of)) and representatives from UNDP, UNEP and UNIDO; two blowing agent wholesalers from Brazil and eight foam injection equipment manufacturers (Brazil and multinational). Dissemination of the results of the pilot projects has been conducted through the work being done as part of the preparation of HPMPs, including stakeholder meetings and visits to foams companies and systems houses. Dissemination through these channels has covered, among other countries: Argentina, Brazil, Chile, China, Dominican Republic, Egypt, Indonesia, Jamaica, Malaysia, Mexico, Nigeria, Trinidad & Tobago, and Uruguay. Interest and enquiries for further material have been received from companies in most of these countries. The Secretariat has also been informed that seven multinational systems houses have agreed to assess MF in their formulations.
- 29. The report on the assessment of MF has developed cost templates to calculate the capital cost of conversion from HCFC-141b to MF. However, consultations by the Secretariat with industry experts and some technology licensees that started in 2008 during preparation of the document on revised analysis of relevant cost considerations surrounding the financing of HCFC phase-out predominantly point to the fact that there is no retrofitting cost associated with the change to MF at enterprise level. On this issue, UNDP indicated that the template was based on discussions with the technology owner (FSI), and licensee companies (Australian Urethane Systems, Australia; Purcom, Brazil; Expanded, India; and Resichem, South Africa), that participated in the process optimization and evaluation of every single complaint that UNDP could identify. This process was required to avoid liability that could result from making superficial conclusions. UNDP had continued to collect market information that may assist fine-tuning the template, as well as other information in its assessment, to improve the quality of investment projects based on MF. Based on this information, UNDP concluded that acid-proofing needs to be part of an MF-based project.

#### Secretariat's recommendation

- 30. The Executive Committee may wish:
  - (a) To take note with appreciation of the report entitled "Methyl formate as blowing agent in the manufacture of polyurethane systems. An assessment for the application in MLF projects", submitted by UNDP;
  - (b) To request bilateral and implementing agencies to give full consideration of the assessment for the application of methyl formate when assisting Article 5 countries in preparing projects for the phase-out of HCFC-141b in polyurethane foam applications.

#### Oman: Terminal phase-out management plan: audit report (UNIDO)

#### Introduction

31. On behalf of the Government of Oman, UNIDO is submitting to the 62<sup>nd</sup> Meeting the verification report on the terminal phase-out management plan (TPMP) for CFCs. The TPMP was approved at the 52<sup>nd</sup> Meeting of the Executive Committee in July 2007 at the funding level of US \$505,250 (including support costs). At the 57<sup>th</sup> Meeting, the Executive Committee provided funding to UNIDO in the context

of its Work Programme Amendments for the verification of the implementation of the TPMP in line with decision 45/54. This document is the result of this verification exercise.

#### Verification of the TPMP achievements

- 32. The verification was carried out from 12 July 2010 to 12 September 2010 by the Sultan Qaboos University in Oman, which collected and reviewed data on imports and consumption of CFCs, and reviewed the Government's policy in controlling the import and the consumption of ODS.
- 33. The Sultan Qaboos University conducted the survey based on the methodology described in the terms of reference. The verification focused on:
  - (a) Verifying/reviewing the country's policy in controlling the import and consumption of ODS and the division of responsibility between national institutions for enforcing the relevant policies;
  - (b) Reviewing the government's statistics on ODS imports against the data from the customs authority and the amount of quota issued against actual quota used in 2009;
  - (c) Reviewing the list of Oman's authorized importers against the record of customs authority;
  - (d) Reviewing, on a representative sampling basis if necessary, the records of importers against the customs authority records and the quota issued;
  - (e) Discussing conclusions on the achievement of the annual ODS reduction target as well as recommendations; and
  - (f) Reviewing the plan of action proposed by the Government of Oman to implement the recommendations from the auditors.

#### Conclusion and recommendation of the verification

- 34. The final recommendation of the verification exercise included the following:
  - (a) Further strengthen the cooperation between the National Ozone Unit (NOU) and Customs Authority to ensure closer monitoring of actual imports versus quotas issued to the importers to reduce discrepancies in reporting;
  - (b) Provide the customs authority with details of the TPMP activities plan to ensure support in meeting its objectives;
  - (c) Need to strengthen equipment and technical capacity of the customs authority to conduct efficient and effective monitoring of ODS imports; and
  - (d) The NOU to fully implement national regulations covering reporting of imported ODS and maintain an up to date data base so that imports can be easily verified.

#### Secretariat's comments

35. The Secretariat reviewed the verification report based on the methodology established. It appears that the verification process was conducted in conformity with the approved methodology. In the frame of the verification, the team contacted all CFC importers in Oman. Their distributors provided data that was

reviewed by the customs authority and the Ministry of Manpower. Oman does not produce CFCs and has not imported any since the beginning of the year 2010.

36. The review of the list of the government's authorized importers showed that 11 importers have been allocated quota for the import of CFCs from 2007 to 2009 out of which only 5 importers have used their quota. The quota allocated to importers and the quantities of CFC-12 imported are presented in the table below.

#### Quota issued and imports of CFCS from 2007 to 2009

Description	2007	2008	2009
Quota	16.889	9.195	4.093
Imports (as per NOU)	10.096	8.493	1.360
Balance	+6.793	+0.702	+2.733

- 37. The report highlighted the discrepancy between data from the NOU and customs authorities due to the methodology used by the customs authorities to record their data. According to the NOU, customs authorities' data may include other chemicals resulting in higher values compared to the NOU data. Thus, NOU data was considered more accurate than that from the customs authorities.
- 38. The analysis of data collected from the NOU and importers revealed that 2 importers did not use their permit to import CFC-12. Based on this finding, customs authorities committed themselves to develop a framework that will improve the management of allocated quota against imports. In this context, the NOU would systematically send licence permits to customs authorities. Moreover, any decision or action taken by both parties would be recorded in a common software to be provided once developed by the customs authorities.
- 39. The verification report refers to Article 19 of the regulations where each importer of controlled substances should provide the names, types, quantities and dates of imported substances together with information on end users during the previous year to the Ministry of Environment and Climate Affairs no later than the end of January of each year. It revealed that this has not been implemented by importers. In this regard, the verification team recommended that the NOU monitors closely the amount of ODS imported, distributed and consumed by recording relevant data in its own database.
- 40. The verification team also addressed the issue related to staffing at the customs authority level and identifiers provided to inspect refrigerants. The team considered that the staffing and the number of identifiers available were insufficient to inspect ODS imports at entry points. In this respect, it recommended that the NOU selects one entry point for inspection of all ODS and ODS-contained equipment.
- 41. The Secretariat noted that the conclusions and recommendations provided in the report (see paragraph 34 above) addressed all the issues found during the verification and that the verification exercise was successfully completed.

#### Secretariat's recommendation

- 42. The Executive Committee may wish to:
  - (a) Take note of the verification of the terminal phase-out management plan (TPMP) of CFCs in Oman in 2009 and the recommendations contained therein; and

(b) Encourage the Government of Oman to continue its efforts in controlling the use of CFCs, and to apply the conclusions and recommendations of this verification in the implementation of the HCFC phase-out management plan.

#### Chillers projects

<u>Brazil</u>: progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)

<u>Colombia</u>: progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)

<u>Cuba:</u> progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP and Canada)

<u>Syrian Arab Republic:</u> Progress report on the demonstration project on the replacement of CFC centrifugal chillers (UNIDO)

<u>Global:</u> progress report on the global chiller replacement project (China, India, Indonesia, Jordan, Malaysia, Philippines, and Tunisia) (World Bank)

<u>Region – Africa:</u> progress report on strategic demonstration project for accelerated conversion of CFC chillers in 6 African countries (Cameroon, Egypt, Namibia, Nigeria, Senegal and Sudan) (UNIDO, France, Germany, and Japan)

<u>Region – Europe:</u> progress report on demonstration project on the replacement of CFC centrifugal chillers (Croatia, the former Yugoslav Republic of Macedonia, Montenegro, Romania, and Serbia) (UNIDO)

<u>Region – Latin America and the Caribbean:</u> demonstration project for integrated management of the centrifugal chiller sub-sector in the Caribbean, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)

#### Introduction

- 43. The Executive Committee had approved at its 47<sup>th</sup> and 48<sup>th</sup> Meetings eight demonstration projects for the replacement of CFC-using chillers for UNDP, UNIDO, the World Bank, Canada, France, Germany, and Japan comprising individual country projects, regional projects, and a global project. The approved project proposals suggested co-financing from a variety of sources, namely, the Global Environment Facility (GEF), Carbon Financing, Canadian International Development Agency (CIDA), the French Global Environment Facility, implementing agency funding and counterpart funding.
- 44. Through decision 55/5(d), the Executive Committee requested the Secretariat to "consult the Global Environment Facility and the implementing agencies on resolving co financing issues with respect to the approval of chiller projects, and when applicable, the related release of funding, and to report to the Executive Committee at its 56<sup>th</sup> Meeting on progress made in all chiller projects."

- 45. The Secretariat provided to the 56<sup>th</sup> Meeting information on the progress made in all chiller projects. The Executive Committee took decision 56/10 to note the report on progress made in all chiller projects and requested that the discussions held at the 56<sup>th</sup> Meeting be taken into account when preparing a revision of the desk study on the evaluation of chiller projects and when preparing a policy paper on "a facility for additional income from loans and other sources" in response to decision 55/2.
- 46. At the 59<sup>th</sup> Meeting, the Executive Committee decided through decision 59/8 to urge the agencies to accelerate implementation of the current chiller projects with co-funding modalities, to provide a progress report to the 62<sup>nd</sup> Meeting, and to encourage agencies to continue in their efforts to explore the applicability of carbon market instruments and other forms of co-financing, as appropriate, for the replacement also of HCFC equipment, particularly chiller equipment.
- 47. The progress report before the Executive Committee is in response to the above decisions, in particular decision 59/8.

#### Progress Report

- 48. In preparation for this progress report, the Secretariat distributed a three-part questionnaire to the three implementing agencies for chiller investment projects, namely UNDP, UNIDO and the World Bank. In the questionnaire, the agencies were requested to provide the following: a brief assessment of the experience to date and results achieved, a description of the co-financing mechanism used, and a summary of the activities undertaken. The questionnaire has been updated as compared to the previous version, to take into account additional information as well as the changing situation in which these projects are being implemented. This update is in line with decision 55/5 (d) of the Executive Committee, in which the Secretariat was requested to consult the implementing agencies on chiller projects. The questionnaires submitted by the agencies are provided as an attachment to this document.
- 49. For some countries, the implementation of the activities has showed significant progress during the last year. This is in particular true for Colombia, Jordan and the global chiller programme. A number of other projects showed no or almost no changes as compared to the report received last year.
- 50. Some programmes continue to face delays in implementation out of a variety of reasons. For example, some beneficiaries became insolvent before an activity could be implemented; in other cases, a similar problem occurred after the chillers were delivered, and new project beneficiaries had to be identified. In another example the beneficiaries are meant to provide the co-funding, but are financially not in the position to do so; in a particular case this situation has now continued for more than one year.
- 51. The majority of the chiller projects were approved by the Executive Committee five years ago with a number of expectations. An overview of the progress of the projects is shown in the table below. This table provides aggregated information regarding all projects, with the number of projects approved, the number of chillers that had to be phased out with the project funding and the expected co-funding, the revision that this number had undergone since the approval, and the actual status.

#### Original approval and current status of the chiller projects

	Number of projects	Total of chillers to be replaced (according to original MLF proposal)	Revised number of chillers to be replaced (according to latest planning)	Number of chillers already replaced
Projects approved	8	237	2,544	103

- 52. This table shows clearly that the implementation of the programme is much slower than anticipated. However, compared to the original objective, about 43 per cent of the chillers originally planned have in the meantime been converted. At the same time, the total number of chillers in the projects has increased more than ten-fold. Only one project, the chiller project for Latin America and the Caribbean showed almost no progress, and UNDP, as implementing agency, indicated that no additional chiller participants had been identified. UNDP suggests considering the project for cancellation at the 63<sup>rd</sup> Meeting. The replies from the agencies provided in the questionnaires allow some observations regarding the delays.
- 53. The difficult synchronization of the project cycles and requirements between the Global Environment Facility, GEF, the Clean Development Mechanism (CDM) and the Multilateral Fund is repeatedly mentioned. The agencies have to respect the procedures and schedules imposed by the funding institutions, which also have different policy frameworks, different deadlines. While the related issues were universal, the Resource Allocation Framework to beneficiary countries, adopted by the GEF Council in September 2005, has added previously unexpected complications; in particular the implementation of the new processes in the beneficiary countries caused significant delays. It was also noted that the CDM and the GEF request countries and agencies to follow strictly the established procedures, which are not co-ordinated between these institutions. Some agencies suggested that an improved coordination between funding bodies would reduce delays and facilitate the implementation of projects.
- 54. The agencies also had to face some unpredictable events during implementation such as the insolvency of project beneficiaries, or the withdrawal of financial intermediaries. With an increasing time lag between approval of the original project and implementation, these difficulties tended to increase. The unexpectedly long time required to organise the co-funding created an additional strain on the working relationships with chiller owners, and therefore on implementation. Finally, also the national project implementation modalities were cited as a potential cause for delays. In one country the mechanism chosen by the Government for co-funding did not create sufficient interest among possible beneficiaries, causing the need for project redesign.
- 55. As mentioned in the report to the 59<sup>th</sup> Meeting (UNEP/OzL.Pro/ExCom/59/10, para. 7), all agencies focussed not only on the replacement of chillers to reduce the demand for CFCs, but also on improving the energy efficiency of these systems. Some agencies advised that energy efficiency is not yet sufficiently promoted, and that the understanding of and interest in the benefits of energy efficiency improvements is not present for many stakeholders. However, in other cases and once the benefits were sufficiently transparent, the co-operation between the national governments and the agencies was very close and instrumental in moving the projects forward.
- 56. The questionnaires this year for the first time include questions regarding differences between the public and private sectors. It appears that agencies find it easier to work with private owners than with public ones. Public owners often have more difficulties to access additional resources needed, are faced with long and complex internal procedures, and might have priorities different from that of the private sector. Public sector owners seem, therefore, to have more difficulty in committing themselves and their resources to a replacement. One conclusion of one agency was that it appears meaningful to inform and take care of public owners upstream of the projects in order to avoid any subsequent complication or delay. On the other hand, private owners do not consider co-funding as a serious impediment as almost all of their commercial investments require several sources of funding.
- 57. Despite the obstacles and challenges reported, the agencies as a whole were quite satisfied with this co-funding experience. They even proposed replicating the experience in the future. UNIDO suggested a similar project be considered for the phase-out of HCFC-based chillers, and UNDP suggested that some elements of chiller co-financing could be explored for early domestic appliances retirement programmes. The World Bank believes also that similar approaches could be taken in the future, focusing on the institutional learning regarding the combination of funding from different sources with different

#### UNEP/OzL.Pro/ExCom/62/9

objectives. All the agencies agree that the lesson learnt from this co-funding experience will be useful for the setting up of future projects.

58. The Secretariat would like to take the opportunity to commend the work of the agencies regarding mobilisation of co-funding, and the flexibility and skill shown by all agencies in successfully overcoming difficulties related to expected financing sources that did not materialise, and in identifying other sources.

#### Secretariat's recommendation

- 59. The Executive Committee might wish to:
  - (a) Note the progress report on progress made in all chiller projects provided in document UNEP/OzL.Pro/ExCom/62/9; and
  - (b) Request the Secretariat to provide another report on progress achieved in chiller projects to the 65<sup>th</sup> Meeting.

\_\_\_\_



# METHYL FORMATE AS BLOWING AGENT IN THE MANUFACTURE OF POLYURETHANE FOAM SYSTEMS

## AN ASSESSMENT FOR THE APPLICATION IN MLF PROJECTS

EXE	CUTIVE SUMMARY	3
1.	INTRODUCTION	6
2.	PROJECT DESIGN	8
3.	PROJECT IMPLEMENTATION	9
4.	PROJECT OUTCOMES	10
4.1	HEALTH, SAFETY AND ENVIRONMENT (HSE)	10
	.1 HEALTH	10
	.2 SAFETY	11
	.3 ENVIRONMENT	12
	System Processability  1 Shipping & Storage	<b>12</b> 12
	.2 STABILITY	12
	.3 Hydrolysis and Corrosion	13
	.4 COMPATIBILITY	13
	FOAM PROPERTIES	13
4.3.	.1 FLEXIBLE AND INTEGRAL SKIN FOAMS	14
4.3.	.2 RIGID INSULATION FOAMS	18
4.4	ADDITIONAL INFORMATION FROM COMPANIES WHICH ARE MF USERS	23
4.5	CONVERSION COSTS	24
	.1 INCREMENTAL CAPITAL COSTS	25
	.2 Incremental Operating Costs	25
4.6	SYSTEM DETAILS	26
5.	CONCLUSIONS	27
5.1	HEALTH, SAFETY, ENVIRONMENT	27
5.2		27
5.3		27
	CONVERSION COSTS	28
	OVERALL ASSESSMENT CACHMENTS	28 30
	TACHMENT IA: METHYL FORMATE ASSESSMENT: RESPONSE TO PEER REVIEW	31
	TACHMENT IB: PEER REVIEW ON THE ASSESSMENT OF METHYL FORMATE AS A POLYURETHANE	31
	AM BLOWING AGENT WITH COMMENTS	33
	FACHMENT II: METHYL FORMATE - MATERIAL SAFETY DATA SHEET	38
	TACHMENT III: METHYL FORMATE EMISSIONS	40
ΑТΊ	FACHMENT IV: COMBUSTIBILITY OF METHYL FORMATE	41
ΑТΊ	FACHMENT V: REVERSE HEAT FLOW TESTS (SUMMARY, DETAILED VERSION IN SEPARATED FILE)	44
ΑΤΊ	FACHMENT VI: LONG TERM PERFORMANCE (SUMMARY, DETAILED VERSION IN SEPARATED FILE)	<b>45</b> 2

#### **EXECUTIVE SUMMARY**

The Executive Committee of the Multilateral Fund for the Implementation of the Montreal Protocol, through Decision 55/43, acknowledged the need to assess HCFC free technologies for use in developing countries and invited its implementing agencies, as a matter of urgency, to prepare and submit specific project proposals for the assessment of chemical systems for use with non-HCFC blowing agents. In response to this mandate UNDP formulated a number of pilot projects to investigate newly introduced HCFC free alternative technologies. This report describes the outcome of an assessment on the safe use of methyl formate (ecomate\* or MF) to replace HCFC-141b in PU foams.

The use of MF based systems in PU foams has been evaluated at Purcom Quimica Ltda in Barueri/SP, Brazil and Quimiuretanos Zadro SA de CV in San Francisco del Rincon/GTO, Mexico with the objective of assessing its performance compared with HCFC-141b based systems and establishing the feasibility of its use in MLF projects.

#### UNDP wishes to state herewith that:

The use of MF in PU foams constitutes proprietary technology;

UNDP has refrained from any investigation or disclosure that would infringe on said property rights but limited itself to evaluation and assessment;

While UNDP has made arrangements with the owner of the technology for technology disclosure and the offering of non-exclusive (sub-)licenses to prospective MLF project beneficiaries, the negotiation of such (sub-)licenses will be the responsibility of the beneficiaries;

Any findings and/or recommendations by UNDP are based on the assumption that beneficiaries will follow health and safety procedures as outlined by the Agency in this document and its attachment and/or recommended by the technology owner.

The technology using MF in PU foam is owned and marketed by Foam Supplies, Inc. (FSI) in the USA. While still small compared to HCFC-141b, its use has been growing substantially in the last few years as the following table shows:

Table 1

YEAR	AMOUNT (metric tons)					
TEAR	Methyl Formate	Polyol System	HCFC-141b Equivalent			
2005	40	850	100			
2006	75	1,500	180			
2007	160	3,200	385			
2008	360	7,200	864			
2009	365	7,300	875			
2010	910*	18,000	2,200			

Estimate based on January thru August

Source: Foam Supplies Inc. (FSI)

Purcom was at time of project initiation the only A5 licensee and, for that reason, was selected as the recipient for this project. Because Purcom does not market shoesole systems, this application has been separately assessed through Zadro. To avoid the perception that MLF funds would cause any preferential treatment, it was agreed from the onset with FSI and relevant licensees that they would grant non-exclusive (sub-) licenses to any interested party that applies for MLF-supported HCFC phase-out projects.

The project identified 17 PU applications. After project approval, November 2008, a slightly modified action program was prepared based on:

- A thorough evaluation and incorporation in the assessment of previous work by FSI and its licensees;
- Elimination of applications requiring direct injection (mostly continuous operations);

Acceptability, for the purpose of this project, was defined as follows:

- Determining the safe use of the technology based on health, safety and environmental (HSE) data;
- Determining the applicability of the technology based on its processability;
- Determining the applicability of the technology by measuring relevant physical properties before and after replacing HCFC-141b.,
- Collecting complementary information, views from enterprises that have tested MF formulations in their production;

The summary outcome of the assessment is as follows:

Table 2

		Acceptability				
Foam Type	Application	Health, Safety and Environment (HSE)	Processability	Physical Properties	Assessment	
	Hyper-soft molded	+	+	+	+	
Flouible	Hyper-soft blocks	+	+	+	+	
Flexible and	Viscoelastic molded	+	+	+	+	
Integral	Viscoelastic blocks	+	+	+	+	
Skin	Steering wheels	+	+*	+	+	
Foams	Structural (rigid)	+	+*	+	+	
Toailis	Semi-flexible	+	+	+	+	
	Shoesoles	+	+*	+	+	
	Residential Appliances	+	-	-	-	
	Other Appliances	+	+	+	+/-	
Rigid	Panels, Transportation, Reefers	+	+	+	+	
Foams	Spray	+	+	+	+	
	Blocks	+	+*	+	+	
	Pipe-in-pipe	+	+	+	+	
	Buoyancies	+	+	+	+	

<sup>\* =</sup> separate injection of MF recommended

<sup>+</sup> Acceptable, - unacceptable; +/- acceptable with conditions

Analysis of the outcome of the assessment led to the following conclusions:

- The use of methyl formate as an alternative blowing agent to HCFC-141b in PU foam applications can be considered as an alternative in developing countries in flexible/integral skin foam applications and in a number of rigid foam applications. It is important to consider that for certain applications on rigid foam the technology could not be recommended at this stage and on others the application of the technology should be analyzed on a case by case basis and could be subject to further optimization.
- To minimize safety risks at downstream users, such projects should preferably be implemented through their system suppliers as fully formulated systems;
- Project designers should ensure that:
  - Chemical compatibility is verified;
  - Minimum packed density is observed;
  - Health, safety and environmental recommendations are incorporated;
  - Implications related to acidity are taken into account.

#### Costs

Conversion costs were to be determined in Phase-II of the MF assessment. A request for funding of this project at Purcom/Brazil, which would be treated as an investment project, was to be submitted jointly with this report. However, for the following reasons it is suggested to forego such a phase in Brazil:

The price structure for PU chemicals in Brazil is not typical. The offering of locally produced polyols
is limited and imported polyols are subject to significant import duties. HCFC-141b, on the other
side, is lower in cost than in most other countries. The result is that MF systems currently are more
than10% higher priced than HCFC-141b systems (in Mexico this is less than 5%).

In this context, UNDP has developed generally applicable cost templates to calculate the incremental cost of conversion from HCFC-141b to MF-based foams (4.5.1, 4.5.2). It should be pointed out that capital and chemical cost can differ significantly from country to country and are also subject to economy of scale considerations.

#### 1. Introduction

The Executive Committee of the Multilateral Fund for the Implementation of the Montreal Protocol, through Decision 55/43 acknowledged the need to assess selected HCFC-free technologies for use in developing countries and invited implementing agencies as a matter of urgency to prepare and submit a limited number of time-specific project proposals for the development, optimization and validation of chemical systems for use with non-HCFC blowing agents. In response to this mandate, UNDP formulated a number of pilot projects to evaluate technology issues that it deemed unresolved. These issues ranged from determination of related global warming effects to validation of technologies that had been not, or only sporadic, been used in an Article-5 context. From these projects, six have been approved and one of these, the assessment of the use of methyl formate (MF) in non-continuous PU applications, has been technically completed. This particular pilot project has been designed around Purcom Quimica LTDA ("Purcom"), the largest independent system house in Brazil and specialized in tailor-made PU systems covering most PU applications. A notable exception is the application of PU foam in shoesoles, which has been validated through a pilot project executed by Quimiuretanos Zadro, a system house in Mexico that is specialized in PU shoesole systems.

MF as blowing agent in PU foams was first introduced by Foam Supplies, Inc. (FSI). The company filed December 18, 2001 for a US patent which was awarded June 22, 2004. By now, FSI has filed for, or has been awarded, patents in most major countries. The use of MF in PU foams has developed as follows (information from FSI):

Table 3

YEAR	AMOUNT (metric tons)					
TEAR	Methyl Formate	Polyol System	HCFC-141b Equivalent			
2005	40	850	100			
2006	75	1,500	180			
2007	160	3,200	385			
2008	360	7,200	864			
2009	365	7,300	875			
2010	910*	18,000	2,200			

<sup>\*</sup> Estimate based on January thru August

The development of ecomate has taken a life of its own and market share has grown as shown in the table above. Marketed under the name ecomate, MF is currently licensed to the following enterprises:

Australian Urethane Systems Asia Pacific

British Oxygen Corporation
 Selected European Countries

• Purcom Quimica South America

Expanded Incorporation India

Resichem South Africa

FSI has agreed to non-exclusive (sub) licensing in the future to system houses that are beneficiaries of MLF-funded HCFC phase-out projects. While the Brazilian part of the assessment was concluded in February 2010, the shoesole part took until August 2010. A first draft—excluding shoesoles—was presented during a workshop March 23/24 held in Curitiba, Brazil, with the participation of system houses, government officers, end users, regional experts, National Ozone Officers from the region and

#### UNDP - METHYL FORMATE ASSESSMENT - 62<sup>ND</sup> EXECUTIVE COMMITTEE MEETING

representatives from several implementing agencies as well as other providers of competing technologies. The completed assessment will be presented to interested parties at a workshop in Leon, Mexico (19th Oct 2010). The complete assessment addresses comments/suggestions from the first workshop participants, Foam Technical Options Committee (FTOC) individual experts consulted, as well as from a peer reviewer.

Technology is ever evolving and there could be future improvements in the use of MF as auxiliary blowing agent that may reduce or eliminate current performance limits. It is believed that the mandate of UNEP's Foams Technical Options Committee is to monitor and to report to the Montreal Protocol parties on such evolutions. UNDP believes that the current assessment is sufficient to draw conclusions on its potential use in MLF projects.

#### 2. Project Design

#### **Approved Design**

The project in its approved version was designed to develop, optimize and assess the use of MF as replacement technology for HCFC-141b in 17 PU applications and would cover acquisition of the necessary testing/prototyping equipment; development of formulations for all pertinent applications; optimization and assessment of these formulations, as well as dissemination of the experience gained through workshops. It also included the determination of incremental changes and related costs (ICCs and IOCs) deemed necessary at both system houses and downstream users to use the technology safely.

#### **Modified Design**

- **Peer Review:** projects normally do include a peer review of the proposed design. However, in this case a peer as review was not required as part of the submission. UNDP felt it prudent to add such a review to the completion procedure of the project (**Attachment-I**).
- Limitations: it is emphasized that this assessment serves a very practical purpose which is to determine the extent to which MF can be satisfactorily used in MLF-funded HCFC phase-out projects and, in this way, avoid unexpected setbacks in project implementations

This does not include an exhaustive investigation into the way the technology works. It does include back-to-back testing with the technology it replaces but also review of existing data, specifically on health, safety and environment. The term "evaluation" or "assessment" therefore better describes the task at hand than the more formal/legal term "validation".

- Applications: The applications for which the assessment was carried out are listed in the table under Section 3.
- **Optimization:** UNDP decided that optimization together with customers is more effective than prototyping at the system house only and would avoid some of the need for "phase-II" projects.
- **Collaborators:** While the project design remained centered around Purcom and Zadro, results have been shared and assistance was provided by other system houses using methyl formate, such as

Australian Urethane Systems: Australia Licensee Resichem: South Africa Licensee

Foam Supplies, Inc.: USA Owner of the technology

Together these system houses cover significant geographical areas. These companies have also shared their customer's views and information on their experience with MF (available upon request).

In recent HPMP related technical presentations the outcome of this assessment has been shared with PU system providers as well as downstream users. As a result, five system houses have already signed non-disclosure agreements and are testing MF systems in their own laboratories. Five others have contacted the technology owner of its licensees for the same purpose. Users in The Dominican Republic, Mexico, Nigeria and Uruguay have voiced their intention to convert to MF.

#### 3. Project Implementation

The project was approved at the 56<sup>th</sup> ExCom meeting in November 2008. Funding was received in February 2009. The original list of applications was modified and reviewed on work already completed (to save time, Purcom started immediately after project conception). By late August 2009, formulation development was completed and by 8<sup>th</sup> October 2009 an action plan for the assessment was ready . By December 18, all optimization except shoesoles work was completed. In August, 2010 the optimization of shoesole formulations, which suffered initially from complications related to compatibility issues was finalized.

Following is a final list of applications that have been evaluated:

Table 4

Foom Tune	Application	Milestones				
Foam Type	Application	Development	Optimization	Assessment		
	Hyper-soft molded	Completed	Completed	+		
Flexible	Hyper-soft blocks	Completed	Completed	+		
and	Viscoelastic blocks	Completed	Completed	+		
Integral	Viscoelastic blocks	Completed	Completed	+		
Skin	Steering wheels	Completed	Completed	+		
Foams	Structural (rigid)	Completed	Completed	+		
(FPF, ISF)	Semi-flexible	Completed	Completed	+		
	Shoesoles	Completed	Completed	+		
	Domestic refrigeration	Completed	Discontinued*	-		
	Other Appliances	Completed	Completed	+/-		
Rigid	Transportation, Reefers	Completed	Completed	+		
Foams	Panels-discontinuous	Completed	Completed	+		
(RPF)	Spray	Completed	Completed	+		
	Blocks	Completed	Completed	+		
	Pipe-in-pipe	Completed	Completed	+		

<sup>+</sup> Acceptable, - unacceptable; +/- acceptable with conditions

Notes: Methyl formate in continuous panels, boardstock and marine applications have been already proven in the USA, the UK and Australia on equipment and process conditions comparable to those in A5 countries. Other appliances include (apart from bottle coolers, display cabinets, etc) water heaters and thermoware which were previously separately listed but are very similar in formulations

<sup>\*</sup> The results did not justify continuation of trials

#### 4. Project Outcomes

Methyl-formate or methyl-methanoate is the methyl ester of formic acid. It belongs to the family of oxygenated hydrocarbons (hydrocarbons with one or more oxygenated functional groups). It has a relatively low molecular weight and is commonly used in the manufacture of formamides, formic acid, pharmaceuticals, insecticides and, more recently, as a blowing agent for foams. There has been also use as a refrigerant. A Material Safety Data Sheet (MSDS) prepared by the International Programme on Chemical Safety (IPCS) is attached (Attachment-II). There are also MSDSs from a number of suppliers and users.

Following data on physical properties have been taken from this MSDS and the 2006 FTOC report and compared with HCFC-141b, as it is targeted as an alternative to this substance:

Table 5

Property	Methyl Formate	HCFC-141b
Appearance	Clear liquid	Clear liquid
Boiling point	31.3°C	32°C
LEL/UEL	5-23%	7.6-17.7%
Vapor pressure	586 mm Hg @ 25°C	593 mm Hg @ 25°C
Lambda, gas	10.7 mW/mk @ 25°C	10.0 mW/mk @ 25°C
Auto ignition	>450°C	>200°C
Specific gravity	0.982	1.24
Molecular weight	60	117
GWP	Negligible	630
ODP	0	0.11

Sources: IPCS and FTOC

#### 4.1 Health, Safety and Environment (HSE)

#### 4.1.1 Health

Following data are taken from the Pesticide Action Network (PAN<sup>1</sup>) Registry:

Acute Hazard: Not listed Carcinogen: Not listed Endocrine Disruption: Not listed Reproductive and Development Toxicity: Not listed

MF is transformed in the body very rapidly (with a half-life of several seconds) into formic acid and methanol. The MSDS mentions 'R20/22' (harmful by inhalation and if swallowed) and 'R36/37' (irritating to eyes and respiratory system). OSHA assigned the substance a 100 ppm TWA and 150 ppm STEL. In the USA, MF is recognized as "GRAS" (Generally Recognized As Safe) and therefore exempt from premarket approval requirements of the Federal Food, Drug and Cosmetic Act. In the EU, it is preregistered under REACH with no further action required u/t 2018.

\_

www.pan-international.org

Based on studies conducted on behalf of FSI by certified industrial hygienists (**Attachment-III**), process emissions from MF in an indoor sprayfoam application—a worst case emission scenario—were determined to be <10.00 ppm at operator samples and <23.00 ppm from area samples. These values are well under the OSHA PEL. For injection applications they were significantly lower.

**Conclusion:** Based on the before mentioned evidence the use of MF as a blowing agent in PU foams appears not to create health concerns up and above those with HCFC-141b. It is highly recommended that applicable safe handling guidelines are followed.

#### **4.1.2** Safety

Methyl Formate's MSDS mentions that methyl formate is "extremely flammable" and "vapor/air mixtures are explosive". Based on this, one of the main arguments voiced against the use of methyl formate as blowing agent in PU foams is its perceived explosiveness. The term explosiveness, however, should be used with care and properly defined. Explosion is defined as" the bursting, or rupture, of an enclosure or container due to the development of internal pressure from a deflagration or detonation as defined in NFPA 69". Essential elements required to trigger an explosion are fuel, air, an ignition source, and containment.

Please note that the fuel can be pure MF or an MF-based fully formulated systems. To bring the latter to explosion is virtually impossible. Apart from the problem to get the polyol mixture ignited, the heat of combustion is so low that the necessary pressure built-up in containment will just not be achieved.

**Attachment IV** deals with flammability issues in more detail. It concludes that:

- Methyl formate as a pure liquid is very flammable and requires proper safeguards. The risk of explosion is, however, remote because its low heat of combustion;
- A PU system base on methyl formate can be formulated as a low combustible liquid and will not reach the LFL even in the drum's head space; and
- There is no reason to treat methyl formate fully formulated systems differently from HCFC-141b fully formulated systems.

Flammability is therefore not an issue for downstream users that apply fully formulated systems. The situation is different for system houses that purchase "pure" (97.5%) methyl formate, blend this with polyol and other components and then package the fully formulated systems into drums for shipment. While measurements show that even then it is difficult to reach the lower flammable limit, it still exists and it is therefore advised to follow recommendations for handling flammable liquids, as below:

- Proper personal protective equipment;
- Closed blending containers, with a dry nitrogen blanket;
- Explosion proof equipment (pump, agitator, light, heating/cooling,);
- Electrically grounded equipment and drums (grounding clip);
- A stationary sensor with alarm function set on 20% LEL;
- Adequate ventilation
- Meter MF under the level of the liquid to which it is being added (to avoid static electricity)
- Use closed blenders to avoid human exposure to isocyanate vapors, in case methyl formate is blended in isocyanate

**Conclusion:** There are fire safety risks associated with blending MF at system house level. They can be managed by following established standards and procedures. For preblended systems, no incremental fire risk exists.

#### 4.1.3 Environment

Methyl Formate is not registered as a hazardous air pollutant, groundwater contaminant or persistent organic pollutant (POP). Ecotoxicity data are not available. In the USA, methyl formate is not treated as a volatile organic compound (not a smog generator) and is SNAP approved. In Europe it is compliant with the RoHS and WEEE directives<sup>2</sup>. Its ODP is zero and its GWP insignificant (USEPA/Federal Register 69.190SNAP). In the EU it is preliminary permitted under REACH regulations.

**Conclusion:** MF fully formulated systems do not pose an environmental hazard based on current regulations

#### 4.2 System Processability

#### 4.2.1 Shipping & Storage

Shipment of MF can be carried out in carbon steel vessels or containers. No special material is required. Carbon steel is also acceptable for storage and piping. Under high moisture conditions (>80% RH) it is suggested to use stainless steel. Potential for moisture contamination can be avoided with a simple nitrogen blanket. MF has a very low viscosity (10% of that of water). This causes the need to recalibrate viscosity sensitive metering equipment (such as low-pressure pumps) but also allows for gravity or low pressure transfer (around 0.7 bar). Pump transfer is more suitable. Shipping, storage, and handling considerations are the same as for HCFC-141b. Transportation and storage labeling has to follow applicable regulations in the countries of use.

**Conclusion:** No special considerations are required for shipment and storage of MF fully formulated systems

#### 4.2.2 Stability

Manufacturers typically offer shelf lives of 6 months for their systems after date of manufacturing if stored in original, unopened containers at temperatures typically between 10°C and 30°C. MF based rigid foam made from two year old samples did still match the reactivity of freshly blended product. Industrial trials showed that MF blended polyols for ISF applications are limited in stability and loose catalytic activity after about one month. Blending MF in isocyanate solved the problem.

**Conclusion**: MF fully formulated polyol systems for all applications, except integral skin foams are sufficiently stable. MF blended isocyanate systems are stable

<sup>&</sup>lt;sup>2</sup> RoHS: Restriction of Hazardous Substances (EU directive), WEEE: Waste Electric and Electronic Equipment (EU directive)

#### 4.2.3 Hydrolysis and Corrosion

With only small amounts of water in the polyol and none in isocyanates, hydrolysis is not expected to be a major issue. The measured pH (typically 6.25) indicates the same. The slight acidity raises, however, concern of potential corrosiveness. The manufacturers emphasize that, provided stabilized systems are used, no special considerations are needed for equipment. They claim that MF systems are used in all types of equipment, and that equipment used for processing HCFC-141b can be used with MF systems.

There are however two known cases where customers claimed corrosion issues. Investigation of the complaints showed that in one case the user was using un-stabilized systems while in the other case the age of the equipment (20+ years) may have played a role. The relationship of corrosion to the use of MF was not established in both cases. Nevertheless, caution is recommended.

**Conclusion:** Equipment and components that come in contact with MF fully formulated systems should be preferably corrosion resistant

#### 4.2.4 Compatibility

Any auxiliary blowing agent requires compatible polyols and MF is not an exception. FSI states that it uses the same polyols, surfactants, catalysts and other additives as it did before (using HCFC-141b, HCFC-22 and HFC-134a). Purcom changed polyols in several cases, but this was part of an optimization process and would have been recommended for the same systems blown with HCFC-141b. For instance, Purcom's spray foam was not very successful in the market and needed stabilization by introducing additional polyols that are elsewhere common in spray foam applications. Their use improved Purcom's systems with both HCFC-141b and MF.

It should be emphasized that compatibility issues when changing blowing agents are normal. Cyclopentane-based systems required at their introduction sometimes significant polyol adjustments to overcome solubility issues and early HCFC-141b-based systems showed severe shrinkage and it took time to conclude that the potent solvent character of this substance limits it use in a system.

**Conclusion:** There are no specific compatibility issues of MF with polyols and/or additives. However, it is recommended that in designing conversion projects, baseline polyols used need to be carefully checked and any required changes to polyols and related costs should be identified.

#### **4.3** Foam Properties

Determining the acceptability and applicability of an HCFC-141b replacement technology includes measuring of relevant physical properties before and after replacing HCFC-141b. The technology is deemed acceptable for a particular application if the physical properties are within a predetermined range (generally 10%) from the original properties using HCFC-141b. Testing has been conducted at following locations:

- Flexible and integral skin foams at Purcom;
- Shoesole foams at Zadro (Mexico) and CETEC (certified laboratory for shoe testing in Mexico);
- Rigid foams at FSI( USA);

#### UNDP - METHYL FORMATE ASSESSMENT - 62<sup>ND</sup> EXECUTIVE COMMITTEE MEETING

 Steering wheels at Takata-Petri (Brazil). The company was not prepared to disclose testing details but confirmed compliance with relevant Volkswagen requirements and provided positive assessment. Domestic refrigerators at Mabe(Mexico).

Test protocols are on file. Test results have been categorized as follows:

Flexible and Integral

- Hypersoft Foams (molded, blocks)

Skin Foams

- Viscoelastic Foams (molded, blocks)

Semi flexibleStructural (rigid)

- Steering Wheels

- Shoesoles

Rigid Foams

- Domestic refrigeration

- Other Appliances (including water heaters and thermoware)

- Panels, Blocks and Transportation

- Spray foams

#### 4.3.1 Flexible and Integral Skin Foams

#### 4.3.1.1 Hypersoft Foams

The tests were conducted at Purcom. Test results are as below:

Table 6

PROPERTY	TEST PROCEDURE		UNITS	HCFC-141b	MF
PROPERTY	NBR*	ASTM	UNITS	HCFC-1410	IVIF
Density	8537	D-3574	Kg/m <sup>3</sup>	19.4	19.2
ILD 25%	9176	D-3574	N	11	10
ILD 40%	9176	D-3574	N	13	13
ILD 65%	9176	D-3574	N	24	23
Comfort Factor	9176	D-3574	n/a	2.2	2.3
Resilience	8619	D-3574	%	42	40
Compression Set 90%	8797	D-3574	%	3	3
Tensile strength	8515	D-3574	kPa	80	88
Elongation	8515	D-3574	%	460	470
Tear Strength	8516	D-3574	N/m	456	460

<sup>\*</sup>National Brazilian Standard

**Conclusion:** The test results with MF are within an acceptable margin from the ones with HCFC-141b

#### 4.3.1.2 Viscoelastic Foams

The tests were conducted at Purcom. Test results are as below:

Table 7

PROPERTY	TEST PROCEDURE		UNITS	HCFC-141b	MF
PROPERIT	NBR	ASTM	UNITS	HCFC-1410	IVIF
Density	8537	D-3574	Kg/m <sup>3</sup>	34.2	34.8
ILD 25%	9176	D-3574	N	28	31
ILD 40%	9176	D-3574	N	36	39
ILD 65%	9176	D-3574	N	60	61
Comfort Factor	9176	D-3574	n/a	2.1	2
Resilience	8619	D-3574	%	6	5.5
Compression Set 90%	8797	D-3574	%	5	5
Tensile strength	8515	D-3574	kPa	60	65
Elongation	8515	D-3574	%	230	222
Tear Strength	8516	D-3574	N/m	270	301

**Conclusion:** The test results with MF are within an acceptable margin from the ones with HCFC-141b or better

#### 4.3.1.3 (Semi) Flexible Integral Skin Foams

Tests were conducted at Purcom. Two different grades of hardness were tested:

Table 8
Black (softer)

PROPERTY	TEST PRO	OCEDURE	LIAUTC	UCEC 141h	DAT.
PROPERTY	ASTM	DIN	UNITS	HCFC-141b	MF
		Produ	ıct		
Molded Density	D-3574		kg/m3	288	285
Hardness	D-2240	53505	Shore A	35	35
Resilience	D-3574		%	45	45
Foam Core					
Internal Density	D-3574		Kg/m3	233	230
Tensile strength		53571	kPa	229	235
Elongation		53571	%	98	95
Tear Strength		53575	N/m	1,280	1,300
Compression set	D-3574		%	28	30
(50%)			_		
		Skin O	nly	1	
Tensile strength		53504	kPa	1,000	1,000
Elongation		53504	%	96	95
Tear Strength		53515	N/m	4,380	4,375

Table 9
White (firmer)

DDODEDTY	TEST PRO	OCEDURE	LINUTC	11050 444h	MF	
PROPERTY	ASTM	DIN	UNITS	HCFC-141b		
		Produ	ict			
Molded Density	D-3574		kg/m3	300	298	
Hardness	D-2240	53505	Shore A	44	44	
Resilience	D-3574		%	45	45	
Foam Core						
Internal Density	D-3574		Kg/m3	215	205	
Tensile strength		53571	kPa	215	210	
Elongation		53571	%	63	60	
Tear Strength		53575	N/m	880	860	
Compression set	D-3574		%	5	3	
(50%)						
		Skin O	nly			
Tensile strength		53504	kPa	1,720	1,700	
Elongation		53504	%	79	77	
Tear Strength		53515	N/m	4,700	4,680	

**Conclusion:** The test results with MF are within an acceptable margin from the ones with HCFC-141b

#### 4.3.1.4 Rigid Integral Skin Foams

There are no formal specifications for rigid integral skin foams in Brazil. The customer judges the surface, which needs to be free of pinholes. In very few exceptions, drop tests or bending tests are performed. The structural strength, however, is much larger than for comparable materials and generally no compliance tests are conducted. While most manufacturers use water-based systems, some insist on HCFC-141b because the skin is thicker (water-based products only provide densification towards the outside rather than a skin) and can be better polished. There is also a large use of rigid structural foam in shoesole applications (platform shoes). Test results on these are mentioned under "shoesoles" and in this case there are stringent requirements. In all rigid structural foam applications MF functioned as well as HCFC-141b.

**Conclusion:** *MF provides a comparable performance to HCFC-141b* 

#### 4.3.1.5 Steering Wheels

Takata-Petri in Brazil supplies steering wheels to almost all (international) car manufacturers in this country. They use exclusively MF systems which they blend in-house in the isocyanate site. This avoids system degradation of the polyol side which is observed when blending MF with ISF-specific catalysts and stabilizers. Takata-Petri confirms that the product meets the requirements of all their customers but declined to provide specifics claiming confidentiality. It was, however, willing to provide a written statement( available upon request) (Other, non-OEM suppliers of steering wheels use preblended ISF formulations with good results, however blended in the isocyanate side.

**Conclusion:** MF provided a comparable performance to HCFC-141b as per the assessment of one company that supplies to international car manufacturers

#### 4.3.1.6 Shoesoles

Zadro's specifications are based on HCFC-141b-blown foams. It produces 8 main formulations that have been consolidated into four main ones—others being derivatives for special customers. All foam samples have been prepared in Zadro's laboratory using a low-pressure prototype dispenser. Densities have been determined by Zadro, other tests were performed by CIATEC, a federally owned and operated testing facility for the shoe industry. CIATEC is ISO-9001/2000 certified. The results are as follows:

Table 10

Property	All	R-095	R-096	R-099	QZCT15	Test Method
Туре	types	SPORT	TRAVEL	RIGID	SEMI-RIGID	
Blowing Agent	141b	MF	MF	MF	MF	
Density (kg/m³)	<450	400	440	420	400	DIN 53420 ASTM D-792
Tear resistance (kgf/cm)	>6*	38.9	41.5	n/a	n/a	DIN 53507 ASTM D-624
Abrasion Resistanc e (mg, maximum	<350	337.2	140.3	147.0	146.9	DIN 42516 ASTM D- 1044
Flex Resistanc e (%, 30,000 cycles)	<200*	0	0	n/a	n/a	DIN 53543 ASTM D- 1052

<sup>\*</sup> Only applicable for flexible shoesoles

Tests protocols for all tests are on file.

Please note that formulation R-099 is rigid integral skin foam and the outcome support previous conclusions for this application. An important aspect of ISF foams in general is a smooth, pinhole-free surface. Methyl formate performed very well on this.

**Conclusion:** MF perform equally or better compared to standards derived from HCFC-141b

#### 4.3.2 Rigid Insulation Foams

Test samples were prepared and tests were performed by FSI based on formulations prepared by, and chemicals from Purcom. This procedure was selected because Purcom did not have test facilities to perform full testing for these applications and no independent test facilities could be sourced in Brazil. On the other side, sending foam samples abroad compromised the samples so that local foaming was required. Test results were as follows:

#### 4.3.2.1 Domestic Appliances

As part of an assessment of HCFC replacement technologies, Mabe, an international manufacturer of domestic refrigerators tested in its corporate technology center in Queretaro/Mexico a fully formulated, MF-based system from Purcom for domestic refrigeration insulation. A Lanzen panel ("Brett Mold") was used for these trials along with a Cannon high-pressure dispenser. Several samples were injected with minimal fills and over-packs of 10, 15 and 20%. A square mold was used in order to prepare test specimens for K-Factor, Compression and Dimensional Stability testing. Results were as follows:

**<u>Processing</u>** showed a slow reaction profile was compared with the current system. This would result in a dramatic cycle time extension on both cabinets and doors.

*Free Density* was recorded at 21 kg/m<sup>3</sup>, which is a low density for Queretaro's altitude, a 24 kg/m<sup>3</sup> is recommended.

Minimal Filling Density (MFD) was recorded at 33 kg/m³ which is relatively high. Recommended MFD for domestic refrigeration is in the range of 27-28 kg/m³. A low flow was observed, which predicts bad filling in narrow areas or complex geometries such as liners ribs, fridge mullion, etc. **Density Profile** was calculated from an over-packed specimen which was 36 kg/m³ at average but some sections shown densities as low as 28 kg/m³. The average density/cut density ratio for this measurement must be in the range of 90-95%. In this case we found a ratio of 28/36x100 = 77%. When this parameter is below 90%, more PU is needed to achieve the minimal density which should be in the range of 30-31 kg/m³. Purcom recommends a density of >35 kg/m³ in order to get optimal results of this system, but this density could not be reached at this altitude because it would require over-pack exceeding 30%, which is too high and unsafe.

**The K-Factor** observed (0.18 BTU-in/ft².ºF.hr) was too high for time zero recording. Current values are around 0.135 BTU-in/ft².ºF.hr. This means a 33% difference and a potential increase in energy consumption of roughly 15%, which is detrimental for energy consumption standards.

**Compression Set and Dimensional Stability** were suitable and within specifications.

It was concluded that the system would need extensive optimization to meet the requirements of domestic appliance manufacturers in general and Mabe's relatively high altitude requirements specifically.

FSI as well as Purcom claim that through such optimization much better results can be obtained and, at a minimum, insulation and densities matching cyclopentane can be obtained. However, the aim of this assessment is comparison with HCFC-141b and the prevailing density for this application is 32 kg/m³, which cannot be reached by MF at the current level of technology. It was decided therefore that continuing optimization of formulations for this sub-sector would serve no purpose for the MLF at this

point. FSI and Purcom may pursue this directly for their own benefit. Mabe's information is part of the testimonies.

**Conclusion:** MF fully formulated systems in domestic appliances did not perform well. They showed higher densities and much lower insulation performance compared to HCFC-141b systems

#### 4.3.2.2 Other Appliances

The same system as used at Mabe was tested at Metalfrio/Celaya, Mexico and produced acceptable results for commercial refrigeration (bottle coolers) with densities around 36 kg/m³ and improved k-factors. Metalfrio's baseline formulation, however, was water-based foam and therefore do not fit the assessment criteria.

Following tests were conducted on a generic fully formulated commercial refrigeration system and have significance for all other appliance foams:

Table 11

TESTS	UNITS	HCFC- 141b UNDP- A*	HCFC- 141b UNDP-B*	MF UNDP-C*	MF UNDP-D*
Closed Cell	%	98.20%	97.08%	98.76%	97.68%
Density,	pcf	1.72	1.67	1.69	2.10
Density, Cold Age, -80°F (-62.2°C)	pcf	1.72	2.08	1.88	2.00
Dimensional Stability 1-Day	ΔV,%	-21.99	-3.35	-0.62	-0.14
	ΔM,%	-2.08	0.27	0.52	0.94
Dimensional Stability 7-Day	ΔV,%	-22.60	-4.35	-1.12	-0.21
	ΔM,%	-2.56	-0.23	0.52	0.28
Density, Heat Age, 200°F (93.3°C)	pcf	1.69	2.03	1.91	1.99
Dimensional Stability 1-Day	ΔV,%	0.08	12.49	-6.43	-1.35
	ΔM,%	-1.03	-0.71	-1.51	-1.45
Dimensional Stability 7-Day	ΔV,%	2.86	2.62	-5.26	-1.20
	ΔM,%	-0.37	-0.04	-0.75	-0.98
Density, Humid Age, 158°F, 100% RH (70°C)	pcf	1.72	2.07	1.91	2.01
Dimensional Stability 1-Day	ΔV,%	7.50	5.75	-5.24	-2.73
	ΔM,%	0.99	0.94	-0.07	0.35
Dimensional Stability 7-Day	ΔV,%	8.18	6.23	-8.91	-2.61
	ΔM,%	4.10	1.45	3.55	7.09
Density, Compression, Parallel	pcf	1.71	2.10	1.95	2.02
	CS, psi	20.61	25.50	27.36	23.00
Density, Compression, Perpendicular	pcf	1.70	2.07	1.88	2.00
	CS, psi	12.12	18.29	13.81	20.30

UNDP - METHYL FORMATE ASSESSMENT - 62<sup>ND</sup> EXECUTIVE COMMITTEE MEETING

TESTS	UNITS	HCFC- 141b UNDP- A*	HCFC- 141b UNDP-B*	MF UNDP-C*	MF UNDP-D*
Thermal Conductivity at $55^{\circ}F$ midpoint Blowing Agent $\ell$	mW/m-°K	10	10	10.7	10.7
k-factor	BTU-in/ft2-hr-°F	0.138	0.140	0.145	0.145
λ value	mW/m-°K	19.9	20.1	20.9	20.9

<sup>\*</sup> refers to different foam sample batches

Test results are reported in the imperial system which is customary in the US. As the purpose of the tests is comparison, no conversion has been performed.

A more accurate thermal efficiency evaluation would be using products in side-by-side (reverse heat flow) testing). **Attachment–V** describes the outcome and conditions of such a test for a refrigerator and a freezer. With only 0.75  $^{0}$ C lower temperature increase compared with HCFC-141b, the results are better than expected from the difference in the  $\Lambda$  factor of the blowing agents and appear to indicate that MF performs better in a laminated product than in a non-laminated sample.

Also important would be to assess long term performance of the foam. An evaluation of physical properties over an extended period of time is provided in **Attachment-VI**. The outcome shows that MF-based foams perform well over time with minimal degradation of foam properties.

#### 4.3.2.2.1 Water heaters

While a sub-application for other appliance foams, the density of water heater foams are generally lower and over-pack is less.

Following results were measured with a Purcom system, foamed and tested at FSI:

Table 12

PHYSICAL PROPERTIES		TEST METHOD	UNITS	HCFC-141b SYSTEM	MF SYSTEM
Density	Core	D-1622	Pcf	2.07	2.12
Closed Cell Content		In-house	%	98.20	98.76
Perpendicular	Density	D-1621	Pcf	2.23	2.35
Compression	Strength	D-1621	Psi	29.40	29.57
Cold age	Density	D-1622	Pcf	2.23	2.32
	ΔV	D-6226	%	0.67	-0.57
	ΔΜ	D1622	%	-1.05	-0.79
Heat Age	Density	D-1622	Pcf	2.25	2.32
	ΔV	D-6226	%	1.35	-0.65
	ΔΜ	D1622	%	-1.10	-1.98
Humid Age	Density	D-1622	Pcf	2.20	2.29
	ΔV	D-6226	%	6.04	-8.84
	ΔΜ	D1622	%	1.69	-0.23

UNDP - METHYL FORMATE ASSESSMENT - 62 ND EXECUTIVE COMMITTEE MEETING

PHYSICAL PROF	PERTIES	TEST METHOD	UNITS	HCFC-141b SYSTEM	MF SYSTEM
Thermal Conductivity	λ		mW/m-hr-°K	22.4	24.6
@ 55°F Midpoint	K-factor	C-518	BTU-in/hr-ft <sup>-</sup> F	0.155	0.171

#### 4.3.2.2.2 Thermoware

This is also a sub-application of other appliance foams (FTOC classification) but with even lower densities than water heaters and less over-pack. Insulation values are also less critical and a more dimensional flexibility allows mitigation through design changes.

Following results were measured with a Purcom system, foamed and tested at FSI:

Table 13

PHYSICAL PROPERTIES		TEST METHOD	UNITS	HCFC-141b SYSTEM	MF SYSTEM
Density	Core	D-1622	Pcf	1.56	1.66
Closed Cell Content		In-house	%	97.08	97.68
Perpendicular	Density	D-1621	Pcf	1.54	1.66
Compression	Strength	D-1621	Psi	18.41	18.08
Cold age	Density	D-1622	Pcf	1.65	1,87
	ΔV	D-6226	%	1.34	-1.47
	ΔΜ	D1622	%	-0,50	-1.11
Heat Age	Density	D-1622	Pcf	1.67	1.95
	ΔV	D-6226	%	1.34	-1.47
	ΔΜ	D1622	%	-0,87	-2.04
Humid Age	Density	D-1622	Pcf	1.62	1.94
	ΔV	D-6226	%	5.32	-12.03
	ΔΜ	D1622	%	1.63	4.82
Thermal Conductivity	λ		mW/m-hr-⁰K	20.8	24.0
@ 55°F Midpoint	K-factor	C-518	BTU-in/hr-ft <sup>-</sup> F	0.144	0.155

**Conclusion:** The test results on essential properties with MF fully formulated systems in "Other Appliances" were within an acceptable margin from the ones with HCFC-141b

#### 4.3.2.3 Panels/Blocks/Transportation

Back to back commercial production of panels with HCFC-141b and with MF has been witnessed at Coldair in Curitiba/Brazil³ with no difference in appearance and density except a significantly improved metal/foam adhesion. A visit of the company was included in the referenced workshop program in March 2010. Densities in these applications are typically 38-41 kg/m³—sometimes higher. Following are the results of comparative testing of a formulation from Purcom, foamed and tested at FSI for this kind of application:

<sup>&</sup>lt;sup>3</sup> **ColdAir** Indústria e Comércio de Sistemas de Refrigeração Estrada da Graciosa, 5823, Curitiba - PR, 83412-460, Brazil. (0xx)41 3675-9545. The company can also be contacted through Purcom

Table 14

Table 14					
PHYSICAL PROPERTIES		TEST METHOD	UNITS	HCFC-141b SYSTEM	MF SYSTEM
Density	Core	D-1622	Pcf	1.88	1.96
Closed Cell Content		In-house	%	98.20	98.76
Perpendicular	Density	D-1621	Pcf	1.78	2.03
Compression	Strength	D-1621	Psi	20.54	26.72
Cold age	Density	D-1622	Pcf	1.82	2.08
	ΔV	D-6226	%	-2.44	0.37
	ΔΜ	D1622	%	-1.75	-1.08
Heat Age	Density	D-1622	Pcf	1.83	2.14
	ΔV	D-6226	%	1.40	0.10
	ΔΜ	D1622	%	-1.23	-1.02
Humid Age	Density	D-1622	Pcf	1.82	2.10
	ΔV	D-6226	%	6.15	3.96
	ΔΜ	D1622	%	0.12	0.11
Thermal Conductivity	λ		mW/m-hr-°K	20.2	26.8
@ 55°F Midpoint	K-factor	C-518	BTU-in/hr-ft <sup>-</sup> F	01.40	0.151

**Conclusion:** The testified use of MF in current commercial production of rigid foam for panels/blocks/transportation applications indicates that there are no specific issues with MF as compared to HCFC-141b and product tests back this up.

#### 4.3.2.4 Spray foam

Purcom's HCFC-141b-based sprayfoam systems did not perform well in stability. The systems were based on locally produced Mannich (polyether) polyols only, while most sprayfoam systems include in addition a mix of aromatic amine and polyester polyols. The system was converted to MF, optimized with the mentioned different polyols and then shipped to the USA for foaming and testing. The results are as follows:

Table 15

PHYSICAL PROPERTIES		TEST METHOD	UNITS	HCFC-141b SYSTEM	MF SYSTEM
Density	Core	D-1622	Pcf	1.90	1.94
Closed Cell Content		In-house	%	97.08	97.68
Perpendicular	Density	D-1621	Pcf	2.66	1.86
Compression	Strength	D-1621	Psi	14.88	27.92
Cold age	Density	D-1622	Pcf	1.94	3.00
	ΔV	D-6226	%	-0.48	-0.90
	ΔΜ	D1622	%	0.00	0.37
Heat Age	Density	D-1622	Pcf	1.84	3.07
	ΔV	D-6226	%	-2.04	-7.84
	ΔΜ	D1622	%	-7.84	-0.61
Humid Age	Density	D-1622	Pcf	1.91	2.84
	ΔV	D-6226	%	-1.53	-2.89

UNDP - METHYL FORMATE ASSESSMENT - 62<sup>ND</sup> EXECUTIVE COMMITTEE MEETING

PHYSICAL PROPERTIES		TEST METHOD	UNITS	HCFC-141b SYSTEM	MF SYSTEM
	ΔΜ	D1622	%	10.37	9.89
Thermal Conductivity	λ		mW/m-hr-°K	19.9	24.5
@ 55°F Midpoint	K-factor	C-518	BTU-in/hr-ft <sup>-</sup> F	0.138	0.170

All physical properties compare well except the thermal conductivity. It has to be kept in mind, however, that this is a completely new system for Purcom and some further optimization will be needed. FSI sells MF sprayfoam systems in the US market along with HFC-134a-based sprayfoam systems. These compare as follows:

Table 16

PHYSICAL PROPERTIES		ASTM TEST METHOD	UNITS	ECOMATE SYSTEM	HFC-134a SYSTEM
Density	Free Rise		Pcf	1.9-2.1	1.9-2.1
	Core	D-1622	Pcf	2	2
Compressive	Perpendicular	D-1621	Psi	24	20
Strength					
Water Absorption	Weight	D-2127	lbs/ft <sup>2</sup>	0.01	0.02
	Volume	D-6226	%	>92	>92
Thermal Efficiency	Initial K factor	C-518	BTU-in/hr-ft <sup>-</sup> F	0.14-0.16	0.15-0.16
	ВА Л		mW/m.k	10.7	14
Dimensial Stability	Wet	D-2126	% Vol change	<1	-1
	Dry		% Vol change	n/d	n/d
	Cold		% Vol change	0	0
Fire Resistance		UL94 HF1		Yes	Yes

**Conclusion:** The mechanical properties of MF-based spray foams are equivalent to commercial HCFC-141b systems or better but the thermal efficiency needs further optimization

#### 4.4 Additional information from companies which are MF users

UNDP solicited and received views/information from companies where MF has been trialed. In addition, system houses that sell ecomate systems were asked to collect the same from companies that currently use MF systems in their commercial operations.

Following table shows the answers received (actual letters are on file):

Table 17

Foam Type	Application	Company	Country	Acceptability Assessment
	Hyper-soft molded	Kumar	Brazil	+
	Hyper-soft blocks	Aumar	Brazil	+
	Viscoelastic molded	Aumar	Brazil	+
Flexible and	Viscoelastic blocks	Tropical	Brazil	+
Integral Skin	Steering wheels	Takata Petri	Brazil	+
Foams	Character and (winsind)	Injefox	Brazil	+
	Structural (rigid)	Poliuretane	Brazil	+
	Semi-flexible	Injefox	Brazil	+
	Semi-nexible	Rallyspeed	Australia	+
	Domestic refrigeration	Mabe	Mexico	-
		Gelopar	Brazil	+
		Zero	South Africa	+
	Commercial refrigeration	Chill Flow	Australia	+
		Fabristeel	China	+
		Perlick	USA	+
		H&K Dallas	USA	+
		Cooke	New Zealand	+
	Water heaters	Prosol	Brazil	+
D:-:-I	Transportation, Reefers	Termosul	Brazil	+
Rigid Foams	Panels continuous	Paneltech	Australia	+
Foams	Panels-discontinuous	Danica	Brazil	+
		Somma	Brazil	+
	Caral	Isar	Brazil	+
Spray Blocks	Spray	Global	Australia	+
		Polyair	Australia	+
	Blocks	Coldair	Brazil	+
	Thermoware	Plastitalia	Brazil	+
	mermoware	Evakool	Australia	+
	Pipe-in-pipe	Somma	Brazil	+
	Buoyancies	Sealite	Australia	+

<sup>+</sup> Acceptable, - unacceptable; +/- acceptable with conditions

Some of the customers purchase MF-based systems already 3-5 years.

## 4.5 Conversion Costs

UNDP has developed a generally applicable cost template to calculate incremental cost of conversion from HCFC-141b to MF-based foams. It should be pointed out that capital and chemical cost can differ significantly from country to country and are also subject to economy of scale considerations.

## 4.5.1 Incremental Capital Costs

Table 18

ENTITY	ACTION	CALCULATION	COSTS (US\$)
System House	Explosion proofing of blending tanks	AA x 30,000	
System House	Nitrogen dispenser	BB x 8,000	
System House	Spray/PIP retrofit package	CC x 5,000	
System House	LPD retrofit package	DD x 10,000	
System House	Pycnometer (closed cell tester)	1 x 5,000	
System House	Portable K-factor tester	1 x 10,000	
System House	Refractometer ( test chemical purity)	1 x 10,000	
System House	Small rent-out dispenser	EE x 10,000	
System House	Project Management	FF customers @ 1,000	
System House	Monitoring & technology transfer		
System House	Contingencies	10% capital costs	
System house	Sub-Total		
Customers	Spray/PIP retrofit packages	GG x 5,000	
Customers	LPD/HPD retrofit package	HH x 10,000	
Customers	New Dispensers	II x 20,000	
Customers	Trials, testing, training,	KK customers @ 3,000	
Customers	Contingencies	10% of 202,000	
Customers	Sub-Total		
		GRAND TOTAL	
		C/E (US\$/kg/ODS)	

## 4.5.2 Incremental Operating Costs

Following is an example of an incremental cost template for IOCs. Prices are for illustration only. Four system houses/experts were asked to convert a given HCFC-based formulation to MF. The results are quite similar. The last two formulations leave the chemical ration the same, which is required for sprayfoams.

Table 19

CHEMICAL	PRICE	BASI	LINE	Comp	any A	Comp	any B	Comp	any C	Comp	any D
	(US\$/kg)	%	Cost	%	Cost	%	Cost	%	Cost	%	Cost
Polyol	3.20	38	1.22	40	1.28	40.6	1.30	42.5	1.36	44	1.41
Isocyanate	3,00	50	1.50	53	1.59	53.4	1.60	50	1.50	50	1.50
HCFC-141b	2.40	12	0.29								
MF	4.00			7	0.28	6	0.24	7.5	0.30	6	0.24
Cost			3.01		3.15		3.14		3.16		3.15
Difference			Base		0.14		0.13		0.15		0.14

## 4.6 System Details

With proprietary technology involved, formulation disclosure is a complex issue. While UNDP has been involved with and has financially supported adjustments of MF-containing formulations for applications that were not already commercial and/or optimizing such formulations in an A5 context, it has not ventured into the underlying technology partly due to intellectual property issues.

Following general rules apply when changing from HCFC-141b to MF as auxiliary blowing agent (ABA):

- Equimolar replacement would require 1 kg HCFC-141b to be replaced by 0.51 kg MF;
- Because of the strong solvent effect of MF, this ration can change at lower MF loads;
- However, the objective to keep the system non flammable, limits the maximum amount of MF to 8 php; equivalent to 16 php HCFC-141b. Increased water levels make up for additional blowing;
- In practice, 1 kg HCFC-141b can be replaced by anywhere from 0.35 kg (spray foam) to 1kg (high-density ISF);
- An MF system has to be stabilized to work well, with minimal hydrolysis and related corrosion and potential silicon/catalyst attack. This stabilization is proprietary technology.

To support MLF recipients, UNDP has arranged with FSI and its licensees that any interested (potential) MLF recipient will be offered, on request:

- Product Information Sheets (PIS) for specific applications;
- Samples and use instructions subject to signature of a non-disclosure/non-analysis agreement;
- A non-exclusive use (sub-) license.

#### 5. Conclusions

Based on the information presented in this Report it is concluded that:

## 5.1 Health, Safety, Environment

- The use of MF does not create health concerns up and above those with HCFC-141b. Both substances have flammable limits but in fully formulated systems will not reach these even remotely under process conditions;
- Flammability of MF is an inherent safety risk. However, this risk is sharply mitigated—even virtually eliminated—at downstream user level when using fully formulated systems;
- MF-based systems do not pose an environmental hazard based on current knowledge/regulations;
- MF-based systems are approved by the US EPA for use in <u>all</u> foam applications (SNAP approval).

## 5.2 System Processability

- Special considerations are required for the shipment and storage of pure MF.
- No special considerations are required for fully formulated systems with less than 6% MF (polyols) or less than 2% MF (MDI) following USDOT regulations. Local regulations have to be consulted.
- MF-blended polyol systems for all applications except for integral skin foams are stable. MF-blended
  isocyanate systems are always stable. UNDP does not support blending in isocyanate and proposes
  instead separate injection through a third stream as developed by Zadro for shoesoles;
- Although there is no conclusive evidence of corrosive effects, it is recommended that components that come in contact with MF or MF blends should be corrosion resistant;
- There are no identified compatibility issues of MF with polyols and/or additives. However, it is recommended that when designing conversion projects, the compatibility of baseline polyols will be carefully checked and any required changes to polyols and related costs should be identified.

## **5.3** Foam Properties

- MF based hypersoft foams match HCFC-141b foams;
- MF based viscoelastic foams match HCFC-141b foams;
- MF based flexible/semi-/rigid/rigid ISF foams match HCFC-141b within an acceptable range;
- MF-based shoesole systems match or exceed HCFC-141b foams;
- MF based rigid foams for other appliances match HCFC-141b foams within an acceptable range;
- MF based spray foams match HCFC-141b systems within an acceptable range and outperform HCFC-134a and HCFC-22-based systems;
- MF based rigid foams for discontinuous panels and transportation match HCFC-141b foams within an acceptable range;
- Product and long-term performance (reversed heat flow and 5 year performance) is acceptable.

It is concluded from customer testing that:

- MF based foams for steering wheels match HCFC-141b foams within an acceptable range;
- MF based foams for domestic refrigerators and freezers do not sufficiently match HCFC-141b foams based on density and insulation.

Information provided by companies that are MF users indicates that:

## Integral Skin:

- One company that supplies products to international car manufacturers informed that MF based rigid integral skin foams match HCFC-141b foams within an acceptable range. Other companies that manufacture steering wheels use standard ISF systems
   MF based foams for buoyancies match HCFC-141b foams within an acceptable range
- One company that produces continuous panels informed that it uses MF without any problem and that MF based foams match HCFC-141b foams within an acceptable range

#### **5.4** Conversion Costs

UNDP has developed a cost template to calculate the incremental cost of conversion from HCFC-141b-to MF-based foams. It should be pointed out, however, that capital and operating (chemical) costs can differ significantly from country to country and that these are also subject to economy of scale operations and location of the supplier.

#### 5.5 Overall Assessment

Following is a consolidated overview of the findings of this report:

Table 20

F			Assessr	ment	
Foam Type	Application	HSE	Processability	Physical Properties	Results
	Hyper-soft molded	+	+	+	+
et. S.L.	Hyper-soft blocks	+	+	+	+
Flexible	Viscoelastic molded	+	+	+	+
and	Viscoelastic blocks	+	+	+	+
Integral	Steering wheels	+	+*	+	+
Skin	Structural (rigid)	+	+*	+	+
Foams	Semi-flexible	+	+	+	+
	Shoesoles	+	+*	+	+
	Residential Appliances	+	-	-	-
	Other Appliances	+	+	+/-	+/-
Rigid	Panels, Transportation, Reefers	+	+	+	+
Foams	Spray	+	+	+	+
	Blocks	+	+*	+	+
	Pipe-in-pipe	+	+	+	+
	Buoyancies	+	+	+	+

<sup>\* =</sup> separate injection of MF recommended

<sup>+</sup> Acceptable, - unacceptable; +/- acceptable with conditions

Based on this assessment, UNDP believes that the use of Methyl Formate as an alternative blowing agent to replace HCFC-141b in PU foam applications in MLF projects would have to be subject to the following conditions:

- 1. Projects should preferably be implemented through local system houses to minimize safety risks at downstream users;
- 2. Project designers should ensure that:
  - a. Chemical compatibility is verified,
  - b Minimum density is observed,
  - c. Health, safety and environmental recommendations are incorporated,
  - d. Implications related to the flammable and corrosive character of the substance are addressed,
  - e. A compliance monitoring proposal is included.
  - f. Local availability and costs of polyols and other elements should be considered to determine operational costs.

# **Attachments**

- 1. ATTACHMENT Ia: METHYL FORMATE ASSESSMENT: RESPONSE TO PEER REVIEW
- 2. ATTACHMENT Ib: PEER REVIEW ON THE ASSESSMENT OF METHYL FORMATE AS A POLYURETHANE FOAM BLOWING AGENT WITH COMMENTS
- 3. ATTACHMENT II: METHYL FORMATE MATERIAL SAFETY DATA SHEET
- 4. ATTACHMENT III: METHYL FORMATE EMISSIONS
- 5. ATTACHMENT IV: COMBUSTIBILITY OF METHYL FORMATE
- 6. ATTACHMENT V: REVERSE HEAT FLOW STUDY
- 7. ATTACHMENT VI: LONG TERM PERFORMANCE

## ATTACHMENT Ia: METHYL FORMATE ASSESSMENT: RESPONSE TO PEER REVIEW

Decision 55/43 requires Agencies to inform the ExCom on pilot projects through "a progress report after each of the two implementation phases...". UNDP suggested in addition, the following alternative supervision arrangements:

- 1. By the Secretariat through an independent, qualified foam expert.
- 2. ExCom to consider requesting Parties to have the supervision of the validation through the UNEP Foams Technical Options Committee (FTOC).

UNDP felt that such a peer review, which could be extended to a preview of intended individual validation programs and preview/endorsement before transferring to Phase-II sub-projects, would increase project quality and general acceptability. However, the FTOC felt that its participation in such a review process would fall outside its mandate and declared itself unable to provide a formal opinion on the report. UNDP then resorted to the usual peer review process for proposed ODS phaseout projects and requested a review by Dr. Mike Jeffs, formerly employed by Huntsman, former Secretary General of ISOPA and standing member of the FTOC. The full review is shown below, with comments provided on UNDP's request by Mr. Bert Veenendaal, UNDP Senior Expert Foams (in "review' mode).

A first draft of this assessment was completed and presented to the FTOC May 18 as part of the FTOC's general technology review process. Comments and suggestions from individual FTOC members were taken into account in a new draft dated June 1, 2010 which was forwarded to the peer reviewer June 3. Present version of the report addresses the comments provided by the independent technical report (Attachment Ib). Below is a summary of UNDP answers to some of the points in the review. The reviewer mentions following required characteristics for a foam blowing agent with the following characteristics:

- 1. An established use base, preferably over some years, such that its use can be stated as "well proven" in all the target applications
- 2. Very low GWP and hence no environmental pressures to curtail its use; also the toxicology should not require any special measures to protect personnel in the manufacturing areas
- 3. Economical to use in terms of both the costs per kg of foam made and the safety (flammability) engineering requirements
- 4. Safe to use without the precautions required for pentane and safe to use in the application of spray foams
- 5. Suitable for a broad range of applications in terms of the various aspects of processability

UNDP does not necessarily disagree with these required characteristics but would like to point out that in the case of methyl formate there was in 2007 no established use base in A2 countries and exactly for that reason it was deemed necessary to prepare an assessment for a substance that, at least from available literature, promised to fit all other requirements mentioned by the reviewer. UNDP does remark in its report on the—rather dramatic—increase of the use of methyl formate after that date, but just to indicate a trend that started after the decision for an assessment was made. For the same reason, testimonies for each application have been collected from companies that use MF in their commercial operations. If there would have been an established use base in A2 countries at the time of project preparation, no assessment would have been needed.

All other requirements have been addressed albeit in another format, i.c.:

- Health, Safety, Environment (HSE)
- System Processability
- Physical Properties
- Conversion Costs

**Health, Safety, Environment** – while health and environment related data are accepted by the reviewer, a desire for more emission testing is voiced. In response, UNDP has commissioned two additional industrial hygiene

studies (one in Brazil and one in South Africa) that will be submitted separately to the ExCom. However, UNDP does not really see the need, as the studies incorporated in the assessment show consistently a very large safety margin in operator exposure as well compared to the flammability potential under operation conditions (<0.2% of the LFL. It can indeed be stated that it has been impossible in trials to create conditions in which the lower flammable limit could even be approached. In view of flammability risk MF gases are comparable with HCFC-141b. UNDP is, however, not adverse to the idea of a post-implementation HSE review by a qualified person and has already sourced affordable equipment for that purpose (~ US\$ 2,000 per monitor). There are also monitoring badges available from at least two suppliers and these may also be considered.

**System Processability** – reviewer correctly voices exposure concerns when remarking on the stability of polyol blends for integral skin foams and the proposed solution (by Purcom) to blend MF in the isocyanate. UNDP mentions in its report (section 5.5: Overall Validation) that "based on the need to blend MF with the isocyanate this is not recommended from an HSE point of view". However, in the mean time, as part of the evaluation of MF in shoesole applications, an alternative procedure has been developed that avoids the need of blending in isocyanate.

Physical Properties – The reviewer states his preference to test from machine samples rather than from laboratory ones. This opinion is generally shared but for integral skin, which features commonly metal inserts and relatively small, complicated shaped parts, this is not always possible and praxis has shown good correlation between handmix and machine samples in physical properties. Apart from ISF/FMF applications, all samples originate from machine-made foams which is essential of insulation and shoesole applications. The mentioned lack of information on rigid ISF foams is recognized and remediated in the final assessment. The observation that insufficient testing on rigid foams is conducted is related to the fact that the reviewer based his report on an outdated version of the assessment. The newer version UNDP sent well before the peer review report includes complete test results for all applications.

Conversion Costs – This section is misunderstood. MF containing systems can be handled without specific safety precautions related to flammability or explosion risk. This is not the case for system houses but one system house supplies at average 30 customers. In other words, safety related costs are reduced to 1/30 of those of hydrocarbon projects. The cost threshold in Mexican projects pending approval (less than US\$ 5.00/kg ODS) shows this impressively. Actual operating costs differ greatly per country. To facilitate fair comparison, UNDP has developed a cost template that offers standardization in costing approaches. The template is included in the final report.

**Editorial Comments** – UNDP agrees with the suggestions but wants to point out that most of these were already implemented in the June version of the assessment.

**Conclusions** – the reviewer observes that global polyurethane system houses have not taken a lead in optimizing MF technology. This is indeed the case and is the very reason that the MLF needed to take the lead on this or forgo a technology that shows potential in cost containment as well in foam properties. Recently though, changes in attitude are becoming apparent and two of these global players have now signed evaluation agreements for MF. Also, the explosive growth in the use of MF—albeit still a minor technology compared with HCFCs or HCFs—shows growing acceptance.

In all this, the limited scope of this assessment should be emphasized. The MLF does not want project failures and wants to make sure that recipients know the pros and cons of a technology that is as of yet not, or not well, known in most A5 countries. The aim is not to conduct or fund research and development. UNDP feels that this assessment provides a clear picture of the potential of methyl; formate to replace HCFC-141b and will avoid adverse surprises during project implementation—as has been, for instance, the case with LCD technology.

## UNDP - METHYL FORMATE ASSESSMENT - 62<sup>ND</sup> EXECUTIVE COMMITTEE MEETING

# ATTACHMENT Ib: PEER REVIEW ON THE ASSESSMENT OF METHYL FORMATE AS A POLYURETHANE FOAM BLOWING AGENT WITH COMMENTS

Dr Mike Jeffs 14/07/2010

#### 1. INTRODUCTORY COMMENTS

Several novel blowing agent technologies have been introduced since the beginning of the MLF process and most have played significant roles in ODS replacement in both A2 and A5 countries. In general, most of these technologies were developed by the major polyurethane formulation suppliers, who operate in both A2 and A5 countries. In many cases they worked with fluorocarbon or hydrocarbon suppliers. This approach has been very successful and a full palette of technologies has been successfully delivered. Additional technological refinements have often been developed by smaller system houses for niche applications in both A2 and A5 countries. A keyblowing agent has been HCFC-141b, which is well proven, and in large-scale use for polyurethane insulation foams plus integral skin foams for shoe soles and automotive/furniture applications.

However, the acceleration of the phase-down of HCFC-141b availability under Decision XIX/6 has emphasized the critical role that this blowing agent has carried out. It has been economical to use, flammability precautions are minor and inexpensive and the physical properties of foams based on it, particularly insulation values, closely match those of CFC-11, which it replaced. It should be remembered that, when first introduced in the early 1990s, HCFC-141b-based foams had major dimensional instability problems leading to large insurance payouts (for shrunken roofs).

Hydrocarbon (pentane)-based foam technologies were introduced at the same time as HCFC-141b and have been very successful but are only economical to apply at medium to large blowing agent-consuming enterprises and, so far, have been considered to be unsafe to use for the important spray foam application.

The later HFCs, such as HFC-245fa and HFC-365mfc, have been successfully introduced in several applications but their in-use costs (operating costs) are much (30 to 100%) higher than for HCFC-141b. Additionally, because of their comparatively high GWPs, their use may be controlled by legislation in both A2 and A5 countries.

Thus, Decision XIX/6 forces on the foam industry the very urgent requirement for a blowing agent with the following characteristics:

- 6. An established use base, preferably over some years, such that its use can be stated as "well proven" in all the target applications
- 7. Very low GWP and hence no environmental pressures to curtail its use; also the toxicology should not require any special measures to protect personnel in the manufacturing areas
- 8. Economical to use in terms of both the costs per kg of foam made and the safety (flammability) engineering requirements
- 9. Safe to use without the precautions required for pentane and safe to use in the application of spray foams
- 10. Suitable for a broad range of applications in terms of the various aspects of processability
- 11. Suitable for a broad range of applications in terms of foam physical properties including dimensional stability and insulation values (for insulating foams)

This report has been commissioned by the UNDP and funded by the MLF to ascertain whether or not technology based on Methyl Formate (MF) meets these criteria. The technology owner is Foam Supplies, Inc (FSI) which sells and licenses MF technology as ecomate®

#### 2. KEY COMMENTS

The report reviewed is dated 25/05/2010 and includes an Attachment (Appendix) on a study of Reverse Heat-Flow. Additional information from FSI on 5-year ageing of foam articles and on "Safe Handling Recommendations for ecomate® spray foam systems" has also been taken into consideration by the reviewer (see comment under Editorial Comments).

In addressing the six criteria listed at the end of Section 1 the following can be stated:

1. The total usage of MF for foam blowing has built up over 5 years and 365 tons were used in 2009. In considering that up to 16 separate applications targeted this usage of MF in 2009 the usage is just less than 23 tons per application. There may be some applications where there has been above average usage, which could bring use experience in that application up to the cusp of the "well proven" status. If this is the case there is no relevant information in the report for such a judgment to be made.

Another consideration is with regard to the experience cited by various enterprises in their testimonies (Section 4.4). A total of 30 enterprises have submitted these testimonies and their average usage of MF must have been only about 12 tons per user. *This cannot be interpreted as sufficient use to be characterised as "well proven"*. It is also noted that the evaluation in shoe soling application will be evaluated in an additional programme to take place in Mexico.

In determining the relevance of the reported use of MF it would be illuminating to identify those applications where usage per enterprise exceeded, for example 50 tons in 2009. It would also be very useful to cite the use per sub-sector.

2. It is clear that the GWP of MF is very low and there should not be any environmental/climate issue with this. In addition, there is no evidence of any other environmental issue.

The toxicology data do not raise significant concerns but it should be noted that all training activities are opportunities to remind staff that there should be no exposure to disocyanates (MDI or TDI). It is the reviewer's understanding that MF will be registered for the European Union's REACH Regulation by BASF (due by 11/2010) and that this registration will include the application of foam blowing. The data in this registration submission should be incorporated in revisions of the MSDS. The rather limited industrial hygiene data (only two applications) show emissions are below OSHA limits.

- 3. The costs per kg of foam made are understood to be broadly similar to those for HCFC-141b. However, most usage of MF-based technologies is expected to be by small to medium-sized foam manufacturers who buy pre-blended formulations from system houses. It is clear that the equipment and procedures required for the safe preparation of formulations are similar to those for pentane. The capital costs associated with the storage and pre-blending operations for pentane are about 50% of the overall costs for a complete foaming plant. Presumably, the MLF will meet these very significant capital costs.
- 4. In considering the question of safety in foaming operations there are several factors to consider see table for the main combustibility parameters for MF.

The data indicate that MF's combustibility performance is in-between those of HCFC-141b and pentane. Whilst this is not a precise scientific statement it indicates that concern is considerably higher than for HCFC-141b. The report contains data on airborne concentrations of MF in two processing/applications. As an intermediate measure it is advisable to measure concentrations of MF for each foaming operation to ascertain proximity or otherwise to the LEL.

	Methyl	HCFC-	Cyclopentane
	Formate	141b	
Flash Point C	-19°C	None	-49°C
Flame Limits (v%)			
Lower (LEL)	4	7.6	1.5
Upper (UEL)	23	17.7	7.8
Auto Ignition Temperature	449	550	260
DOT Shipping	Class III	Not	Class III
Classification	Flammable	regulated	Flammable

The reviewer has more concern with respect to spray foam operations, particularly in confined situations. The FSI document "Safe Handling Recommendations for ecomate® spray foam systems" referred to above gives guidance and a clear set of recommendations should be developed for each (processing) application and, especially, for spray foaming. These recommendations should include a requirement, until a further review, for MLF projects to include the measurement of concentrations and the provision for detectors and enhanced ventilation.

#### See also comments on the combustibility of foams in section VI below.

5. The report contains information on shipping and storage, stability, hydrolysis/ corrosion and compatibility with polyols. One issue raised is the stability in integral skin formulations and the apparent solution of blending in the diisocyanate (typically MDI) stream rather than in the polyol. This should be approached with care because of the hazards of handling diisocyanates. It is also mentioned that this stability issue may be associated with the limited range of polyols available to Purcom.

In the discussion on hydrolysis and corrosion it is noted that equipment and components should be preferably corrosion resistant. This conservative approach is supported.

As stated in the report, questions of polyol compatibility arise whenever a chemical component is changed in formulations. Purcom has been active in this area, including on spray foam systems in collaboration with UNDP. Unfortunately, circumstances prevented the evaluation of the foams resulting from this process. The recommendation that potential users optimise their formulations around MF is, of course, fully supported.

- 6. Foam property information is provided for 10 applications using either flexible or rigid products. The latter include several insulation foam applications. The test sample preparation methods are given in Attachment-VI. It is noted that flexible and integral skin samples were prepared by hand mixing. It would be preferable and more representative of production techniques to have machine-made samples. Samples for rigid foams (pour and spray foams) were prepared using dispensing machines. Comments per application are as follows:
- **Hyper Soft Foams:** Purcom carried out a range of tests (ASTM and National Brazilian Standard) and results are essentially the same as for the HCFC-141b-based control.
- Viscoelastic Foams: Purcom carried out a range of tests (ASTM and National Brazilian Standard) and results are essentially the same as for the HCFC-141b-based control.
- Flexible Integral Skin Foams (Including Steering Wheels): Purcom carried out a range of tests (ASTM and DIN) on two hardness grades (ca. 35 and 44 hardness by Shore A) and results are similar to those obtained for the HCFC-141b-based control. There is no data for Steering Wheels as the testing was carried out by

the enterprise Takata-Petri who has not shared their data except to state that the MF-based material met VW requirements (Specification #?). The reviewer recommends that data be obtained by additional testing to verify the suitability of MF in this application. (Note that shoe-soling testing will be carried out at a later date (in Mexico).

- Rigid Integral Skin Foams: There is no information on who performed the evaluation (Purcom?) and no data. One criterion is that the surface is free of pinholes. It is claimed that foams based on MF give a comparable performance to those based on HCFC-141b but further information would be helpful.
- Rigid Insulation Foams: It is clear that the evaluation of the properties of rigid insulating foams based on MF is incomplete. This is due to limited testing facilities being available at Purcom plus the nature of test data required to verify insulating foams, which should include medium-long terms ageing tests on thermal conductivity and dimensional stability. The latter are partially covered by the additional paper on "Ecomate After Five Years" and by the Reverse Heat Leakage Tests (Attachment 4). The former has several illustrations of parts stored for 5 years. Changes in dimensions are stated to be less than 3.5% in all cases.
  - Domestic Appliances: Mabe carried out the testing with formulations developed by Purcom. The
    foam system required higher densities than those that are normal in this application, poor flow and
    cure time plus thermal conductivities much higher than for HCFC-141b-based foams. It is accepted
    that the foam system was not optimised around MF and improved results are likely as a result. Given
    the position achieved by cyclopentane and pentane blends it was decided not to pursue optimisation
    in this sub-sector.
  - 2. Other Appliances: The formulations used in the previous section were tested by another enterprise (Matalfrio/Celaya) and compared to HCFC-141b-based controls. Based on the results displayed, the MF-based foams showed more shrinkage, on average, in the dimensional stability testing up to 7 days. No longer-term data is displayed. There was also a small increase (4.5%) in initial thermal conductivity. It is noted that reverse heat leakage tests by FSI on unspecified formulations showed slightly less heat leakage for MF compared to HCFC-141b-based foamed cabinets. The data in the "Ecomate After Five years" for a drinks dispenser a slightly higher loss in insulation efficiency after 5 years compared to a HFC-134a-based control. Tests on display cabinets showed losses in insulation efficiency that were less than for the HFC-134a-based controls.
  - 3. Water Heaters: A Purcom system was foamed and tested by FSI in comparison to a HCFC-141b-based control. The cold, hot and humid ageing data do not show the ageing period involved and so no comments are possible beyond the point that there is little difference in properties compared to the control. The initial thermal conductivity is about 10% higher for MF compared to HCFC-141b-based foams.
  - 4. **Thermoware:** Again, a Purcom system was foamed and tested by FSI in comparison to an HCFC-141b-based control. The densities in this application are lower than in the previous appliance applications. However, it is noted that shrinkage is higher than for the controls, particularly under hot and humid conditions. Again, the test time is not specified. The initial thermal conductivity is over 7% higher for MF compared to HCFC-141b-based foams.
  - 5. Panels/Blocks/Transportation: Again, a Purcom system was foamed and tested by FSI in comparison to an HCFC-141b-based control. At the higher densities in these applications here is no significant difference in dimensional stability test data shown. Again, the test time is not specified. The initial thermal conductivity is about 8% higher for MF compared to HCFC-141b-based foams. The data in the "Ecomate After Five years" for an insulated shipping container showed a small loss in insulation efficiency after 5 years. An additional point is the combustibility of the finished articles, particularly if they are subject to building codes/regulations in the end use such as part of a building this is the case in many A5 countries. This information should be obtained where applicable.

6. Spray Foams: It would appear that only data from FSI is included and then in comparison with a control based on HFC-134a that is generally not used in A5 countries. The data show, not altogether surprisingly, better properties for MF than for the control. Further testing is necessary and will be carried out with an optimised formulation to be developed by Purcom and foamed and tested by FSI. It is necessary to include controls based on HCFC-141b in this extension of the testing programme. An additional point is the combustibility of the foam in use. Spray foams are normally subject to building codes/regulations in the end use such as part of a building – this is the case in many A5 countries. This information should be obtained where applicable.

## 3. EDITORIAL COMMENTS

There are a small number of editorial comments to be made. These include:

- All pages to be numbered and correlated with the Contents (page 2)
- Consideration to be given to inclusion of the additional papers from FSI on 5-year ageing of foam articles and on "Safe Handling Recommendations for ecomate® spray foam systems" into the report (as attachments?)
- There are additional style/language/grammar points which should be clear after a Word spell check.

#### 4. CONCLUSIONS

The report and attachments are key parts of a comprehensive review of the suitability of MF for a range of applications as a replacement for HCFC-141b. The challenge is particularly sever as HCFC141b is used in a large number of A5 countries in almost all polyurethane foam applications. It must also be remembered that Decision XIX/6 imposes tight and global deadlines that were rarely encountered by "emerging" blowing agents in the past. Many of the apparent shortfalls in MF's performance are very likely to be addressed by formulation optimisation but, in the present case, this optimisation process has not, so far, been led by the global polyurethanes systems houses – as was the case with earlier blowing agents.

However, this review highlights several points that require further data/attention. These are included in the text of this review in *blue italic font*. They are in the following areas:

- Information on experience and MF usage per application (sub-sector)
- Combustibility safety during foam processing need for concentration measurements and ventilation
- Combustibility of the end product/foam in some cases
- Data on spray foams and shoe soling elastomer applications
- Further and longer-term dimensional stability test data, particularly for rigid insulating foams. As a temporary measure the density of foams which are normally near 32 kg/m³ could be increased by 2-3 kg/m³ to safeguard dimensional stability until more experience is gained
- Similarly, longer term thermal conductivity testing using accelerated ageing methods such as the slicing method or ageing at 70°C

## ATTACHMENT II: METHYL FORMATE - MATERIAL SAFETY DATA SHEET

METHYL FORMATE 0664 April 1997			
		13 EC No: 607-014-00-1 Formic acid me	thyl ester Methyl methanoate
C2H4O2 / HCC	OOCH3 Molecular mass: 60.1		
TYPES OF HAZARD/ EXPOSURE	ACUTE HAZARDS/SYMPTOMS	PREVENTION	FIRST AID/FIRE FIGHTING
FIRE	Extremely flammable.	NO open flames, NO sparks, and NO smoking.	Powder, alcohol-resistant foam, water spray, carbon dioxide.
EXPLOSION	Vapor/air mixtures are explosive.	Closed system, ventilation, explosion-proof electrical equipment and lighting. Prevent build-up of electrostatic charges (e.g., by grounding). Do NOT use compressed air for filling, discharging, or handling.	In case of fire: keep drums, etc., cool by spraying with water.
EXPOSURE			
Inhalation	Cough. Dizziness. Dullness. Headache. Labored breathing. Shortness of breath. Unconsciousness.	Ventilation, local exhaust, or breathing protection.	Fresh air, rest. Artificial respiration may be needed. Refer for medical attention.
Skin	Redness.	Protective gloves.	Remove contaminated clothes. Rinse skin with plenty of water or shower. Refer for medical attention.
Eyes	Redness.	Safety goggles.	First rinse with plenty of water for several minutes (remove contact lenses if easily possible), then take to a doctor.
Ingestion	(Further see Inhalation).	Do not eat, drink, or smoke during work.	Rinse mouth. Give a slurry of activated charcoal in water to drink. Induce vomiting (ONLY IN CONSCIOUS PERSONS!). Rest. Refer for medical attention.
SPILLAGE DISP	POSAL	PACKAGING & LABELLING	
Evacuate danger area! Collect leaking liquid in sealable containers. Absorb remaining liquid in sand or inert absorbent and remove to safe place. Do NOT wash away into sewer. Personal protection: self-contained breathing apparatus.		F+ Symbol Xn Symbol R: 12-20/22-36, Class: 3 UN Pack Group: I	/37 S: (2-)9-16-24-26-33 UN Hazard
EMERGENCY R	RESPONSE	SAFE STORAGE	
	ergency Card: TEC (R)-30S1243 NFPA	Fireproof. Separated from strong oxid	dants. Cool.
-		International Programme on Chemical ATION ON THE BACK. IPCS International	

#### **0664 METHYL FORMATE**

#### **IMPORTANT DATA**

Physical State; Appearance COLOURLESS LIQUID, WITH CHARACTERISTIC ODOUR. Physical dangers The vapor is heavier than air and may travel along the ground; distant ignition possible. The vapor mixes well with air, explosive mixtures are easily formed. Chemical dangers Reacts vigorously with oxidants. Occupational exposure limits TLV: 100 ppm as TWA, 150 ppm as STEL; (ACGIH 2004). MAK: 50 ppm, 120 mg/m3; Peak limitation category: II(4); skin absorption (H); Pregnancy risk group: C; (DFG 2004).

Routes of exposure The substance can be absorbed into the body by inhalation of its vapor and by ingestion. Inhalation risk A harmful contamination of the air can be reached very quickly on evaporation of this substance at 20/C. Effects of short-term exposure The substance is irritating to the eyes and the skin. The vapor is irritating to the eyes and the respiratory tract. The substance may cause effects on the central nervous system. Medical observation is indicated.

## **PHYSICAL PROPERTIES**

Boiling point: 32/C Melting point: -100/C Relative density (water = 1): 0.98 Solubility in water, g/100 ml at 20/C: 30 Vapor pressure, kPa at 20/C: 64 Relative vapor density (air = 1): 2.07 Relative density of the vapor/air-mixture at 20/C (air = 1): 1.7 Flash point: -19/C Auto-ignition temperature: 449/C Explosive limits, vol% in air: 5-23 Octanol/water partition coefficient as log Pow: -0.21

#### **ENVIRONMENTAL DATA**

#### **NOTES**

The odor warning when the exposure limit value is exceeded is insufficient. Card has been partly updated in October 2004 and 2005. See sections Occupational Exposure Limits, EU classification, Emergency Response.

## **ADDITIONAL INFORMATION**

**LEGAL NOTICE** 

Neither the EC nor the IPCS nor any person acting on behalf of the EC or the IPCS is responsible for the use which might be made of this information

©IPCS 2005

#### **ATTACHMENT III: METHYL FORMATE EMISSIONS**

#### 1. Occupational Exposure

Methyl formate has been assessed by OSHA (the US Occupational Safety and Health Administration), resulting in an Occupational Guideline September 1978, which is still valid. This information has been incorporated in all available MSDSs. OSHA and the American Conference of governmental Industrial Hygienists (ACGIH) have both instituted applicable exposure limits as follows:

OSHA PEL (ppm)	ACGIH TLV (ppm)	ACGIH STEL (ppm)
100	100	150

PEL = permissible emission limit (8 hr average)
TLV = threshold value limit (8 hr average)

STEL = short term exposure limit (15 min average)

FSI commissioned three industrial hygienic (IH) surveys, two by "Safe Day Consulting" (Missouri) and one by ICU (Texas). These surveys covered sprayfoam (1) and refrigerated vending machines applications (2-this survey was repeated to determine the effect on emissions of a low and high production rate). Both contractors are certified, used AIHA accredited laboratories and maintained chain of custody logs. Full individual results cannot be published because of pertinent US laws that regulate such disclosure to safeguard medical records (HIPAA and AAEMR). UNDP has confidentially reviewed the chains of custody and has de-personalized detailed records of the outcome on file. The outcomes were as follows:

Application	Survey Date	Concentration Range	Average Concentration
Sprayfoam	02-18-2004	1.3 – 23 ppm	8.2 ppm
Vending Machines	03-13-2003	0.0 – 4.5 ppm	2.2 ppm
Vending Machines	02-18 2004	0.5 – 23 ppm	0.9 ppm

Under no circumstance the permissible emission level was even approached and, so even less the lower flammability level (50,000 ppm).

#### 2. Other Exposure

The ICU survey also including sampling around drums with polyol blend with the following results

• 6" above open container 0 ppm

Immediately above open container:
 2" above liquid:
 < 500 ppm (<1% LFL)</li>

6" above liquid: 0 ppm
Immediately above fresh foam: 0 ppm

Immediately above 1hour old foam: 0 ppm

These tests were done with an electronic monitor programmed in % LFL and therefore not able to make precise differentiation at very low LFLs.

**Conclusion**: no specific exposure control limits are needed for methyl formate system operations

#### ATTACHMENT IV: COMBUSTIBILITY OF METHYL FORMATE

One of the arguments voiced against the use of methyl formate as blowing agent in PU foams is its perceived explosiveness. This has been initially the case with HCFC-141b as well—first projects included explosion proofing—but praxis showed this concern was not justified. It may be useful to look into the phenomenon of combustibility.

#### 1. BACKGROUND

Properties commonly used to define flammable substances are 4:

- **flash point**: the lowest temperature at which vapors above the liquid will "flash" when exposed to a flame in a standard test apparatus
- **auto-ignition temperature**: the temperature at which a flammable substance will burn spontaneously (without an external ignition source)
- flammable limits: concentrations range where a flame will propagate away from an ignition source
- maximum explosion pressure: highest buildup of pressure after ignition in a closed vessel
- maximum rate of pressure rise: maximum slope of the plot of pressure versus time, after ignition, up to maximum pressure
- **minimum ignition energy**: smallest amount of energy in an electric spark which will ignite a flammable mixture
- **heat of combustion**: the energy released as heat when a compound undergoes complete combustion with oxygen under standard conditions

#### 2. APPLICATION TO EXPANSION AGENTS

Combustibility - a blowing agent is commonly stored and processed as a liquid but then turns due to an exothermic reaction between water and isocyanate (and to a lesser extent polyol and isocyanate) into a gas, expanding the still liquid reaction mixture and filling the generated foam cells. Addressing the combustibility of a blowing agent as a liquid is therefore equally important as of MF as a gas. For instance, HCFC-141b is not flammable as a liquid but its vapors may still burn. As it easily generates vapors at ambient conditions it should therefore also be tested for gaseous flammable properties. HCFC-141b is therefore often listed as "moderately" flammable or simply "yes"<sup>5</sup>. Methyl formate, on the other side, is, even as a liquid flammable—which does not necessarily imply explosive. It has a burning profile very much like alcohol, i.e. it burns with a low energy, blue flame and its energy of combustion is very low—much more like HCFC-141b than like pentanes. Following data show this:


Substance	Heat of Combustion (kcal/g)	Comments
HCFC-141b	1.88	
Methyl Formate	3.88	
Pentane (commercial mix)	11.5	Cyclopentane estimated ~10% lower

The low heat of combustion is also the reason that neither HCFC-141b nor MF adds to the fire load of foams the way HCs do. HCFC-containing polyol systems generally are non flammable and the same is the case for MF—within certain limits.

Finally, a low heat of combustion decreases the **explosion pressure** and the **maximum rate of pressure rise** as the following picture shows (courtesy FSI):

<sup>&</sup>lt;sup>4</sup> Panov, G.E. and Polozkov, V. T.. "Flammable Substances", Encyclopedia of Occupational Health and Safety, 3<sup>rd</sup> Edition, International Labor Office Geneva, pp. 881-883 (1983)

<sup>&</sup>lt;sup>5</sup> Lavelle, J. P., "Flammability Characteristics of HCFC 141b and HCFC-142b", Journal of Fire Sciences 1989 7; pp 426-439



**Flash Point** is commonly the primary property to describe the fire hazard of a **liquid**. Pure MF, with its flashpoint of -32° C certainly needs proper safeguarding but this changes after blending with a product of no or low combustibility. Tests have shown such systems to be meeting non-flammability labeling criteria by the US-DOT—non-sustained burning at 120° F (ASTM D4206-96)—at MF concentrations <6% for polyols and <2% for isocyanates. Such concentrations suffice to reformulate almost all HCFC-based systems. FSI has this certified through sustained burning tests in September 2005 by the St. Louis testing Laboratories.

**Flammable, Flammability**, or **Explosive** limits are the primary property describing the fire hazard of **gases**. They indicate the proportion of combustible gases in a mixture, between which limits this mixture is flammable. The lower flammable limit (LFL) describes the leanest mixture that is still flammable, i.e. the mixture with the smallest fraction of combustible gas, while the upper flammable limit (UFL) identifies the richest flammable mixture. A **deflagration** is a propagation of a combustion zone at a speed less than the speed of sound in the un-reacted medium. A **detonation** is a propagation of a combustion zone at a velocity greater than the speed of sound in the un-reacted medium. An **explosion** is the bursting, or rupture, of an enclosure or container due to the development of internal pressure from a deflagration or detonation as defined in NFPA 69.

The three essential items for burning a material are fuel, air (or another oxidizing agent), and an ignition source. If there is not enough fuel, the mixture is considered below the lower flammability limit and it will not burn. Once the fuel-air mixture is within the flammable range, there still must be an ignition source present for it to burn (assuming the temperature is less than the auto-ignition temperature). Given a substance has a flammability range, there are several potential scenarios:

Scenario	Mitigating Action
The LFL will not be approached	No action required
The LFL can be approached or exceeded	Exhaust will keep the space under LFL
The LFL will be exceeded	Spark arrestors will keep the space free of ignition sources

The mitigation actions for the latter two scenarios are frequently combined and completed with an early warning system (sensors with alarm function).

#### 3. APPLICATION TO METHYL FORMATE

# UNDP - METHYL FORMATE ASSESSMENT - 62<sup>ND</sup> EXECUTIVE COMMITTEE MEETING

For neither HCFC-141b nor methyl formate the LFL will be even remotely be approached under standard process conditions (ambient temperatures 15-40 °C; substance emissions under legal exposure limits) as the following calculations show:

#### Methyl Formate

- LEL = 5% in air by volume =  $125 \text{ g/m}^3 = 50,000 \text{ ppm}$
- Maximum concentration allowed by OSHA.NIOSH/ACGIH:
  - TWA = 100 ppm = 250 mg/m<sup>3</sup> = **0.20% of LFL**
  - STEL = 150 ppm = 375 mg/m<sup>3</sup> = **0.30% of LFL**

#### HCFC-141b

- LEL = 7.4% in air by volume =  $925 \text{ g/m}^3 = 193,000 \text{ ppm}$
- Maximum concentration allowed (WEEL):
  - TWA =  $500 \text{ ppm} = 2.4 \text{ g/m}^3 = 0.26\% \text{ of LFL}$
  - STEL = 3,000 ppm =  $14.4 \text{ g/m}^3 = 1.56\% \text{ of LFL}$

#### 4. CONCLUSIONS

- Methyl formate as a pure liquid is very flammable and requires proper safeguards. The risk of explosion is, however, remote because its low heat of combustion;
- A PU system base on methyl formate can be formulated as a low combustible liquid and will not reach the LFL even in the drum's head space; and
- There is no reason to treat methyl formate differently from HCFC-141b.

#### ATTACHMENT V: REVERSE HEAT FLOW TESTS (SUMMARY, DETAILED VERSION IN SEPARATED FILE)

#### **INTRODUCTION**

**Reverse heat flow testing** can be used to determine the heat flowing through the product which must be removed by the cooling system. This testing provides a measurement of the comparative efficiency of a cooling system in which insulation foam is one of the components. By keeping all other parameters the same, the comparative insulation performance of one insulation component can be measured. In this case this is applied to comparing different foam types.

Foam Supplies, Inc. (FSI commissioned this test in March 2008 as part of a program to support customers in achieving Energy Star performance for their appliance products. The test, however, also provides a comparison between the insulation performance of HCFC-141b and methyl formate.

#### **TEST METHOD**

Two identical freezer chest were used, one with methyl formate blown foam and one with HCFC141b foam. Each chest was heated by one light bulb of 40W at an ambient temperature of  $4.40^{\circ}$  C. The chests were fed from one energy source (= same voltage) for 24 hours. The temperature at that point was

89.890 F for the HCFC-141b foam 88.6640 F for the methyl formate foam

Difference 1.25° F or 0.7° C

The test was repeated with a 100W lamp at an ambient temperature of -17.8° C. Tis time the temperatures were

86.01<sup>0</sup> F for the HCFC-141b foam 84.73<sup>0</sup> F for the methyl formate foam

Difference 1.27° F or 0.7° C

The differences are deemed by the industry as negligible

## **CONCLUSION**

HCFC-141b and methyl formate blown foams perform virtually identical in energy loss.

Details of the tests are on file.

#### ATTACHMENT VI: LONG TERM PERFORMANCE (SUMMARY, DETAILED VERSION IN SEPARATED FILE)

#### INTRODUCTION

The purpose of this study is to evaluate the long-term performance of MF-blown foams. A number of parts of various types from a variety of industries were stored in a warehouse at ambient conditions for a minimum of 5 years. Similar parts were foamed and tested when initially trialed and the results of those tests were used as the baseline for this study.

#### **INSULATION VALUE**

An insulated shipping container manufactured on July 12, 2002 was after 5 years retested in accordance with the original test method. A block of dry ice was placed into the container and the lid closed and sealed with shipping tape. Ambient temperature was 70·F. The temperature inside the box was measured with a thermocouple and allowed to stabilize for 1 hour before reaching stasis. This initial temperature was measured and the test began from there. The interior temperature was then measured and recorded every 24 hours. The results are as follows:

Inside Temperature	Initial Testing July 13-15, 2002	Retesting November 10-12, 2008
24 hours	No change	1 <sup>0</sup> F increase
48 hours	4 <sup>0</sup> F increase	6 <sup>0</sup> F increase
72 hours	6 <sup>0</sup> F increase	8 <sup>0</sup> F increase

In another test, Individual samples were taken from three commercial refrigerators to compare insulation values from when they were originally foamed and five years later. The refrigerators were stored under ambient conditions in a warehouse. Samples were tested at different temperatures relating to their particular end-use but all follow-up testing was run at the same temperatures as the original test. Sample were tested In following ASTM-C 518: "Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus". The results are as follows:

Application	Test temperature (°F)	Δ k Factor
Cold Vending Machine	75	+1.2%
Cold Vending Machine	77	+2.4%
Glass front reach-in Cabinet	55	+12.5%

#### THERMAL STABILITY

Soft drink dispensers with exposed foam skins were tested using the "Ice Melt" method according to industry standards. One gallon plastic jugs were filled with equal amounts of tap water and then frozen. Lids for the units were constructed from identical pieces of e>.1:ruded polystyrene to make the test consistent between units. A jug of ice was placed into each unit and the lid placed on top. At 24 hour intervals the water was poured off each jug and the jug was then reweighed to calculate the melt. All units were tested at 75 'F ambient to simulate a convenience store atmosphere. Test -Identical units were constructed and tested using foam systems blown with different blowing agents. The test units were foamed with an ecomate system and the control units were foamed with the manufacturer's current HFC-134a system. The test was designed to measure both the difference in insulation value when it is made and after multiple years in the field. The results were that after more than five years storage, the unit foamed with MF showed 0.5% more loss in insulation value over time than the HFC-134a control. Neither unit exhibited a change in physical dimensions greater than 1%.

#### **DIMENSIONAL STABILITY**

More than 20 foam parts were stored under ambient conditions in a warehouse for 5 years. The parts included exposed skin soft drink dispensers, ice bins, rotomolded food service carriers, doors and walk-in cooler panels. All parts remained stable after 5 years. The worst part exhibited less than 3.5% change in any direction.

## **QUESTIONNAIRES ON CHILLER PROJECTS**

Brazil: progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)

Colombia: progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)

Cuba: progress report on the demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP and Canada)

Syrian Arab Republic: Progress report on the demonstration project on the replacement of CFC centrifugal chillers (UNIDO)

Global: progress report on the global chiller replacement project (China, India, Indonesia, Jordan, Malaysia, Philippines, and Tunisia) (World Bank)

Region – Africa: progress report on strategic demonstration project for accelerated conversion of CFC chillers in 6 African countries (Cameroon, Egypt, Namibia, Nigeria, Senegal and Sudan) (UNIDO, France, Germany, and Japan)

Region – Europe: progress report on demonstration project on the replacement of CFC centrifugal chillers (Croatia, the former Yugoslav Republic of Macedonia, Montenegro, Romania, and Serbia) (UNIDO)

Region – Latin America and the Caribbean: demonstration project for integrated management of the centrifugal chiller sub-sector in the Caribbean, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-based chillers (UNDP)

Project data					
	Demonstration project for integrated management of the centrifugal chiller sub-sector, focusing on application of energy -				
	efficient CFC-free technologies for replacement of CFC-based chillers				
Approved at [ExCom Meeting]	47th				
Country/countries/region covered	Brazil				
MLF funding approved	1,000,000				
Minimum co-funding requirement	252,000				
Source(s) of co-funding as envisaged in project proposal (amount envisioned	GEF: US\$ 1 Millio	n			
Number of chillers to be replaced	12				
Lead agency	UNDP				
MLF funding associated			1,000,000		
Other agencies/bilaterals	Agency 1	Agency 2	Agency		
Name	•	-	-		
Responsibility	-	-	-		
MLF funding associated	-	-	•		

assessment (provide some <u>brief</u> text, please; bullet points also pos	
General experience	Ensuring cofinancing and starting the project took more than two years. Being one of the first experiences to combine d sources of funding for climate change mitigation and ozone protection, it has been difficult to achieve a timely combinat the two sources due to different policy frameworks and project cycles managed. However, valuable experience has bee gained on this issue for future comparable initiatives under GEF 5. As reported in previous years GEF requested to incl finance institution as the administrator of the performance/risk guarantee financial instrument/business model. UNDP do capacity strengthening, technical and financial assistance to public buildings and the financial institution administer the sector portion. The project received CEO endorsement in July 29, 2009 and the project document for the GEF was sign first meetings under the framework of the two projects took place. Current situation of the MLF component is being anal the delay in obtaining the cofinancing may have generated changes in the original situation.
Greatest challenges	As reported in previous years the main challenge was related to the obtention of the cofinancing that took several years.
Lessons learned	See above
Did you work with both public and private owners, and if yes: was there a different policy/approach needed for the two?	The project, which is in initiation phase, covers work with both private and public owners. According to information colle during project preparation it appears that working with private owners may be easier as the system to receive the saving the energy gains is simpler, the owner invests in the conversion and the owner saves in the energy bill. Budgets are less simple in the public sector, for instance, in some cases the process required to obtain approval for the investment is long in other occasions the monetary savings from the energy gains are not necessarily received by the same department the decides to undertake the investment on the chiller, and this could make the process more complex.
Remarks on interest by chiller owners / did you experience good co- operation / did the quality of interaction change with time? Remarks on interest by chiller owners	Chiller owners are interested and in expectation that the project removes the main barriers for them to undertake the investment. Interaction was limited during the period taken to obtain the cofinancing required to start the project; however that this is resolved, the project is starting and closer interaction with the chiller owners is expected to be restablished.
Expected results beyond chillers funded: (e.g.: Will the demonstration lead to more chillers being replaced, if yes how concrete is that understanding? If no why is that assumed?)	It is expected that the demonstration will provide the elements to other chiller owners to invest in their chillers conversion GEF project cofinancing this demonstration will establish the conditions to replicate the conversions done through the M project by any chiller owner interested.
Reasons for delays	Move from GEF 3 to GEF 4 and need to get RAF allocation approved by the Government, a decision out of the control of National Ozone Unit. Introduction of the financial institution required redrafting of the proposal, and due diligence process financial institution took longer than expected. Process of signature of project document for the combined initiative (GEF MLF) could only start once the two approvals cycles were completed. Project document is now signed and several meet among the stakeholders have taken place.
Experience with funding organisations	See above
How do you see the potential of replication of this approach for other sectors?	Some elements of the present approach such as the combining of funding could be explored for early appliances retiren programmes. Chillers projects and early domestic appliances retirement approaches are two of the identified sources of for destruction in Brazil and other countries.
Would you say that this co-funding experience was positive?	It had positive and negative elements. It was positive because was successfully materialized, the negative part was the of several years to obtain the minimum cofinancing to start the project.
Should a similar approach be taken in the future again, what are	a) and b) Better coordination with other funding bodies would ensure timely cofinancing and avoid delays. c) Coordination
your suggestions for improvements a) related to the MLF; b) related to other donors (where relevant); c) related to implementation and	the Ministry of Energy is necessary to undertake projects that involve energy efficiency, a strong commitment from this N is very important to support project implementation. During the project implementation new areas of improvement will be
co-operation with stakeholders and the country; d) related to other	identified.
	N.A.

Co-funding information

Co-funding information					
Per approved co-funding	1st co-funding	2nd co-funding	co-funding		Refers to all co-financing that materialised
Co-funding institution	GEF	IDB	Private Sector	Government	GEF cofinancing
	GEF	IND	FIIVALE SECIOI	Government	GET COMMANDING
Name, purpose of programme					
Amount approved in total (currency)	13,750,000	15,000,000	50,000,000	165,000	
Was this co-funding foreseen in the original submission to the	.,,	-,,	, , ,	1	
	Vaa	No	Vaa	Na	
47th/48th Meeting?	Yes	No	Yes	No	yes/no
			It was expected during		
			project preparation but		
If yes: Did the amount change (please provide from to)	from 350,000 to 13,750,000		there was no estimation		
ii yes. Did tile amodili change (please provide nom to)	110111 330,000 to 13,730,000		there was no estimation		
		GEF requested the need for a			
		financial institution. UNDP			
If no: When (approx.) did you become aware of this		had to contact as per		During GEF project	Explain briefly: 2, 3 sentences (separate below) or some
ii no. when (approx.) did you become aware of this					
possibility, and how? Please explain briefly		instruction of the GEF		preparation	bullet points
How much of the cofinancing constitutes project costs in the					
MLF definition (see letter from MFS)	2.5				
	3.5				
Date of approval	14-Jun-07	14-Jun-07	14-Jun-07	14-Jun-07	
	CEO Endorsement received	To be used in the Partial			
		Performance Guarantee			e.g. for replacing chillers in hospitals in country x; for
Major conditions associated	document signed.	Mechanism			replacing one system in institution y;
Additional activities severed (if and A. (F. a., France, "	CEE project course East	OFF project contract			
Additional activities covered (if any): (E.g.: Energy efficiency	GEF project covers Energy	GEF project covers Energy			
program for building,)	Efficiency for buildings	Efficiency for buildings	1		
- '	j				
	Deced on projectle Ever-		I		
	Based on project's Excom		I		
	condition. 100% of the MLF		I		
	approval can be released				
Funds saread by the MECts he released based on that					
Funds agreed by the MFSto be released based on that	now as the minimum				
approval	cofinancing was ensured.				
	MLF project disbursements				
Date of related release of Funds by the MFS	have not started yet.				
· · · · · · · · · · · · · · · · · · ·	·				
	1	I			I
Per co-funding presently sought	1st co-funding	2nd co-funding	co-funding		Explanations
Co-funding institution	Not Applicable				
Name, purpose of programme	''				
Amount sought in total					
How much of that constitutes project costs in the MLF					
definition					
Expected approval					
Reasons for the delay					
Major conditions associated					
Additional activities covered (if any): (E.g.: Energy efficiency					
program for building,)					
				<u> </u>	<del></del>
Co-funding sources previously pursued but subsequently	ĺ		ĺ		
	Ant an founding	Ond on two diam	and the state of		Fundamentana
<u>abandoned</u>	1st co-funding	2nd co-funding	co-funding		Explanations
Co-funding institution	Not Applicable				
Name, purpose of programme					
	<del> </del>		<del> </del>		
Amount sought in total	ļ				
How much of that constitutes project costs in the MLF	1		I		
definition			1		
	<del> </del>		<del> </del>		
When was the quest for co-funding from this			1		
institution/programme abandoned?	<u> </u>		<u>                                     </u>	<u>                                     </u>	
Reasons for the decision					
	t.		ı.	1	l.
					_
	1				
Additional external resources acquired for the chiller phase-out	1st co-funding	2nd co-funding	co-funding		Explanations
Co-funding institution	Not applicable		1		p ==
	INOL APPIICADIE				
Name, purpose of programme					
Amount sought in total		-			
How much of that constitutes project costs in the MLF					
			1		
definition					
When was the quest for co-funding from this			I		
institution/programme abandoned?			1		
Reasons for the decision					
reasons for the decision					
· · · · · · · · · · · · · · · · · · ·			· · · · · · · · · · · · · · · · · · ·		

General information		Explanations
How many chiller users have been	1250	
identified in the country		
How many chillers remain?	TBD	The original estimation will be reconfirmed or updated as part of the project
		implementation.
How many belong to the public	TBD	The original estimation will be reconfirmed or updated as part of the project
sector? How		implementation.
many to the private sector?		
What share of the country's chiller users	90%	
have been identified (estimated)		
Have there been agreements planned with	Yes	The Interamerican Development Bank will participate in the project and will
other institutions to facilitate		administer the Partial Performance Guarantee Risk Mechanism.
implementation or lending? If yes, please		
elaborate briefly		

or (main) activity	Activity 1	Activity 2	A otivity 2	A otivity	Evalenations
er (main) activity	Activity 1	Activity 2	Activity 3	Activity	Explanations
Type of activity	Enhancing EE	Access to EE	Interest enhanced		e.g.: Chiller replacement / Chiller retrofit / Workshop /
		services and	in the replacement	Guarantee	
		commercial financing		Mechanism (PPGM)	
		for public sector	CFC-using chillers	made available to	
		buildings enhanced		stimulate EE	
		with a public building		investment through	
		initiative		ESCOs	
Country	Brazil	Brazil	Brazil	Brazil	
Country	GEF CEO			GEF CEO	Operation of the district of the first of the section of the secti
Status		GEF CEO	GEF CEO		Completed, new chiller fully functional/largely completed, new chiller
	endorsement	endorsement	endorsement	endorsement	delivered and in the process of installation and trial/partially completed, n
	received. Project	received. Project	received. Project	received. Project	chiller delivery expected / Tendering complete and contract issued /
		document signed.	document signed.	document signed.	Tender process ongoing / Preparation of tender process // Workshop
		Inception Workshop			
		completed. Project		completed. Project	provide copy)
		manager appointed.		manager appointed.	
	Project Steering	Project Steering	Project Steering	Project Steering	
	Committee planning	Committee planning	Committee planning	Committee planning	
	meetings took	meetings took place.	meetings took	meetings took	
	place.		place.	place.	
	ľ		ľ		
case of chiller replacements					
Owner, use					e.g. "city of x", "hospital cooling"
					jerge ony er er, weep name er en eg
When was the agreement with the owner					
concluded					
(Expected) Status of completion					
Actual cost with a break down by					
equipment					
installation					
1					
construction					
Information on energy efficiency					
Original technology					
Age of chiller being replaced					
Original capacity					
Replacement technology					(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-chiller)
Replacement capacity					[please provide unit = kW or tons]
Assumed / measured change in energy efficiency					(from/unit to /unit)
onorgy officiality	1		1	1	1

Project data						
Title	Demonstration Project for integrated management of the centrifugal chiller sub-sector, focusing on applications of energy-efficient CFC-free					
Approved at [ExCom Meeting]	47th					
Country/countries/region covered	Colombia					
MLF funding approved	1,000,000					
Minimum co-funding requirement	705,000					
Source(s) of co-funding as envisaged in project proposal (amount envisioned	GEF: US\$ 1 Millio	on				
Number of chillers to be replaced	13					
Lead agency	UNDP					
MLF funding associated	1,000,000					
Other agencies/bilaterals	Agency 1	Agency 2	Agency			
Name	-	-	-			
Responsibility	-	-	-			
MLF funding associated	-	-	-			

assessment (provide some brief text, please; bullet points also possi	,
General experience	As of Today the main experience gained has been the capacity to combine funding from different sources to tackle the climate change an ozone challenges. Being one of the first experiences to combine these sources of funding it has been difficult to achieve a timely combina the two sources due to different policy frameworks and project cycles managed. Valuable experience has been gained on this issue for fur comparable initiatives under GEF 5. With regards to the status of the GEF cofinancing, MSP was approved and cofinancing was therefore officially obtained.
	Obtaining Cofinancing
	See above
	The project, which is in initiation phase, covers work with both private and public owners. According to information collected during project preparation it appears that working with private owners may be easier as the system to receive the savings from the energy gains is simple owner invests in the conversion and the owner saves in the energy bill. Budgets are less simple in the public sector, for instance, in some the process required to obtain approval for the investment is long, or in other occasions the monetary savings from the energy gains are necessarily received by the same department that decides to undertake the investment on the chiller, and this could make the process mo complex.
Remarks on interest by chiller owners / did you experience good co-	Chiller owners are interested and in expectation that the project removes the main barriers for them to undertake the investment. The qual the interaction decreased due to the long time required to obtain the cofinancing required to start the project; however, now that this is result the project is starting, the NOU will focus on improve the interaction with the chiller owners again.
Expected results beyond chillers funded: (e.g.: Will the demonstration lead to more chillers being replaced, if yes how	1. While removing the barriers for conversion to non-CFC energy efficient chillers, it is expected that other additional chillers will be benefit from the project as the owners will be able to benefit from the favourable regulatory and financial conditions package set by the project (bu model for market transformation). 2. In addition, through the cofinancing the promotion of energy efficiency will extend to create a comprehensive program for energy efficiency in buildings with the following main outcomes: development of regulations to promote energy efficiency in buildings, stimulation of the demand and supply for energy efficiency and creation of awareness and capacity to take advanta the market opportunities presented by building energy efficiency.
	Cofinancing procurement took longer than expected due to the change of operational procedures in the GEF (improvements on the projec introduction of the PIF and PPG instead of PDF A and PDF B, etc) and creation and inclusion of the project in the Resource Allocation Framework established for the country. As the Resource Allocation Framework consists on a limited allocation of funds for projects in Clim Change the final decision on what projects are submitted is out of the National Ozone Unit control. Several changes were done to the cofinancing proposal to have a comprehensive energy efficient buildings project, this generated additional delays.
	For future initiatives where MLF and GEF funding could be combined, coordination among the two funds will be an added value as it will a synchronizing project cycles.
	N.A.
How do you see the potential of replication of this approach for	Some elements of the present approach such as the combining of funding could be explored for early appliances retirement programmes. Chillers projects and early domestic appliances retirement approaches are two of the identified sources of CFC for destruction in Colombia other countries.
Would you say that this co-funding experience was positive?	It had positive and negative elements. It was positive because was successfully materialized, the negative part was the delay of several ye obtain the minimum cofinancing to start the project.
your suggestions for improvements a) related to the MLF; b) related	a) and b) Better coordination with other funding bodies would ensure timely cofinancing and avoid delays. c) Coordination with the Ministry Energy is necessary to undertake projects that involve energy efficiency, a strong commitment from this Ministry is very important to support project implementation. During the project implementation new areas of improvement will be identified.

Co-funding information

approved co-funding	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialised
Co-funding institution	GEF	Government of Colombia	<u> </u>	- Control of the cont
Name, purpose of programme	Cofinancing obtained	Sales Taxes Exemption		
rvanie, purpose or programme		Cales Taxes Exemption		
	through a Medium Size			
	Project submitted to GEF			
	under the Climate Change			
	Focal Area: 'CO-			
	EFFICIENCY', Improving			
	Energy Efficiency in			
	Buildings in Colombia			
	through Synergies between			
	Environmental			
	Conventions.			
	Conventions.			
Amount approved in total (ourroppy)	1 000 000	Reduction of the Sales		
Amount approved in total (currency)	1,000,000	taxes (16%) for the		
		materials procured by		
		chiller owners during		
		chillers conversion. Final		
		value will be known at the		
		end of the project when all		
		the conversions take		
		place.		
Was this co-funding foreseen in the original submission to the 47th/48th Meeting?	Yes	Yes		yes/no
If yes: Did the amount change (please provide from to)	Minimum cofinancing as	No		
	per Excom approval was			
	705,000.			
If no: When (approx.) did you become aware of this	703,000.			Fundain briefly: 2, 2 contenses (conserts below) or come bullet noi
				Explain briefly: 2, 3 sentences (separate below) or some bullet poi
possibility, and how? Please explain briefly				
How much of the cofinancing constitutes project costs in the	975,000 will be used in the	It covers only activities		
MLF definition (see letter from MFS)	activities related to the	directly related to the		
WEET GENINITION (SEE TELLET HOTH WIFS)				
	project, 25,000 were used	chillers replacement.		
	in the preparation of the			
	GEF Medium Size Project.			
Data of approval	Octobor 7 2000	Available to chiller		
Date of approval	October 7 2009	Available to chiller		
Date of approval	October 7 2009	onwners when purchasing		
Date of approval	October 7 2009			
Date of approval	October 7 2009	onwners when purchasing		
		onwners when purchasing elements for the		e.g. for replacing chillers in hospitals in country x: for replacing on
	Signature of document in	onwners when purchasing elements for the		
Date of approval  Major conditions associated	Signature of document in Oct 2009 (accomplished),	onwners when purchasing elements for the		e.g. for replacing chillers in hospitals in country x; for replacing on system in institution y;
	Signature of document in Oct 2009 (accomplished), closing date of the project	onwners when purchasing elements for the		
	Signature of document in Oct 2009 (accomplished), closing date of the project July 2012 and Final Report	onwners when purchasing elements for the		
	Signature of document in Oct 2009 (accomplished), closing date of the project	onwners when purchasing elements for the		
Major conditions associated	Signature of document in Oct 2009 (accomplished), closing date of the project July 2012 and Final Report	onwners when purchasing elements for the		
Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency	Signature of document in Oct 2009 (accomplished), closing date of the project July 2012 and Final Report 6 months after.	onwners when purchasing elements for the		e.g. for replacing chillers in hospitals in country x; for replacing one system in institution y;
Major conditions associated	Signature of document in Oct 2009 (accomplished), closing date of the project July 2012 and Final Report 6 months after.  Strengthening of government institutions in	onwners when purchasing elements for the		
Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency	Signature of document in Oct 2009 (accomplished), closing date of the project July 2012 and Final Report 6 months after.  Strengthening of government institutions in charge of promoting EE.	onwners when purchasing elements for the		
Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency	Signature of document in Oct 2009 (accomplished), closing date of the project July 2012 and Final Report 6 months after.  Strengthening of government institutions in charge of promoting EE. Establish policies to	onwners when purchasing elements for the		
Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency	Signature of document in Oct 2009 (accomplished), closing date of the project July 2012 and Final Report 6 months after.  Strengthening of government institutions in charge of promoting EE. Establish policies to promote EE in buildings.	onwners when purchasing elements for the		
Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency	Signature of document in Oct 2009 (accomplished), closing date of the project July 2012 and Final Report 6 months after.  Strengthening of government institutions in charge of promoting EE. Establish policies to	onwners when purchasing elements for the		

Funds agreed by the MFS to be released based on that approval	100%. The cofinancing level obtained from the GEF MSP is above the minimum required as per the Excom condition associated to the project.			
Date of related release of Funds by the MFS				
Per co-funding presently sought	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution			Chiller owners	
Name, purpose of programme				
Amount sought in total				
How much of that constitutes project costs in the MLF definition	1			
Expected approval	7			
Reasons for the delay	7			
Major conditions associated	7			
Additional activities covered (if any): (E.g.: Energy efficiency	1			
program for building,)				
Co-funding sources previously pursued but subsequently abandoned	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution	+			
Name, purpose of programme	+			
Amount sought in total				
How much of that constitutes project costs in the MLF definition				
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this				
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?				
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this				
How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision				
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?	1st co-funding	2nd co-funding	co-funding	Explanations
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  Additional external resources acquired for the chiller phase-out  Co-funding institution	1st co-funding	2nd co-funding	co-funding	Explanations
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  Additional external resources acquired for the chiller phase-out  Co-funding institution  Name, purpose of programme	1st co-funding	2nd co-funding	co-funding	Explanations
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  Additional external resources acquired for the chiller phase-out  Co-funding institution  Name, purpose of programme  Amount sought in total	1st co-funding	2nd co-funding	co-funding	Explanations
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  Additional external resources acquired for the chiller phase-out  Co-funding institution  Name, purpose of programme	1st co-funding	2nd co-funding	co-funding	Explanations
How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  Additional external resources acquired for the chiller phase-out  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding	co-funding	Explanations
How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  Additional external resources acquired for the chiller phase-out  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF	1st co-funding	2nd co-funding	co-funding	Explanations

General information					Explanations
How many chiller users have been identified in the country?				50	
How many chillers remain?				TBD	The original estimation will be reconfirmed or updated based on the study being completed as part of the project implementation.
How many belong to the public sector? How many to the private sector?				TBD	The original estimation will be reconfirmed or updated based on the study being completed as part of the project implementation.
What share of the country's chiller users have been identified (estimated)				13	This is the number of chillers expected to be included in the demonstration. The project will create the conditions for the remaining chillers to be converted.
Have there been agreements planned with other institutions to facilitate implementation or lending? If yes, please elaborate briefly	Yes				The project will identify the bank-partner that will manage the fund. The project will work with the bank to detail the loan structure for the program including interest rate and loan term.
lending: If yes, please classified shelly					
Per (main) activity	Activity 1	Activity 2	Activity 3	Activity	Explanations
Type of activity	Identification and mitigations of risks	Validating business model	Assess success of demo projects	Put in place conditions for implementation	e.g.: Chiller replacement / Chiller retrofit / Workshop /
Country	Colombia				
In case of chiller replacements	Cofinancing obtained. Project documents for GEF and MLF projects signed by the parties. Local expert to undertake updated inventory of chillers including characterization of each one of the units in service and diagnosis of the required investment for conversion being contracted. In parallel, discussions with international expert and private companies are taking place to analyse the possibility to migrate to alternative technologies with low GWP additional to the ones considered in the design of the project.	the financial instruments available and select the most	Application of the business model in the 13 chillers will take place once these studies in Activity 1 and Activity 1 and Activity 2 are completed.	This activity will take place after activity 3 is completed. Results from the demonstrative conversions will be disseminated through a workshop and will also be published.	Completed, new chiller fully functional/largely completed, new chiller delivered and in the process of installation and trial/partially completed, new chiller delivery expected / Tendering complete and contract issued / Tender process ongoing / Preparation of tender process // Workshop planned / Workshop held (when?) / Results published (when? Please provide copy)
					a a "city of y" "hoopital cooling"
Owner, use					e.g. "city of x", "hospital cooling"
When was the agreement with the owner concluded					
(Expected) Status of completion					
Actual cost with a break down by	T	T	ı	1	
equipment					
installation					
construction					
Information on energy efficiency					
Original technology					
Age of chiller being replaced					
Original capacity Replacement technology					(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-chiller)
Replacement capacity					[please provide unit = kW or tons]
Assumed / measured change in energy efficiency					(from/unit to /unit)
Assumed annual saving in energy					(in kWh)

Project data			
	Demonstration pr	oject for integrat	ed management of the centrifugal chiller sub-sector in Cuba, focusing on
Title	application of ene	rgy-efficient CF0	C-free technologies for replacement of CFC-based chillers
Approved at [ExCom Meeting]	47th		
Country/countries/region covered	Cuba		
MLF funding approved	984,353 US\$ plus	s support cost	
Minimum co-funding requirement	410,125 US\$		
Source(s) of co-funding as envisaged in project proposal (amount envisioned			
and currency in brackets)	Canada (public ar	nd private), UND	P Thematic Trust Fund on Energy, and Cuban Government
	Replace 7 chillers	and convert 5 of	chillers (this target was revised with the Secretariat before ExCom 53 in
Number of chillers to be replaced	2007)		
Lead agency	UNDP		
	All funds are now with UNDP. Funds initially approved to Environment Canada has been transferred to UND		
MLF funding associated	at ExCom 51.		
Other agencies/bilaterals	Agency 1	Agency 2	Agency
Name			
Responsibility			
MLF funding associated			

Its / assessment (provide some brief text, please; bullet points also po	ossible)
General experience	The implementation of the chillers project in Cuba is now well on track, though it has faced several lengthily delays in the process. 4 Chillers have now been replaced and they are currently being tested before they go into full operation. Several technical issues have been detected and are in the process of being fixed. 5 additional Chiller sites are currently being prepared for the installation of the remaining 5 chillers. All the equipment is in Cuba, and we expect the process to finish before the end of the year. All co-finance has been secured. There is a high commitment from the government of Cuba, and Environment Canada has played an instrumental role in assuring the co-finance from Private and Public Sector in Canada, as well as with the coordination of all the stakeholders.
Greatest challenges	There have been different challenges in different stages of the project. Initially it was complicated to get the cofinance assured. The company that was interested in doing chiller retrofits left the project at a late stage, and thereby leaving the project in a complicated state. This situation was discussed with the Secretariat, and the agreement was to increment the number of chillers replacements as well as removal of additional chillers (where one new chiller replaces two old ones). Later on there have been some technical challenges that needed to be resolved. In 2008 Hurricane Ike caused tremendous damage to Cuba and to several of the buildings where we are in the process of replacing chillers. One chiller compressor got damaged during the hurricane, and we will have to replace one of the compressors. This is the first time this kind of chillers will be installed in an article 5 country in LAC, and it has also generated some challenges for the chiller manufacturer. Most of the problems have been solved, and we expect to finish the installation of the remaining chillers soon.
Lessons learned	The need to raise additional co-finance in a MLF project substantially delays the implementation process.
Remarks on interest by chiller owners	The government of Cuba has so far been very satisfied with the project.
Expected results beyond chillers funded: (e.g.: Will the demonstration lead to more chillers being replaced, if yes how concrete is that understanding? If no why is that assumed?)	It is expected that the current project will promote chillers replacement in Cuba. There are still many old CFC based chillers left in Cuba. This project will show that new and advanced technology works in Cuba and generates large energy savings.
Reasons for delays	See above - Co-finance issues, bureaucratic challenges, technical challenges, hurricane lke.
Experience with funding organizations	Very positive experience with the Canada (Private and Public sector co-finance)
Impact on the chiller market in the relevant country/countries; market transformation observed	All chillers are owned by the government of Cuba. No market transformation will take place. The purpose of this project is to test a new technology in an article 5 context.
Other remarks and/or explanations	Prices of raw materials and thereby chillers have increased since the development and approval of the project.

Co-funding information

er approved co-funding				
	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialized
Co-funding institution	Government of Canada	Private Sector Canada	UNDP	
			T	
	Technology Early Action Measures		Thematic Trust Fund for	
Name, purpose of programme	(TEAM) by the Government of Canada	Chiller producer	Energy	
Amount approved in total (currency)	655,000 CAD	335.000 CAD	40.000 US\$	
ranount approved in total (carrelley)	000.000 07.15	not explicitly. Co-finance from public	10.000 000	
Was this co-funding foreseen in the original submission to the	Co-finance from Canada was foreseen	and private sector in Canada was		
47th/48th Meeting?	though not negotiated at that stage.	mentioned.	yes	yes/no
· ·	amount was not specified in original			
	document. The negotiated amount is			
	higher than the external resources			
If yes: Did the amount change (please provide from to)	required by ExCom 47.		no	
ii yes. Dia tile amount change (piease provide nom to)	required by Excont 47.		110	
		Environment Canada identified the		
		possibility of requesting funds from		
If any Mile and Community of the Communi				F
If no: When (approx.) did you become aware of this possibility,		TEAM and with private sector		Explain briefly: 2, 3 sentences (separate below) or some
and how? Please explain briefly		participation.		bullet points
How much of the co financing constitutes project costs in the				
MLF definition (see letter from MFS)	All of it	Most of it.	Most of it	
Date of approval	2007	2007	2006	
		200.	2000	
	Must demonstrate Canadian	l	L	
	technology, and must generate climate	Is dependent of approval of TEAM	Support the implementation of	e.g. for replacing chillers in hospitals in country x; for
Major conditions associated	benefits.	funds (which already happened)		replacing one system in institution y;
Iviajor corruitions associated	Deficitio.	runus (which already happened)	trie Crimera project in Cuba.	replacing one system in institution y,
		yes, training of Cuban technicians in	Regional workshop to	
Additional activities covered (if any): (E.g.: Energy efficiency		Canada, translation of technical	disseminate results from	
program for building,)	no	manuals, site visits in Cuba, etc.	project.	
Funds agreed by the MFS to be released based on that			1 - 1 - 1	
	204.050.1100	204.050.1100	004.050.1100	
approval	984.353 US\$	984.353 US\$	984.353 US\$	
Date of related release of Funds by the MFS	Oct-07			
er co-funding presently sought	1st co-funding	2nd co-funding	co-funding	Evalenations
	TSL CO-TUNGING	zna co-tunaing	co-iunding	Explanations
Co-funding institution				
Name, purpose of programme				
Amount sought in total				
How much of that constitutes project costs in the MLF				
definition				
ueiiiiiiuii				
Expected approval				
Expected approval Reasons for the delay				
Expected approval Reasons for the delay Major conditions associated				
Expected approval Reasons for the delay Major conditions associated				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency				
Expected approval Reasons for the delay Major conditions associated				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently	1st confunding	2nd co-funding	confunding	Evaluations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently pandoned	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently andoned Co-funding institution	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently andoned Co-funding institution	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  o-funding sources previously pursued but subsequently bandoned  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned?	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  o-funding sources previously pursued but subsequently bandoned  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) Defunding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned?	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned?	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  o-funding sources previously pursued but subsequently bandoned  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision	1st co-funding	2nd co-funding	co-funding	Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently bandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) Defunding sources previously pursued but subsequently bandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision	1st co-funding	2nd co-funding  2nd co-funding	co-funding	Explanations  Explanations
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  o-funding sources previously pursued but subsequently pandoned  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  dditional external resources acquired for the chiller phase-out Co-funding institution				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  o-funding sources previously pursued but subsequently pandoned  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  o-funding sources previously pursued but subsequently bandoned  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  diditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) Defunding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  diditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently vandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  dditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) ofunding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  dditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  o-funding sources previously pursued but subsequently bandoned  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  ddittional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) ofunding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  dditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently vandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned?				
Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) ofunding sources previously pursued but subsequently pandoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  dditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this				

G	eneral information		Explanations
	How many chiller users have been	According to the original documents there are about 200 chillers in Cuba.	
	identified in the country		
	What share of the country's chiller users	9 new chillers will be installed.	
	have been identified (estimated)		
	Have there been agreements planned with	Environment Canada is playing a key role in project implementation and in securing	
	other institutions to facilitate	co-finance.	
	implementation or lending? If yes, please		
L	elaborate briefly		

er (main) activity	Activity 1	Activity 2	Activity 3	Activity	Explanations
Type of activity	Inspection of	Preparation of sites	Replacement of 4	Replacement of 5	e.g.: Chiller replacement / Chiller retrofit / Workshop /
	chillers sites		chillers	chillers	
Country	Cuba	Cuba	Cuba	Cuba	
Status	Completed. All	Completed. All Chiller	Completed. First	5 additional chillers	Smardt made a mission to Cuba in 2010 where they monitored the
	Chiller sites have	sites have been	four chillers were	were replaced in	operation of the 4 chillers that were installed in 2009, and at the
	been inspected.	prepared.	commissioned in	2010, and all	same time started up the operation / test phase of the final 5 chillers
	· ·	i i	2009 and after a	chillers have now	We are in the process of identifying better ways to continuously
			period of	been replaced in	monitor the operation of the chillers and delegate more responsibility
			troubleshooting,	the project. The 5	to the Cuban technicians in order to be less dependant on Smardt in
			they are now	chillers are in the	the daily operation of the Chillers. Additional training to Cuban
			functioning fine.	process of being	technicians will probably be needed.
				tested, and they	
				should enter in full	
				operation soon.	
				operation soon.	
case of chiller replacements					
Owner, use		Government, 1	Government, 5		e.g. "city of x", "hospital cooling"
		scientific institute.	hospitals.		[g,,pg
		one Theater, 2			
		hospitals.			
When was the agreement with the owner	All sites are owned b	by the government of Cu	ıba	l	
concluded		,			
(Expected) Status of completion					
Actual cost with a break down by	•		•		
equipment			No data	No data	
installation			No data	No data	
construction			No data	No data	
Information on energy efficiency					
Original technology			Centrifugal Chillers	Centrifugal Chillers	
Age of chiller being replaced			Ü	ŭ	
Original capacity			Must be verified. In s	several cases two	
			old chillers will be re	placed with one	
			new.		
Replacement technology			Direct drive variable	-speed oil-free	(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-
. top.dooment toomlology					chiller)
			centrifugal chiller, incorporating magnetic bearing technology		orimor)
l <b>1</b>			1 x 250 TR, 3 x 150		[please provide unit = kW or tons]
Dealessant sansaits				5 X 150 TK	[[please provide unit = kvv or tons]
Replacement capacity			TR		
Assumed / measured change in			No data	No data	(from/unit to /unit)
				No data	(from/unit to /unit) (in kWh)

Project data				
Title	Demonstration project on the replacement of CFC centrifugal chillers			
Approved at [ExCom Meeting]	47	47		
Country/countries/region covered	Syria / West Asia	Syria / West Asia		
MLF funding approved	585,961			
Minimum co-funding requirement	27,195			
Source(s) of co-funding as envisaged in project proposal (amount envisioned				
and currency in brackets)	Counterpart co-financing (US\$ 179,000)			
Number of chillers to be replaced	3 to be replaced and 4 to be retrofitted			
Lead agency	UNIDO			
MLF funding associated	585,961			
Other agencies/bilaterals	Agency 1	Agency 2	Agency	
Name	N/A	N/A	N/A	
Responsibility	N/A	N/A	N/A	
MLF funding associated	N/A	N/A	N/A	

/ assessment (provide some brief text, please; bullet points also poss	sible)
General experience	The overall assessment for the implementation of this project is good because of the interest of the chiller owners, the willingness of the chiller suppliers to engage in the project, the coordination by the NOU and the support of procurement services unit in negotiating and finding solutions to facilitate the project implementation. 2 major difficulties faced UNIDO in implementing this project. 1) huge fluctuations in the exchange rate from EUR to US\$, 2) difficulting the compressors of the chillers to be retrofitted to the USA to perform the retrofit at Trail USA due to the embargo on Syria, 3) the results of the retrofitting are not so efficient nor guarant.
Greatest challenges	as the chiller are old!
Lessons learned	Due to the mentality of chiller owners and the fact that most chillers are publicly owned, having local commercial banks engaged in financing c replacements was found inappropriate.
Remarks on interest by chiller owners / did you experience good co- operation / did the quality of interaction change with time?	The chiller owners were interested and cooperative however it is difficult for the hospital to mobi resources sufficient for the replacement of the chillers as the budget normally covers other medi related expenses.
	The Ministry of Health and the Ministry of Tourism showed high interest in participating in the pro and committed funding beyond that foreseen in the project to complete the project.
concrete is that understanding? If no why is that assumed?) Reasons for delays	It is expected that after the completion of the regional seminar and the dissemination of the demonstration results, more chillers would be replaced.  N/A  N/A
Impact on the chiller market in the relevant country/countries;	The chiller suppliers were involved since the onset of the project, they are engaging in more inte marketing activities and show a lot of competitiveness.
	Yes a project for an early replacement programme of chiller or other equipment would be useful deal with the HCFC service sector.
Would you say that this co-funding experience was positive?	Yes however there is no replication impact.
co-operation with stakeholders and the country; d) related to other	A similar project may be applied to the phase out of HCFC based chillers on a revolving fund bas with some grant subsidy to be given as an incentive. However this needs to be early on in plant the HCFC phase out to allow for sufficient time for the revolving fund to be replenished.

o-funding information				
er approved co-funding	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialised
	Le Meridien Latakia	El-Basel Hospital	i	
Co-funding institution	(Ministry of Tourism)	(Ministry of Health)		
Name, purpose of programme	Counterpart co-financing	Counterpart co-financing		
Amount approved in total (currency)	US\$ 120,000	US\$ 150,000		
Was this co-funding foreseen in the original submission to the		224 120,000		
47th/48th Meeting?	ves	ves		yes/no
47 til/40til Meeting:	the amount foreseen remained the	yes		yes/110
If your Did the account the account of the control		f		
If yes: Did the amount change (please provide from to)	same	from 52,900 to 150,000		Frankis kaistka 0.0 saataasaa /saasaata kalaa
If no: When (approx.) did you become aware of this				Explain briefly: 2, 3 sentences (separate below
possibility, and how? Please explain briefly	N/A	N/A		or some bullet points
How much of the cofinancing constitutes project costs in the				
MLF definition (see letter from MFS)	74,000	100,000		
	Nov - 06			
Date of approval	Funds disbursed in July 2007	Jan-08		
Date of approval	I dilas disbursea in July 2007	Jan-08	1	
				o a for replacing chillers in beenitele in a control
No. 1		l.,		e.g. for replacing chillers in hospitals in country
Major conditions associated	None	None		x; for replacing one system in institution y;
Additional activities covered (if any): (E.g.: Energy efficiency		Replacement of cooling		
program for building,)	None	towers, pipes and water pumps.		
Funds agreed by the MFS to be released based on that		p.p.p.p. a.i.a mater parilpor		
approval	585,	961		
Date of related release of Funds by the MFS	Dec		+	
Date of foldied foldade of funds by the fill o	Dec	-00		
	Ast as for the s	lond on for diam	The second second	Trusten e Cons
er co-funding presently <u>sought</u>	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution				
Name, purpose of programme				
Amount sought in total				
How much of that constitutes project costs in the MLF				
definition				
Expected approval				
Reasons for the delay				
Major conditions associated				
Additional activities covered (if any): (E.g.: Energy efficiency				
program for building,)				
11 - 3				
funding courses provincely nursual but subsequently		1	1	T
o-funding sources previously pursued but subsequently	dat as funding	2nd on funding	an fronting	Evalenations
pandoned Transport of the state	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution				
Name, purpose of programme				
Amount sought in total				
How much of that constitutes project costs in the MLF				
definition				
When was the quest for co-funding from this				
institution/programme abandoned?				
Reasons for the decision				
•	•		•	•
dditional external resources acquired for the chiller phase-out	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution	Tot oo farining	Zna oo-ranang	50-runung	Enployment of the
Name, purpose of programme		+	+	+
				+
Amount sought in total				
How much of that constitutes project costs in the MLF				
definition				
definition When was the quest for co-funding from this				
definition  When was the quest for co-funding from this institution/programme abandoned?				
definition When was the quest for co-funding from this				

General information	Explanations
How many chiller users have been identified	32 CFC-based centrifugal chillers (including those considered under the project)
in the country	
How many chillers remain?	
How many belong to the public sector?	
How many to the private sector?	
What share of the country's chiller users have	All
been identified (estimated)	
Have there been agreements planned with	No
other institutions to facilitate implementation	
or lending? If yes, please elaborate briefly	

er (main) activity	Activity 1	Activity 2	Activity 3	Activity	Explanations
Type of activity	Chiller Replacement	Chiller retrofit	Supplier Seminar		e.g.: Chiller replacement / Chiller retrofit / Workshop /
Country	Syria	Syria	Austria		
Status	Completed	The retrofit of the chillers operating at Al-Basel Hospital is impractical and inefficient as the chillers are old and not well maintained. The implementation has been pending and retrofitting seems not to be possible. A request to consider replacement of the chillers instead of the retrofit was addressed to the Executive Committee through the progress report.	Completed		Completed, new chiller fully functional/largely completed, new chiller delivered and in the process of installation and trial/partially completed, new chiller delivery expected / Tendering complete and contract issued / Tender process ongoing / Preparation of tender process // Workshop planned / Workshop held (when?) / Results published (when? Please provide copy)
case of chiller replacements					
Owner, use	Hotel Le Meridien, Cooling of hotel rooms, offices and public areas	Al-Basel Hospital, Latakia "Hospital Cooling"			e.g. "city of x", "hospital cooling"
When was the agreement with the owner concluded	Nov-06	Nov-08			
(Expected) Status of completion	Dec-08	Jun-11			
Actual cost with a break down by	200 00	04.11		1	
equipment	435,000	180,000			
installation	28,000 including a 3 year maintenance contract.	O			
construction	Counterpart responsibility locally!	Counterpart responsibility			
Information on energy efficiency		İ			
Original technology	CFC-12, centrifugal				
Age of chiller being replaced	30 years (1978)				
Original capacity	320 tons	·			
Replacement technology	HFC134a, screw chiller				(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-chiller
Replacement capacity	1120 kW				[please provide unit = kW or tons]
Assumed / measured change in energy efficiency	from COP = 2.5 to COP=4.5				(from/unit to /unit)
Assumed annual saving in energy	1750 kWh				(in kWh)

Project data				
Title	Global: Global chi	iller replacement	project (China, India, Indonesia, Malaysia and Philippines)	
Approved at [ExCom Meeting]	The 47th ExCom	Meeting		
Country/countries/region covered	China, India, Indo	nesia, Jordan, M	lalaysia, Philippines and Tunisia	
MLF funding approved				\$6,884,612
Minimum co-funding requirement				\$13,769,224
	GEF, CDM (\$70 n	nillion and \$82 m	nillion respectively as per original project proposal, based on a total \$683 million cost)*	
Number of chillers to be replaced				150
Lead agency				The World Bank
MLF funding associated				\$516,346
Other agencies/bilaterals	Agency 1	Agency 2	Agency	
Name	N/A	N/A		
Responsibility				
MLF funding associated				

Name	N/A	N/A					
Responsibility							
MLF funding associated							
Results / assessment (provide some brief text, please; bullet points also possi							
	There has been overall a positive response by chiller owners, financial institutions and other partners (GEF, suppliers, US EPA, etc) on the potential of the project. The fathat all stakeholders are willing to move forward however does not eliminate the lead-time required to set up the institutional framework and finalize financing, project management and disbursement requirements. This is particularly so give the complexity of the initiative which combines financing from several sources as well as separa environmental objectives.						
	,		developing an averall implementation framework at the country lavel where attributed interests are believed with the mode of the country				
Greatest challenges	The greatest challenges were/are developing an overall implementation framework at the country level where stakeholder interests are balanced with the needs of project, overcoming misunderstanding about the ExCom decision on the chiller replacement project (in terms of eligibility and co-financing) and obtaining agreement national governments to allocate GEF financing to chiller replacement under the climate change window. More recently, there have been challenges with securing financing because of perceived risk that an insufficient number of CERs would be generated before the first compliance period ends in 2012 which was a requirement originally envisioned purchaser.						
Lessons learned			ram with multiple funding sources and several environmental goals requires a significant amount of time upfront. However, once a good time can be saved when replicating the program for other countries.				
Did you work with both public and private owners, and if yes: was there a different policy/approach needed for the two?	To date we have we public sector owner or two cases when	worked on a very ers of course hav re payment to the	limited basis with both private and public owners. Because the subsidy amount awarded was the same for both (in the case of Jordan), re had more difficulty in committing to replacement and convincing their management for the need to replace chillers. There has been one e supplier has been slow. If the public sector is involved, very early awareness raising and engagement is necessary to give it sufficient time acement, budget the required resources and follow internal procurement procedures.				
Remarks on interest by chiller owners / did you experience good co- operation / did the quality of interaction change with time?	model. This interest from chiller owner Thailand years ba	est has been obs s - they have bee ck, the awarenes	ested in the program given that energy prices continue to increase and the convincing figures in energy savings that are shown utilizing the erved in all countries where chiller discussions have taken place. For the Philippines and Jordan in particular, there was positive response an extremely proactive and have followed up with the NOU/project coordinator in hopes of accelerating the process. As was the case in so brought on by the many consultations with building owners and the demonstrated results shown from those that have replaced chillers until outside the project in the entire sector.				
	have served to catalyze replacements outside the project in the entire sector.  It is expected that the entire chiller sector in a country will be transformed with first the seed funds from the MLF and GEF but eventually through revenue generated by the CDM. Moreover, it is hoped that chiller replacement will cause chiller owners to seek other energy efficiency measures in their buildings, either alone or in partnership with other EE programs in the country.						
Reasons for delays	The reason for delay in starting project implementation was time needed by countries to decide on and request an allocation under the GEF for chiller replacement (climat change). Other time consuming, but necessary steps were development and approval of the chiller energy efficiency methodology under the CDM, developing a project framework at the country level (in coordination with executing agency candidates, suppliers, the Government, etc) and review and clearance of the first component of the global chiller project by GEF (for India). In addition, the first component of the project for India coincided with restructuring of the GEF project cycle. The most recent form delay was for Indonesia. The project was delayed because the requirements for co-financing could not be met, particularly through the mechanism chosen by the Government of Indonesia – concessional lending. A modality satisfactory and feasible to the Government was accepted allowing this project to move forward.						
	as the chillers rep of perceived risk.	laced). There ha However, a KfW	in terms of GEF, once it could be clearly demonstrated the environmental benefits attributed to each funding entity under the project (as well is been some uncertainty with the originally planned purchaser of emission reductions in both the India and Philippines component because has agreed to be a buyer in both cases. In the case of Indonesia, it was difficult to use the environment fund for concessional lending as owners to one commercial bank with which they may not have a business relationship/collateral. This created a roadblock for project				
Impact on the chiller market in the relevant country/countries; market							
transformation observed	Chiller replacement	nt under the proje	ect has only taken place in Jordan and the Philippines to date.				
How do you see the potential of replication of this approach for other sectors?	address specific b hence different so	arriers or constra urces of funds has as and procedure	or sectors is extremely high. Under the Global Chiller Replacement Project, several modalities were/are being piloted. These approaches aints that may be present in other sectors and countries. The idea however of using synergies to generate environmental co-benefits and as now been realized and will give the confidence to other stakeholders that this model is feasible. Moreover the different external and as required can now be easily followed - the source of delay from the first project - India was due to having to forge new ground in almost all o				
	The co-funding experience was generally positive. Private owners do not see co-funding in itself as a major difficulty as normally all of their commercial investments require several sources of funding. It is also the nature of the lenders to distribute their commercial risk. However, there is room for improvement. Given that funding is from several sources with several requirements, more preparation work needs to be done simultaneously on all fronts so that the project start is not held back from processes attributed to one source of funds.  As implied above, we believe the approach should and will have to be taken in the future, given likely constraints in financing for different sectors, technologies and applications. In regards to the MLF, the Executive Committee provided clear guidance and parameters of how to approach the project (for instance 1:3 cofinancing requirement and obligation to use the model the determine the level of subsidy) and the funding followed without much difficulty. In regards to the other donors, focal points for other financial mechanisms (i.e. GEF country focal points) need to be included in the process early on to ensure full understanding of the project objectives, modality and outputs/benefits. Energy efficiency in particular is a difficult sell and therefore a lot upfront education and explanation is needed (potential energy efficiency gains substantiated by analytical work is key) for all stakeholders, including the managers of the relevant funds. In terms of carbon finance, an area of financing in which the MP community was not so familiar prior to these projects, special attention is required on the speed of preparation. Delays led to a number of chillers being excluded from the project and carbon finance because the methodology has strict requirements on the age window of eligible chillers. The total amount of carbon finance expected is lower than originally planned - simply because of project delays. Thus in terms of carbon finance time is of the essence.						
Should a similar approach be taken in the future again, what are your suggestions for improvements a) related to the MLF; b) related to other donors (where relevant); c) related to implementation and co-operation with stakeholders and the country; d) related to other							
	ExCom Meeting to	proceed with th	for India and the Philippines because of its small CFC-based chiller sector. No objection was expressed by the Secretariat at the 56th e approach. Malaysia will not participate in the project as all its chillers are HCFC based. China and Tunisia will most likely not participate ed but also with a slightly different approach where GEF co-financing will be used to fund bank guarantees.				

runding information				1-4
approved co-funding	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialised
Co-funding institution	GEF	CDM		
Name, purpose of programme	Chiller Energy Efficiency Pr	piect		
Amount approved in total (currency)	US\$6,300,000	US\$5,850,000		
Was this co-funding foreseen in the original submission to the		0000,000,000		
47th/48th Meeting?	yes	yes		
				The ratio of carbon revenue expected has gor
				down since preparation of the initial project
				document because of the decrease in size of
				the fleet eligible for carbon finance under the
If you: Did the amount shange (please provide from to)	yes, from 10.4 to 6.3 million	voc from \$12.9 to \$15. to 5	E OE million	methodology.
If yes: Did the amount change (please provide from to)	yes, nom 10.4 to 6.5 million	yes 110111 \$12.6 to \$15 to \$	J.65 HIIIIIOH.	
If no: When (approx.) did you become aware of this				Explain briefly: 2, 3 sentences (separate belo
possibility, and how? Please explain briefly	n/a	n/a		or some bullet points
How much of the cofinancing constitutes project costs in the				
MLF definition (see letter from MFS)	US\$5,700,000	US\$5,850,000		
Date of approval	Apr-08			
Date of approval	Αρι-ου			
				e.g. for replacing chillers in hospitals in count
Major conditions associated	None	n/a		x; for replacing one system in institution y;
Additional activities covered (if any): (E.g.: Energy efficiency				
program for building,)	TA; Monitoring and Verifica	ion		
Funds agreed by the MFS to be released based on that	171, Worldoning and Vollinga	I		
	LIC#4 000 000	- /-		
approval	US\$1,000,000	n/a		T. ( ); 1 11 ( 100)
				The funding was made available to IDBI upor
				signing of the grant agreement. However, fu
				will be disbursed based on withdrawal
				applications, US\$230,000 has been disburse
Date of related release of Funds by the MFS	26-Aug-00			1 * *
Date of related release of Funds by the MFS	26-Aug-09			applications. US\$230,000 has been disburse to the special account to date.
·				
co-funding presently sought	26-Aug-09	2nd co-funding	co-funding	1
·			co-funding	to the special account to date.
co-funding presently sought Co-funding institution			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency			co-funding	to the special account to date.
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)	1st co-funding	2nd co-funding		Explanations
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently indoned			co-funding	to the special account to date.
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  Funding sources previously pursued but subsequently adoned  Co-funding institution	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  Funding sources previously pursued but subsequently adoned  Co-funding institution  Name, purpose of programme	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  inunding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  Funding sources previously pursued but subsequently adoned  Co-funding institution  Name, purpose of programme	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  inunding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) iunding sources previously pursued but subsequently indoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  iunding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  iunding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  Funding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?	1st co-funding	2nd co-funding		Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently adoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision	1st co-funding  1st co-funding  1st co-funding	2nd co-funding  2nd co-funding	co-funding	Explanations  Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  itional external resources acquired for the chiller phase-out  Co-funding institution	1st co-funding  1st co-funding  1st co-funding  US EPA	2nd co-funding  2nd co-funding	co-funding	Explanations  Explanations  Explanations
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently indoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  itional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme	1st co-funding  1st co-funding  1st co-funding  US EPA	2nd co-funding  2nd co-funding	co-funding	Explanations  Explanations  Explanations
co-funding presently sought  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently modoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  itional external resources acquired for the chiller phase-out  Co-funding institution  Name, purpose of programme  Amount sought in total	1st co-funding  1st co-funding  1st co-funding  US EPA	2nd co-funding  2nd co-funding	co-funding	Explanations  Explanations  Explanations
co-funding presently sought Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently indoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  itional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme	1st co-funding  1st co-funding  1st co-funding  US EPA	2nd co-funding  2nd co-funding  2nd co-funding	co-funding	Explanations  Explanations  Explanations

	approved as funding	1 at an funding	2nd on funding	oo fundin ~	Potors to all an financing that materialised
Per	approved co-funding	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialised
1	Co-funding institution	GEF	CDM (KfW)		
	Name, purpose of programme	Chiller Energy Efficiency Pre	oject		
					The amt of carbon financing expected was
					\$7.77 million. Actual purchaser, Kfw, has
I	Amount approved in total (currency)	US\$2,600,000	\$6,000,000		agreed to \$6 million.
I	Was this co-funding foreseen in the original submission to the		ψ3,555,000		
I	47th/48th Meeting?	luga.	V00		
	47 th/48th Meeting?	yes	yes		T
					The ratio of carbon revenue expected has gone
					down slightly since preparation of the initial
					project document because of the decrease in
					size of the chiller fleet eligible for carbon finance
	If yes: Did the amount change (please provide from to)	yes, from 3.655 to 2.6 millio	ves from \$3,623 to \$7,77 to	o \$6 million	under the methodology.
	If no: When (approx.) did you become aware of this	)	.yeee	I	Explain briefly: 2, 3 sentences (separate below)
	possibility, and how? Please explain briefly	n/a	n/o		or some bullet points
	possibility, and now? Please explain briefly	n/a	n/a		or some builet points
	How much of the cofinancing constitutes project costs in the				
	MLF definition (see letter from MFS)	US\$2,600,000	US\$6,000,000		
					The Bank Board approved the Philippines
I	Date of approval	Nov. 2008			Energy Efficiency Project in June 2010.
I			1		
I					o a for replacing chillers in beenitals in security
					e.g. for replacing chillers in hospitals in country
	Major conditions associated	None	n/a		x; for replacing one system in institution y;
	Additional activities covered (if any): (E.g.: Energy efficiency				
	program for building,)	TA; Monitoring and Verificat	tion		
	Funds agreed by the MFS to be released based on that				
	approval	US\$1,000,000	n/a		
	арргота	υσφ1,000,000	11/4		Five grant agreement effectiveness conditions
					are in place which have not yet been met.
					Therefore no MLF funding has been released to
	Date of related release of Funds by the MFS	not yet released			the country to date.
		-	•	L	
Per	co-funding presently sought	1st co-funding	2nd co-funding	co-funding	Explanations
Per	co-funding presently sought	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated	1st co-funding	2nd co-funding	co-funding	Explanations
Per	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency	1st co-funding	2nd co-funding	co-funding	Explanations
	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)	1st co-funding	2nd co-funding	co-funding	Explanations
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned	1st co-funding	2nd co-funding  2nd co-funding	co-funding	Explanations
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned?				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned?				
Co-	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned?				
Co- aba	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision	1st co-funding	2nd co-funding	co-funding	Explanations
Co- aba	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision	1st co-funding			
Co- aba	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  itional external resources acquired for the chiller phase-out Co-funding institution	1st co-funding  1st co-funding US EPA	2nd co-funding	co-funding	Explanations
Co- aba	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  itional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme	1st co-funding  1st co-funding  US EPA  Technical Assistance	2nd co-funding	co-funding	Explanations
Co- aba	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  itional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total	1st co-funding  1st co-funding US EPA	2nd co-funding	co-funding	Explanations
Co- aba	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  itional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme	1st co-funding  1st co-funding  US EPA  Technical Assistance	2nd co-funding	co-funding	Explanations
Co- aba	Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Expected approval Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) funding sources previously pursued but subsequently ndoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme abandoned? Reasons for the decision  itional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total	1st co-funding  1st co-funding  US EPA  Technical Assistance	2nd co-funding  2nd co-funding	co-funding	Explanations

funding information	T			T= 4
approved co-funding	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialised
Co-funding institution	GEF	Concessional Loan		
Name, purpose of programme	Chiller Energy Efficiency			
Amount approved in total (currency)	US\$3,300,000	\$20,000,000		
Was this co-funding foreseen in the original submission to the 47th/48th Meeting?	no	no		
If yes: Did the amount change (please provide from to)				
If no: When (approx.) did you become aware of this possibility, and how? Please explain briefly	In June 2009. See explanation.	In late 2009.		In 2006 and 2007, some efforts were made to see how GEF support could be linked to the sloan program of the Government and KfW willimited success. It was not until June 2009, the GEF National Focal Point agreed to supp the submission of chiller project to be funded under GEF 4 with the utilization of a novel approach (GEF funding will be used to fund bank guarantees).
How much of the cofinancing constitutes project costs in the				
MLF definition (see letter from MFS)	US\$3,300,000	US\$20,000,000		
Date of approval	Mar. 2010	00420,000,000		
ναιο οι αργιοναι	IVIAI. 2010			
Major conditions associated	None	n/a		e.g. for replacing chillers in hospitals in count x; for replacing one system in institution y;
Additional activities covered (if any): (E.g.: Energy efficiency		1		, , , , , , , , , , , , , , , , , , , ,
program for building,)	TA; Monitoring and Veri	fication		
Funds agreed by the MFS to be released based on that	, .viorintoring and von			
approval	US\$1,000,000	n/a		
Date of related release of Funds by the MFS	not yet released	1,74		
	not you released			l l
co-funding presently sought	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution			oo .a.iaiiig	
Name, purpose of programme	<del> </del>			
Amount sought in total	1			
How much of that constitutes project costs in the MLF				
definition				
definition Expected approval				
definition  Expected approval  Reasons for the delay				
definition  Expected approval  Reasons for the delay  Major conditions associated				
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency				
definition  Expected approval  Reasons for the delay  Major conditions associated				
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)				
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently				
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?	1st co-funding	2nd co-funding	co-funding	Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision				
definition  Expected approval  Reasons for the delay Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  itional external resources acquired for the chiller phase-out	1st co-funding	2nd co-funding  2nd co-funding	co-funding	Explanations  Explanations
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  itional external resources acquired for the chiller phase-out  Co-funding institution				
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently ndoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  litional external resources acquired for the chiller phase-out  Co-funding institution  Name, purpose of programme				
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  lititional external resources acquired for the chiller phase-out  Co-funding institution  Name, purpose of programme  Amount sought in total				
definition  Expected approval  Reasons for the delay  Major conditions associated  Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  funding sources previously pursued but subsequently indoned  Co-funding institution  Name, purpose of programme  Amount sought in total  How much of that constitutes project costs in the MLF definition  When was the quest for co-funding from this institution/programme abandoned?  Reasons for the decision  ditional external resources acquired for the chiller phase-out  Co-funding institution  Name, purpose of programme				

Genera	l information					Explanations
ident	many chiller users have been ified in the country					440 chillers have been targeted for replacement through GEF, MLF and CDM assistance (at 14-20%) under the Chiller Replacement Project. As of Sep. 2010, the pipeline includes about 62 CFC-based eligible (per the CDM methodology) chillers.
	How many chillers remain?	It is estimated that the same baseline number exists - no chillers have been replaced under the project to date.				
	How many belong to the public sector? How many to the private sector?		rs targeted by the proje te and public sectors.	ect, however, we hav	e not received the break	
	t share of the country's chiller users been identified (estimated)				100%	Number was estimated through a data collection process. The data collection was conducted using two approaches: chiller manufacturer's survey; and chiller owners' survey. Chiller manufacturers' survey was the basis for the development of a database. It was created through the development and administration of a survey questionnaire and included a web-based data collection system. It included direct administration of the survey questionnaire in separate meetings will all of the major chiller manufacturers. Chiller owners' survey was conducted through the indirect administration of a survey questionnaire via mailings and a web site developed for this purpose. It was supported by advertisement and announcements in association newsletter.
othe imple	e there been agreements planned with r institutions to facilitate ementation or lending? If yes, please orate briefly				Yes	IDBI selected as the executing agency and will be responsible for fund managemer and project implementation.
D /		A .: 4	IA 11 11 0	A 11 11 0	Ta it to a	le i e
	ain) activity	Activity 1	Activity 2	Activity 3	Activity 4	Explanations
Cour	of activity	India	India	India	if Project Management India	e.g.: Chiller replacement / Chiller retrofit / Workshop /
		commencement in S the chiller manufactu coordinating entity. workshops were helu change in the carbon Emissions Transfer and Verification Age completed. The POA	rers and suppliers acti Intensive marketing str d to inform potential be n buyer and an ERPA v	or of Agreements have in the country. Phategy was launched neficiaries about the was signed with KfW a signed with 5 chilled and the baseline and PDD is about to be	ive been signed with all MU set up in IDBI, the and a number of project. There was a in early 2010. Legal r owners. A Monitoring for 5 chillers has been	in the process of installation and trial/partially completed, new chiller delivery expected / Tendering complete and contract issued / Tender process ongoing / Preparation of tender process // Workshop planned / Workshop held (when?) / Results published (when? Please provide copy)
In case	of chiller replacements					No chillers replaced as of Sep. 10.
_	er, use					e.g. "city of x", "hospital cooling"
Whe	n was the agreement with the owner luded					
(Exp	ected) Status of completion					
Actu	al cost with a break down by					
	equipment					
	installation					
Infa-	construction					
	mation on energy efficiency			<del>                                     </del>		
	Original technology  Age of chiller being replaced					
	Original capacity			1		
	Replacement technology			1		(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-chiller)
	Replacement capacity			1		[please provide unit = kW or tons]
	Assumed / measured change in energy efficiency					(from/unit to /unit)
	Assumed annual saving in energy					(in kWh)

G	eneral information		Explanations
	How many chiller users have been	250	195 chillers have been targeted initially (first phase) for replacement
	identified in the country		through GEF, MLF and KfW assistance under the Chiller
			Replacement Project.
	What share of the country's chiller users	100%	The inventory of CFC centrifugal chillers was developed on the basis
	have been identified (estimated)		of information provided by chiller suppliers.
	Have there been agreements planned with	Yes.	A Project Management Contractor has been selected (competitively)
	other institutions to facilitate		to support DENR in its role as Coordination Entity to manage the
	implementation or lending? If yes, please		project. KfW and DENR are working together to secure a DOE for
	elaborate briefly		validation.

Per (main) activity	Activity 1	Activity 2	Activity 3	Activity 4	Explanations
Type of activity	Chiller Replacement	Technical Assistance	Monitoring and Veri	Project Managemen	e.g.: Chiller replacement / Chiller retrofit / Workshop /
	Philippines	Philippines		Philippines	
	agreed to purchase occurred in June 20 monitoring plan which been replaced. Valid to ensure that emissions.	ch would be submitted dation of the methodological	ne WB Board approval didates have been se to the CDM EB and a ogy/project must be o tained from the proje	al of the project elected to validate for already 7 chillers have arried out by a DOE	Completed, new chiller fully functional/largely completed, new chiller delivered and in the process of installation and trial/partially completed, new chiller delivery expected / Tendering complete and contract issued / Tender process ongoing / Preparation of tender process // Workshop planned / Workshop held (when?) / Results published (when? Please provide copy)
n case of chiller replacements					TOTAL No. replaced as of Sep 2010 = 7
Owner, use					e.g. "city of x", "hospital cooling"
When was the agreement with the owner concluded					
(Expected) Status of completion					
Actual cost with a break down by	1	ı	I	ı	
equipment					
installation					
construction					
Information on energy efficiency					
Original technology					
Age of chiller being replaced					
Original capacity					
Replacement technology					(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-chiller)
Replacement capacity					[please provide unit = kW or tons]
Assumed / measured change in energy efficiency					(from/unit to /unit)
Assumed annual saving in energy					(in kWh)

General information		Explanations
How many chiller users have been identified in the country		CFC-based chillers only. However, six of these chillers have been removed from the list of chillers targeted for MLF assistance (30% incentive) because they were already replaced with new chillers and required criteria for eligibility have not been fulfilled.
How many chillers remain?	Four CFC-based chillers remain.	
How many belong to the public sector? How many to the private sector?	They belong to the Airport International Group which was once public but has been privatized. Of the chillers already replaced, two belonged to a public entity, the rest to the private sector.	
What share of the country's chiller users have been identified (estimated)	100%	
Have there been agreements planned with other institutions to facilitate implementation or lending? If yes, please elaborate briefly	No	

er (main) activity	Activity 1	Activity 2	Activity 3	Explanations
Type of activity	Chiller Replacement	Technical Assistance	Project Management	e.g.: Chiller replacement / Chiller retrofit / Workshop /
Country	Jordan	Jordan	Jordan	
Status	2009. Chiller was replaced by January 2010. As of Sep. 10, 16 CFC-based chillers have	CFC disposal and safe storage for the replaced chillers in Oct. 2010. A technical workshop was held for chiller owners and another is planned in late	started in late 2009. PMU is	Completed, new chiller fully functional/largely completed, new chiller delivered and in the process of installation and trial/partially completed, new chiller delivery expected / Tendering complete ar contract issued / Tender process ongoing / Preparation of tender process // Workshop planned / Workshop held (when?) / Results published (when? Please provide copy)
case of chiller replacements	N/A	N/A	N/A	TOTAL No. replaced as of Sep 2010 = 16
Owner, use				e.g. "city of x", "hospital cooling"
When was the agreement with the owner concluded (Expected) Status of completion				
Actual cost with a break down by				
equipment				
installation				
construction				
Information on energy efficiency				
Original technology				
Age of chiller being replaced				
Original capacity				
Replacement technology				(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-chiller)
Replacement capacity				[please provide unit = kW or tons]
Assumed / measured change in energy efficiency				(from/unit to /unit)
Assumed annual saving in energy				(in kWh)

_					le i d						
	eneral information				Explanations						
	How many chiller users have been identified	in		160							
	the country										
	NATIONAL CONTRACTOR OF THE STATE OF THE STAT			1000/							
	What share of the country's chiller users have	е		100%							
	been identified (estimated)										
	Have there been agreements planned with			No							
	other institutions to facilitate implementation	or									
	lending? If yes, please elaborate briefly										
		<u> </u>									
Da	or (main) activity	A attivity 1	A attivity 2	A ativity 2	Evalenations						
Pe	er (main) activity	Activity 1	Activity 2	Activity 3	Explanations						
	Type of activity	Chiller Replacement	Technical Assistance	Project Management	e.g.: Chiller replacement / Chiller retrofit / Workshop /						
	Country	Indonesia	Indonesia	Indonesia							
	Status				Completed, new chiller fully functional/largely completed, new chiller						
					delivered and in the process of installation and trial/partially						
					completed, new chiller delivery expected / Tendering complete						
					and contract issued / Tender process ongoing / Preparation of tender						
					process // Workshop planned / Workshop held (when?) / Results						
					published (when? Please provide copy)						
					,						
In	case of chiller replacements	N/A	N/A	N/A							
_	Owner, use	1 47 1		147.	e.g. "city of x", "hospital cooling"						
	Owner, use				e.g. City of X , Hospital cooling						
	140										
	When was the agreement with the owner										
	concluded										
	(Expected) Status of completion										
	Actual cost with a break down by	•	•	•							
	equipment										
	in stallation										
	installation										
	construction										
	Information on energy efficiency	<u> </u>									
	Original technology	1	1	+							
	Age of chiller being replaced	1	1								
	Original capacity				[						
	Replacement technology				(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-						
					chiller)						
	Replacement capacity				[please provide unit = kW or tons]						
	Assumed / measured change in energy	,			(from/unit to /unit)						
	efficiency				ľ						
	Assumed annual saving in energy				(in kWh)						
	, localities difficult daving in chergy	1	1		[ \						

Project data						
	Strategic Demonstration Project for Accelerated Conversion of CFC Chillers in 5 African Countries (Cameroon,					
Title	Egypt, Namibia, N	Egypt, Namibia, Nigeria and Sudan)				
Approved at [ExCom Meeting]	48					
Country/countries/region covered	Cameroon, Egypt	, Namibia, Nigeria	and Sudan			
MLF funding approved	US\$ 2000000					
Minimum co-funding requirement	US\$ 477876					
Source(s) of co-funding as envisaged in project proposal (amount envisioned						
and currency in brackets)	French Global En	vironment Facility				
Number of chillers to be replaced	20					
Lead agency	UNIDO					
MLF funding associated	747,500					
Other agencies/bilaterals	Agency 1	Agency 2	Agency			
Name	France	Germany	Japan			
	implementation					
	assigned to	, , ,	implementation			
· · · · · · · · · · · · · · · · · · ·	UNIDO	activities	assigned to UNIDO			
MLF funding associated	360,000	192,500	700,000			

	The project implementation is not yet fully operationalized therefore the general experience so far relates to the mobilization of additional resources. In this context, working with the bilateral agencies to mobilize the support of the French Global Fac.
	1) Introducing to the FGEF the concept of linking the Kyoto Protocol and Montreal Protocol through replacing CF based chillers with energy efficient non-CFC based chillers, 2) Synchronizing the project cycles of FGEF and ML and 3) Introducing a new concept to the national ozone units
Greatest challenges Lessons learned	and by mitroducing a new concept to the material exerte units
Remarks on interest by chiller owners / did you experience good co-	Not yet started
Remarks on interest by chiller owners	N/A
Expected results beyond chillers funded: (e.g.: Will the demonstration lead to more chillers being replaced, if yes how concrete is that understanding? If no why is that assumed?)	One component under the projects deals with the elaboration of a chiller replacement policy and replication of the demonstration results
Reasons for delays	N/A
Experience with funding organisations	The FGEF and the French Ministry of Environment was very supportive and enthusiastic about the project conc This facilitated the quick approval of the co-funding requirement.
Impact on the chiller market in the relevant country/countries; market transformation observed	The chiller suppliers were involved since the onset of the project, they are engaging in more intense marketing activities and show a lot of competitiveness.
How do you see the potential of replication of this approach for other sectors?	N/A
Would you say that this co-funding experience was positive?	N/A
Should a similar approach be taken in the future again, what are your suggestions for improvements a) related to the MLF; b) related to other donors (where relevant); c) related to implementation and co-operation with stakeholders and the country; d) related to other	
	N/A
Other remarks and/or explanations	In accordance with the approval conditions, Senegal was added to the list of countries covered by the project.

o-runding information	Ta	0 1 1 1		In
er approved co-funding	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialised
	French Global Environment			
Co-funding institution	Facility (FGEF)			
Name, purpose of programme	Energy efficiency and climate	te change		
Amount approved in total (currency)	EUR 750,000			
Was this co-funding foreseen in the original submission to the				
47th/48th Meeting?	ves			yes/no
Truly Tour Mooning.	The funding approved			1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
	increased from US\$			
Marian Bid the assessed above (alesses asserted forms				
If yes: Did the amount change (please provide from to)	500,000 to EUR 750,000			
If no: When (approx.) did you become aware of this				Explain briefly: 2, 3 sentences (separate bel
possibility, and how? Please explain briefly	N/A			or some bullet points
How much of the cofinancing constitutes project costs in the				
MLF definition (see letter from MFS)	EUR 750,000			
Date of approval	Jul-07			
• • • • • • • • • • • • • • • • • • • •				
				e.g. for replacing chillers in hospitals in cour
Major conditions associated	None			x; for replacing one system in institution y;
Additional activities covered (if any): (E.g.: Energy efficiency	None			x, for replacing one system in institution y,
program for building,)	None			
Funds agreed by the MFS to be released based on that				
approval	2,000,000			
Date of related release of Funds by the MFS	Sep-07			
er co-funding presently sought	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution	January 1	3		,
Name, purpose of programme				
Amount sought in total				
How much of that constitutes project costs in the MLF			<b> </b>	
definition				
Expected approval				
Reasons for the delay				
Reasons for the delay Major conditions associated				
Reasons for the delay				
Reasons for the delay Major conditions associated				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently	Act on funding	2nd on funding	oo funding	Evaluations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently andoned	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  Defunding sources previously pursued but subsequently andoned Co-funding institution	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,) o-funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  Defunding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned  Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  P-funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition	1st co-funding	2nd co-funding	co-funding	Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision  ditional external resources acquired for the chiller phase-out	1st co-funding	2nd co-funding  2nd co-funding	co-funding	Explanations  Explanations
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision  ditional external resources acquired for the chiller phase-out Co-funding institution				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision  ditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision  ditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision  ditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  -funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision  ditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  p-funding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision  Iditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition				
Reasons for the delay Major conditions associated Additional activities covered (if any): (E.g.: Energy efficiency program for building,)  Defunding sources previously pursued but subsequently andoned Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition Reasons for the decision  Iditional external resources acquired for the chiller phase-out Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF				

G	General information								Explanations
	How many chiller users have been identified in the country		trifugal chillers, which a a (6), Nigeria (64), Sen			onsidered under the	project)		
	How many chillers remain?	0	N/A	200	7	13	16	50	
	How many belong to the public sector? How many to the private sector?			60% of th	e chillers are privatel	owned			
	What share of the country's chiller users have been identified (estimated)	All							
	Have there been agreements planned with other institutions to facilitate implementation or lending? If yes, please elaborate briefly	No							
_									
P	Per (main) activity	Activity 1	Activity 2	Activity 3	Activity 4	Activity 5	Activity 6	Activity	Explanations
	Type of activity	Chiller Replacement	Regional Workshop	Setup of a financial mechanism				Setup of a financial mechanism	e.g.: Chiller replacement / Chiller retrofit / Workshop /
	Country	Namibia	Egypt	Egypt	Senegal	Sudan	Cameroon	Nigeria	
	Status	Completed	The workshop was held in September 2006 and the results were published by GTZ (copy attached)	1)Project steering committee operational, 2) Agreement with the national bank of Egypt will be signed by end October 2010 3) Chiller replacements will start in December 2010.	does not have	Procurement of the chillers will be initiated at the end of November 2010,	The NOU wishes that all the owners benefit from the fund therefore local banks are being contacted to check options for establishment of a revolving fund to cover all remaining beneficiaries.	1) Steering Committee Established, 2) selection of the project beneficiaries is ongoing 3) Agreement with the Nigerian Industry Bank will be signed in December 2010	Completed, new chiller fully functional/largely completed, new chille delivered and in the process of installation and trial/partially completed, new chiller delivery expected / Tendering complete and contract issued / Tender process ongoing / Preparation of tender process // Workshop planned / Workshop held (when?) / Results published (when? Please provide copy)
ln	n case of chiller replacements								
	Owner, use	Katatura Hospital, hospital cooling			Hotel (Government owned)	Textile Industries			e.g. "city of x", "hospital cooling"
	When was the agreement with the owner concluded	Jan-08							
	(Expected) Status of completion	Dec-08							
	Actual cost with a break down by	•	,		1		1		
	equipment								
	installation								
	construction								
	Information on energy efficiency								
	Original technology  Age of chiller being replaced	<del> </del>		<u> </u>					
	Original capacity								
	Replacement technology								(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-chiller)
l	Replacement capacity		_						[please provide unit = kW or tons]
	Assumed / measured change in energy efficiency								(from/unit to /unit)
L	Assumed annual saving in energy								(in kWh)

Project data					
7					
Title	Demonstration project on the replacement of CFC centrifugal chillers (Croatia, Macedonia, Romania and Serbia and Montenegro)				
Approved at [ExCom Meeting]	47				
	Croatia, Macedonia, Romania and Serbia and				
Country/countries/region covered	Montenegro / Eas	tern Europe and	I Central Asia		
MLF funding approved	US\$ 1,069,074	•			
Minimum co-funding requirement	US\$ 416,175				
Source(s) of co-funding as envisaged in project proposal (amount envisioned					
and currency in brackets)	Counterpart co-fir	ancing (US\$ 75	0,000)		
Number of chillers to be replaced	12 chillers				
Lead agency	UNIDO				
MLF funding associated	US\$ 1,069,074				
Other agencies/bilaterals	Agency 1	Agency 2	Agency		
Name	N/A	N/A	N/A		
Responsibility	N/A	N/A	N/A		
MLF funding associated	N/A	N/A	N/A		

assessment (provide some brief text, please; bullet points also pos	sible)
	The overall assessment for the implementation
	of this project is good because of the interest of the chiller owners, the willingness of the chiller suppliers to engage in the project and
General experience	support of the procurement services unit at UNIDO in negotiating prices.
	1) Solvency of companies in the region. Some end-users who were pre-selected went bankrupt before the implementation of the proje
	therefore other beneficiaries were selected however in some other cases, the beneficiaries went bankrupt after the chillers were
Greatest challenges	commissioned. With a lot of support from the NOUs, the chillers were reallocated to other beneficiaries.
oreatest trialienges	
	1)Low operating hours due to the weather conditions in the region make the energy savings not so attractive, saving on maintenance
	the old chillers and compliance with EU regulations become the major drivers for the replacement in the Eastern European Region! Ei
	Service Companies would only be interested in such projects if it integrates other measures relating to green buildings!
	2) Replacement of the chillers alone do not yield the expected energy savings. To obtain optimal energy savings, other components i
	chilling plant including the cooling towers, piping and pumps should be replaced. This is usually very costly and acts as a disincentive
Lessons learned	replacement.
Did you work with both public and private owners, and if yes: was	Yes both public and private sector beneficiaries were considered. Since the counterpart co-financing was used, no major difference in
there a different policy/approach needed for the two?	approach was needed.
and a amorem penegrappied on medada for the tire.	approach was needed.
Remarks on interest by chiller owners / did you experience good co-	The chiller owners were interested and cooperative. Often the incentive given to replace one chiller triggered the counterparts to replace
operation / did the quality of interaction change with time?	other chillers if more than one were operated!
Expected results beyond chillers funded: (e.g.: Will the	Galler Grand Christian Charles and Control operation
demonstration lead to more chillers being replaced, if yes how	Given the accession of many participating countries into EU and their wish to comply with EU regulations on CFCs, the chiller owners
concrete is that understanding? If no why is that assumed?)	aware of the urgent need to replace their chillers! No replication impact is expected.
Reasons for delays	Aware of the digent need to replace their chillers: No replication impact is expected.
Experience with funding organisations	IWA N/A
Impact on the chiller market in the relevant country/countries;	The chiller suppliers were involved since the
market transformation observed	onset of the project, they are engaging in more intense marketing activities and show a lot of competitiveness.
	priser or the project, they are engaging in more intense marketing activities and show a for or competitiveness.
How do you see the potential of replication of this approach for	
other sectors?	Yes a project for an early replacement programme of chiller or other equipment would be useful to deal with the HCFC service sector.
Would you say that this co-funding experience was positive?	Yes however there is no replication impact.
Should a similar approach be taken in the future again, what are	
your suggestions for improvements a) related to the MLF; b) related	
to other donors (where relevant); c) related to implementation and	A similar project may be applied to the phase out of HCFC based chillers on a revolving fund basis with some grant subsidy to be give
co-operation with stakeholders and the country; d) related to other	incentive. However this needs to be early on in planning the HCFC phase out to allow for sufficient time for the revolving fund to be
issues.	replenished.
Other remarks and/or explanations	

o-funding information				
er <u>approved</u> co-funding	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialised
Co-funding institution	5 Counterparts	5 counterparts	Ĭ	j
Name, purpose of programme	Counterpart co-financing	counterpart co-financing	1	
Amount approved in total (currency)	US\$ 230,000	US\$ 240,000		
Was this co-funding foreseen in the original submission to the	230,000	254 270,000	1	
	l			
47th/48th Meeting?	yes	yes		yes/no
	the amount foreseen	the amount foreseen		
	is equivalent to that	is equivalent to that		
If yes: Did the amount change (please provide from to)	approved	approved		
If no: When (approx.) did you become aware of this				Explain briefly: 2, 3 sentences (separate below
possibility, and how? Please explain briefly	N/A	N/A		or some bullet points
The state of the s		1		
How much of the cofinancing constitutes project costs in the		<u> </u>		
	1100 100 000	1100 105 000		
MLF definition (see letter from MFS)	US\$ 183,000	US\$ 195,000	1	
	Nov - 06	Nov - 06		
Date of approval				
				e.g. for replacing chillers in hospitals in country
Major conditions associated	None	None	1	x; for replacing one system in institution y;
Additional activities covered (if any): (E.g.: Energy efficiency		1.0		in, in includion y, in
program for building,)	None	None		
	None	INOTE	1	
Funds agreed by the MFS to be released based on that				
approval	471,679			
Date of related release of Funds by the MFS	May-07			
er co-funding presently sought	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution				
Name, purpose of programme		+	1	1
		-	1	
Amount sought in total			1	
How much of that constitutes project costs in the MLF				
definition	<u> </u>	<u> </u>	<u> </u>	
Expected approval				
Reasons for the delay				
Major conditions associated			1	
Additional activities covered (if any): (E.g.: Energy efficiency		<u> </u>	1	1
program for building,)			1	
program for building,)				
o-funding sources previously pursued but subsequently				
<u>pandoned</u>	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution				
Name, purpose of programme				
Amount sought in total				
How much of that constitutes project costs in the MLF		1		
definition			1	
When was the quest for co-funding from this			1	
institution/programme abandoned?			<u> </u>	
Reasons for the decision				
·	-	•		•
				1
dditional automal vacarinas acquired for the obliver of a	1 at an funding	2nd on friedless	an francisco	Funlanations
dditional external resources acquired for the chiller phase-out	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution				
Name, purpose of programme			<u> </u>	
Amount sought in total				
How much of that constitutes project costs in the MLF			İ	İ
definition				
		+	1	
When was the quest for co-funding from this			1	
institution/programme abandoned?				
Reasons for the decision	<u>                                     </u>	<u> </u>	<u>l                                      </u>	<u> </u>
Reasons for the decision				

eneral information					Explanations
How many chiller users have been	Romania: 7 CFC-based centrifugal	chillers (including those considered under the project	t)		
identified in the country		chillers (including those considered under the project			
identified in the country					
		ntrifugal chillers (including those considered under the			
	Serbia and Montenegro: 34 CFC-ba	sed centrifugal chillers (including those considered	under the project)		
How many chillers remain?					
,					
How many belong to the public					
sector? How					
many to the private sector?					
many to the physic coston.					
What share of the country's chiller users	Almost all 95%				During project implementation some new sites were detected in
have been identified (estimated)					Serbia, which were not part of the original inventory
Have there been agreements planned with	No				
other institutions to facilitate					
implementation or lending? If yes, please					
elaborate briefly					
leiaborate briefly	1				1
	Ta e se a	In the co	I	Ta	le i e
er (main) activity	Activity 1	Activity 2	Activity 3	Activity	Explanations
Type of activity	Chiller Replacement	Chiller Replacement in concrete pipeline phase	Supplier Seminar		e.g.: Chiller replacement / Chiller retrofit / Workshop /
Country	Romania (1),	Croatia (4), Serbia (2)	Austria	Serbia (1)	
	Macedonia (2), Serbia (1),				
	Montenegro (1)				
Status	Completed	Completed except the one in Viskoza Kord,	Completed	Awaiting advise of the	Completed, new chiller fully functional/largely completed, new chiller
Claras	Completed	Serbia. The company was bankrupt during 2010.	Completed	Secretariat regarding	delivered and in the process of installation and trial/partially
		UNIDO with the assistance of the NOU are trying		reimbursement of the	completed, new chiller delivery expected / Tendering complete
		to recover the chiller and to reutilize it for a new		hospital for the costs	and contract issued / Tender process ongoing / Preparation of
		beneficiary. Additional costs to bring the chiller		incurred to replace the	tender process // Workshop planned / Workshop held (when?) /
		into operation might be needed.		chiller at VMA.	Results published (when? Please provide copy)
case of chiller replacements					
Owner, use	1) Radio House, cooling of	1) Zagrebcanka		VMA	e.g. "city of x", "hospital cooling"
Owner, use				VIVIA	e.g. City of X , Hospital cooling
	technical rooms and studios	Business Tower, Cooling, 2) SRDJ Galeria,			
	2) National Bank, cooling, 3) OHIS	Cooling, 3) Clinic Osijek, hospital cooling, 4)			
	chemical factory, cooling of	Ministry of Economy, cooling, 5) Vizkoza Kord,			
	mechanical equipment, 4) Airport	cooling, 6) Radio Television Serbia (RTS), cooling		1	
	Belgrade, cooling 5) Television	of technical rooms and studios			
	Montenegro, cooling of technical				
	rooms and studios				
<del>                                     </del>	Tooms and studios			1	+
NA/In an area of the common and width at	0 00			+	+
When was the agreement with the owner	Sep-06	Apr-08		1	
concluded	1				
(Expected) Status of completion	Dec-08	Dec-09			
Actual cost with a break down by					
equipment	585,000	680,000			
installation (startup only)	20,000	30.000		1	
construction	Counterpart	Counterpart		1	
oon ou doubli	responsibility locally!	responsibility locally!			
Information on angual officional	responsibility locally!	responsibility locally:		1	
Information on energy efficiency	1411.6	10.050.44		+	
Original technology	All five are CFC-11, centrifugal	1) CFC-11, centrifugal		1	
		2) CFC-11, centrifugal		1	
		3) CFC-12, centrifugal		1	
		4) CFC-11, centrifugal		1	
		5) CFC-114, centrifugal			
1 1	1		ĺ	1	
		6) CFC-11, centrifugal			

Age of chiller being replaced	1) 30 years (1978)	1) 33 years (1975)		
	2) 32 years (1976)	2) 36 years (1972)		
	3) 34 years (1974)	3) 27 years (1981)		
	4) 30 years (1978)	4) 25 years (1983)		
	5) 29 years (1979)	5) 42 years (1956)		
		6) 30 years (1979)		
Original capacity	1) 580 kW	1) 974 kW		
	2) 900 kW	2) 1080 kW		
	3) 605 kW	3) 700 kW		
	4) 800 kW	4) 1,046 kW		
	5) 930 kW	5) 1,512 kW		
	, , , , , , , , , , , , , , , , , , , ,	6) 930 kW		
Replacement technology	All five are HFC-134a, screw	1) HFC-134a, screw		(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-
1,		2) HFC-134a, screw		chiller)
		3) HFC-134a, screw		
		4) HFC-134a, centrifugal		
		5) HFC-134a, screw		
		6) HFC134a, screw		
Replacement capacity	1) 580 kW	1) 1204 kW		[please provide unit = kW or tons]
Tropiasoment supusity	2) 1100 kW	2) 644 kW		[produce provide drift = KVV or terror
	3) 600 kW	3) 1248 kW		
	4) 956 kW	4) 999 kW		
	5) 950 kW	5) 900.1 kW		
	5) 550 KW	6) 604.8 kW		
Assumed / measured change in	1) from COP = 3.2 to COP = 6.1	1) from COP = 3.45 to COP = 4.8		(from/unit to /unit)
energy efficiency	2) from COP = 2.8 to COP = 6.35	2) from COP =3.40 to COP = 5		(monitation family)
chargy emolericy	3) from COP = 3.5 to COP= 6.24	3) from COP =3.43 to COP = 5.91		
	4) from COP = 3.4 to COP = 5.11	4) from COP= 4.3 to COP = 6.05		
	5) from COP = 3.72 to COP=5.04	5) from COP=3.69 to COP = 5.52		
	3) 110111 001 = 3.72 to 001 = 3.04	6) from COP= 3.72 to COP=5.48		
		0) 110111 001 = 3.72 to 00F=3.40		
Assumed annual saving in energy				(in kWh)
Assumed annual saving in energy				(III KVVII)

Project data					
	Regional demonstration project for integrated management of the centrifugal chiller sub-sector in the				
	Caribbean, focusing on application of energy-efficient CFC-free technologies for replacement of CFC-bas				
Title	chillers				
Approved at [ExCom Meeting]	47th				
Country/countries/region covered	Jamaica, Barbade	os, Trinidad and	Tobago and the Dominican Republic		
MLF funding approved			1,000,000		
Minimum co-funding requirement	690.000 US\$				
Source(s) of co-funding as envisaged in project proposal (amount envisioned	Regional GEF MS	SP of 1.000.000	US\$ + 160.000 US\$ UNDP Trust Fund		
Number of chillers to be replaced			14		
Lead agency	UNDP				
MLF funding associated					
Other agencies/bilaterals	Agency 1	Agency 2	Agency		
Name					
Responsibility					
MLF funding associated					

/ assessment (provide some brief text, please; bullet points also p	ossible)
	The Chillers project in the Caribbean has faced several challenges. The project was originally developed the idea that a regional MSP on energy efficiency would serve as co-finance for the project. However, the RAF discussions and many other similar problems meant that the idea was abandoned a long time ago. I have been looking for other co-financing sources. The most promising one was developed by our finance analyst on business models, where he established the criteria for a financial mechanism for the public se in Jamaica, and this had in principle been approved by a financial institution. However, simultaneously to exercise we were trying to make a list of the remaining chillers in Jamaica (one of the four countries). The result of the assessment was that there were only 9 CFC based chillers left in Jamaica, and 7 of them we replaced after the chillers project was approved leaving only two CFC based chillers in the country. This is course not enough to establish a financial mechanism. We have not been able to locate additional chiller. We are therefore in a situation where it is difficult to comply with the original project objective – to develop financial mechanism for chillers replacement. It is also not possible to develop the model under the GEF we will not seek financial assistance from the GEF.  We never managed to identify any CFC based chillers in Barbados and Trinidad and Tobago. We had a lof some chillers in the Dominican Republic. Last time we went there we tried to visit the buildings, but the were no CFC chillers left. The maintenance workers told us that they had been replaced a long time ago.
General experience	project will focus on co-financing replacement of remaining CFC based chillers, and provide additional technical support and training in the countries to support chillers replacements.
'	To locate CFC based centriful chillers in the countries
Greatest challenges Lessons learned	To locate CFC based centified chillers in the countries
Remarks on interest by chiller owners	Public Sector in Jamaica very interested in the project. Jamaica has been the most pro-active player in the project.
Expected results beyond chillers funded: (e.g.: Will the demonstration lead to more chillers being replaced, if yes how concrete is that understanding? If no why is that assumed?)	
Reasons for delays	The implementation of the RAF in the GEF made it very difficult for UNDP to prepare the regional MSP a submit it to the GEF SEC. An alternative finance strategy was developed by our finance analyst. However most of the chillers had already been replaced when the strategy was developed
Experience with funding organisations	The GEF SEC has a different project cycle than the MLF, and it is not always easy combine the two fundi sources - this is especially the case in multi country projects. This is further complicated for countries that does
Impact on the chiller market in the relevant country/countries; market transformation observed	Most of the market transformation already took place. Public sector, especially in Jamaica, seems to be ti sector with the most difficulties.
Other remarks and/or explanations	

Co-funding information				
Per approved co-funding	1st co-funding	2nd co-funding	co-funding	Refers to all co-financing that materialised
Co-funding institution		UNDP Energy TTF	Jamaica	<u> </u>
		Regional Caribbean demonstration project on application of CFC-free energy	Replacement of chillers in Public and	
Name, purpose of programme		efficient technologies for replacement of CFC-based centrifugal chillers.	Private Sector	
	1			
Amount approved in total (currency)	ļ	160,000	not quantified	
Was this co-funding foreseen in the original submission to the				
47th/48th Meeting?		yes	no	yes/no
If yes: Did the amount change (please provide from to)		No		
If no: When (approx.) did you become aware of this possibility, and				Explain briefly: 2, 3 sentences (separate below) or
how? Please explain briefly		This was foreseen in the original proposal	High energy prices promoted the process	some bullet points
, ,			0 0,1 1	·
How much of the cofinancing constitutes project costs in the MLF	1			
definition (see letter from MFS)		Most of it	All of it.	
Date of approval	<b>+</b>		2006 - 2008	
Date of approval			2006 - 2006	
		To support the implementation of the chillers programme. It is complimentary to		
		another project funded by the UNDP TTF on Energy Efficiency in Public		e.g. for replacing chillers in hospitals in country x; for
Major conditions associated		Buildings in Jamaica that was approved before 2006.	no specific conditions	replacing one system in institution y;
Additional activities covered (if any): (E.g.: Energy efficiency program		''		i
for building,)		see above		
	1		<u> </u>	
Funds agreed by the MES to be released based on that conserval			,	$\mathbf{J}$
Funds agreed by the MFS to be released based on that approval Date of related release of Funds by the MFS	<b> </b>	· ·	'	/
Date of related release of Funds by the MFS				
Per co-funding presently sought	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution				
Name, purpose of programme				
Amount sought in total	İ			
How much of that constitutes project costs in the MLF definition				
Expected approval	1			1
Reasons for the delay	<del> </del>			
	1			
Major conditions associated	ļ			
Additional activities covered (if any): (E.g.: Energy efficiency program				
for building,)				
Co-funding sources previously pursued but subsequently abandoned	1st co-funding	2nd co-funding	co-funding	Explanations
Co-funding institution	GEF		· · · ·	·
	Regional Energy			
	Efficiency			
Name, purpose of programme	Programme			
			-	
Amount sought in total	1000000			
How much of that constitutes project costs in the MLF definition	Most of it.			
	The idea of			
	presenting a			
	proposal to the GEF			
	was abandoned			
When was the quest for co-funding from this institution/programme	when the RAF was			
abandoned?	implemented.		-	
	L			
	To coordinate a four			
	country regional			
	MSP country with			1
	mor country man			
Reasons for the decision	RAF is quite			
	RAF is quite			
	RAF is quite			
	RAF is quite complicated			
Additional external resources acquired for the chiller phase-out	RAF is quite	2nd co-funding	co-funding	Explanations
Co-funding institution	RAF is quite complicated	2nd co-funding	co-funding	Explanations
Co-funding institution Name, purpose of programme	RAF is quite complicated	2nd co-funding	co-funding	Explanations
Co-funding institution	RAF is quite complicated	2nd co-funding	co-funding	Explanations
Co-funding institution Name, purpose of programme Amount sought in total	RAF is quite complicated	2nd co-funding	co-funding	Explanations
Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition	RAF is quite complicated	2nd co-funding	co-funding	Explanations
Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition When was the quest for co-funding from this institution/programme	RAF is quite complicated	2nd co-funding	co-funding	Explanations
Co-funding institution Name, purpose of programme Amount sought in total How much of that constitutes project costs in the MLF definition	RAF is quite complicated	2nd co-funding	co-funding	Explanations

General information		Explanations
identified in the country	locations identified during project preparation, but all had been replaced. Trinidad and Tobago: No CFC based centrifugal chillers have been identified. Jamaica: We have located 9 CFC based centrifugal chillers of which 7 were replaced in 2006 and 2007.	We have only found CFC based chillers in Jamaica (9) and 7 had been substituted at the time we did the survey. Jamaica has not imported CFCs since 2006 and we doubt that additional chillers can be found there. In neither of the four countries we have found CFC based chillers when we
What share of the country's chiller users have been identified (estimated)	not been possible to locate them so far.	We believe that only a very limited number of CFC based chillers would still be in the countries. We have not been able to locate additional chillers.
or lending? If yes, please elaborate briefly	UNDP developed with funds from the Thematic Trust Fund on Energy the principles of a finance scheme for Chillers replacement. The scheme was discussed with stakeholders and 3 potential banks (all showed interest in the scheme). However, the low quantity of chillers to be replaced made if impossible to reach a critical mass, and it would therefore not be cost efficient to implement the scheme in Jamaica.	

r (main) activity	Activity 1	Activity 2	Activity 3	Activity	Explanations
Type of activity	Development of financial Scheme	Identification of CFC based chillers	Replacement of 7 chillers	Potential replacement of 2 chillers	e.g.: Chiller replacement / Chiller retrofit / Workshop /
Country	Jamaica				
Status	quantity of chillers made it	9 chillers in 7 locations identified in Jamaica. Seven have been replaced. No CFC based chillers found in Dominican Republic and Trinidad and Tobago.	Seven chillers replaced in Jamaica		Completed, new chiller fully functional/largely completed, new chiller delivered and in the process of installation and trial/partially completed, new chiller delivery expected / Tendering complete and contract issued / Tender process ongoing / Preparation of tender process // Workshop planned / Workshop held (when?) / Results published (when? Please provide copy)
case of chiller replacements					
Owner, use			The seven Chillers were located in the following locations: Sangster International Airport, Starfish Hotel, Bank of Jamaica, Airport Authority of Jamaica, and Jamaica Pegasus Hotel.		The Ministry of Health main building in Kingston, Jamaica has two CFC based chillers. We have no additional information on these chillers.
When was the agreement with the owner concluded					
(Expected) Status of completion			Completed		
Actual cost with a break down by				•	
equipment			Funded by company		
installation			Funded by company		
construction			Funded by company		
Information on energy efficiency					
Original technology			N/A		
Age of chiller being replaced			N/A		
Original capacity			N/A		
Replacement technology			All chillers replaced with 134 a chillers from Carrier, York and Trane.		(refrigerant AND type, e.g. turbo-chiller, screw-chiller, absorption-chiller)
Replacement capacity	1				[please provide unit = kW or tons]
Assumed / measured change in					(from/unit to /unit)
energy efficiency					